

ITEM - JOINT AND CRACK REPAIR (PCCP)

The work under this Item shall consist of renovating longitudinal and transverse joints in the existing Portland Cement Concrete Pavement and routing and sealing random cracks as specified in Section 402 of the Standard Specifications.

The estimated quantity of the joints and random cracks requiring renovation and sealing are listed below:

Milepost	Direction	Description	Lineal feet of Renovation

The random cracks to be renovated and sealed will be determined in the field by the Engineer; the estimated quantity is based on visual observations made in *, *. The exact quantity may vary from this estimate.

DESIGNER:

Lineal footage of cracks to be repaired shall be determined during field review.

* Add the Month and Year the visual observtions were made.