

ITEM - PAVEMENT GRINDING (PCCP)

The work under this Item consists of grinding the surface of the existing concrete pavement at the locations shown on the plans and as specified in Section 402 of the Standard Specifications.

The pavement to be ground has been in-place for approximately _ years and was formulated from _ inch maximum size aggregate having a Los Angeles abrasion of approximately _ at 500 revolutions.

The estimated quantity of pavement to be ground is _ square yards. The exact quantity may vary from this estimate.

DESIGNER:

Existing PCCP maximum size aggregate is typically 2 1/2 inches.