

ITEM - PAVEMENT GROOVING (PCCP)

The work under this Item consists of grooving the surface of the existing concrete pavement at the locations shown on the plans and as specified in Section 402 of the Standard Specifications.

The pavement to be grooved has been in-place for approximately _ years and was formulated from _ inch maximum size aggregate having a Los Angeles abrasion of approximately _ at 500 revolutions.

The estimated quantity of grooving on this project is _ square yards. The exact quantity may vary from this estimate.

DESIGNER:

The existing PCCP maximum size aggregate is typically 2 1/2 inchs.