


STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
CONSTRUCTION

JULY



1994

10/95

Also

DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

October, 1995

TO: All Users of Construction Standards

FROM: Terry H. Otterness, Design Program Manager, Roadway Engineering Group

SUBJECT: Revisions to Construction Standards - English Version

Several changes are being made to Construction Standard Drawings and the Construction Standards Index.

Most of the changes consist of miscellaneous items found during the final development of the Metric Construction Standards. Generally, the revisions consist of minor corrections and a few major items. These include: revising gutter depression depths, eliminating Type A curb and gutter, clarifying gutter depression versus inlet depression at catch basins, revising reinforcing steel clearances and dimensions, and clarifying manhole frames and covers to match what vendors can supply.

There are two new standards involving concrete half barrier and transition, C-10.62 and C-10.71. Standard C-10.22 has a new second sheet that is a timber post alternate for the freeway guard rail.

One standard has been deleted: C-06.20 - Detour Geometrics.

TO: All Users of Construction Standards

FROM: Mr. Terry H. Otterness, Design Program Manager, Roadway Engineering Group  
Mr. August V. Hardt, Assistant State Engineer, District Operations Group, Administration

SUBJECT: Revisions to Construction Standards

Several changes are being made to existing Construction Standard Drawings and the Construction Standards Index.

All Construction Standard Drawings are now converted to CADD. Fifty standards are being reissued without revisions; some have been rearranged. Several other standards are being revised or are new standards.

Major changes include: a reorganization of the C-10 Series, replacing the BCT with a guard rail extruder terminal (GET), which is based on the ET-2000, combining slip form and fixed form for cast in place concrete barrier into one standard with continuous reinforcing, adding a standard for superelevation distribution, adding curb and gutter transitions, consolidating sidewalk details to C-05.20, clarifying contraction joint spacing for curb and gutter and sidewalk, adding a standard for crossroad PCCP joints, splitting C-10.98 and C-10.99 into several new standards based on pay items, adding a new standard for side slope median catch basin, clarifying pipe culvert installation details, detailing storm drain outlet gates, and clarifying median catch basin details.

A complete listing of the revised and new Standards and the various revisions is as follows:

<b><u>REVISED DRAWING</u></b>	<b><u>REVISION</u></b>
C-02.50 Superelevation Distribution	New standard. A reproduction of the diagrams in Plan No. D-56.40 of the 1986 Roadway Guides.
C-04.10 Spillway, Embankment	Clarified the terminus of the embankment curb to extend 2 feet beyond the guard rail post to decrease erosion around the post.

## **REVISED DRAWING**

## **REVISION**

C-04.20 Downdrain, Embankment	Clarified the terminus of the embankment curb to extend 2 feet beyond the guard rail post to decrease erosion around the post.
C-05.10 Single Curb, Curb & Gutter, Embankment Curb	Added expansion joint detail.
C-05.11 Ramp Curb and Gutter Layout	Separated the entrance ramp layout (sheet 1) from the exit ramp (new sheet 2). Moved the curb and gutter transition to Std C-05.12. Moved sidewalk details to Std C-05.20.
C-05.12 Curb and Gutter Transitions	Changed the transition types from letters (A,B...) to numbers (1,2...). Added note regarding length of entrance ramp. Revised note 1. Added perspective view for Type 3 transition. Added Type 4 transition from old Std C-05.11. Added Type 5 and Type 6 transitions.
C-05.20 Concrete Driveways and Sidewalks	Revised note 2 regarding referencing the contraction joint detail on sheet 2. Added section B-B for driveways with sidewalk separated from the curb. On sheet 2, added information regarding contraction joint spacing, scoring line spacing and contraction joint details. Revised detail and section for driveway with adjacent sidewalk to provide 3' wide sidewalk with 1% cross slope, as per ADA regulations.
C-05.30 Sidewalk Ramps (sheets 2 & 4 only)	Corrected note 4.
C-06.10 Driveway & Turnout Layouts	Revised the driveways in the plan and section to match the revised driveway standard with the 3 foot wide strip along the back.

**REVISED DRAWING**

**REVISION**

C-06.20 Geometrics, Detour

Added note in upper right quadrant to use Detour 'B'.  
Corrected "typo" from "34' or under" to "34' or wider".

C-07.10 Crossroad PCCP Joints

New standard.

C-08.10 Ramp Geometrics

Revised curve callout to see plans.

C-10.01 Type A Guard Rail Installation

Combined the sections since the only difference is the use of embankment curb.  
Clarified note and revised drawing regarding guard rail extending beyond the embankment curb.  
Added a note referring to C-10.03 for measurement limits.  
Revised reference of BCT to a reference to a generic end treatment.  
Added a note to see the Standard Specifications for reflector tab spacing.

C-10.02 Type B Guard Rail Installation

Combined the sections since the only difference is the use of embankment curb.  
Clarified note and revised drawing regarding guard rail extending beyond the embankment curb.  
Added a note referring to C-10.03 for measurement limits.  
Revised reference of BCT to a reference to a generic end treatment.  
Added a note to see Standard Specifications for reflector tab spacing.

C-10.03 Measurement Limits for  
W Beam System

Rearranged standard into two sheets and added departures.  
Changed buried anchor to nested W Beam, Std C-10.28.  
Changed BCT to new GET.  
Added approach and departure transitions to bridges.  
Changed measurement of Concrete Half Barrier Transitions from Lin. Ft. to Each.  
Deleted the median barrier transition.  
Added departure for thrie beam bridge retrofit.

**REVISED DRAWING**

**REVISION**

C-10.06 Half Barrier Terminal w/ Type B or C Curb & Gutter	New standard. Shows installation details for half barrier with a new GET.
C-10.15 Barrier Details at Piers	New standard from old Std C-10.20. Revised to show only installation details with barrier moved to new Std C-10.64.
C-10.20 G4(1W) and G4(2W) Blocked Out W Beam (Timber Post)	New standard from old Std C-10.04. No changes.
C-10.21 G4(1S) and G4(2S) Blocked Out W Beam (Steel Post)	New standard from old Std C-10.05. No changes.
C-10.22 G4(1S-Modified) Blocked Out W Beam (Steel Post) with Special Curb & Gutter	New standard from old Std C-10.06. Added reference to Curb and Gutter in Section. Revised callout for Curb and Gutter. Added note limiting height of curb to 4 inches.
C-10.23 G9(A) and G9(B) Blocked Out Thrie Beam (Steel Post)	New standard from old Std C-10.07. No changes.
C-10.24 G9(C) Blocked Out Thrie Beam (Steel Post)	New standard from old Std C-10.08. No changes.
C-10.28 Nested Steel W Beam Short Span Type 1 and 2 (sheet 1 only)	Moved and revised section A-A to improve understanding that nested rail is additional W Beam to the regular guard rail.
C-10.40 Guard Rail Extruder Terminal GET-1	New standard to be used on non-curb conditions. Includes installation details for use with Type A and B guard rail.
C-10.41 Guard Rail Extruder Terminal GET-2	New standard to be used on curbed conditions. Includes installation details for use with Type A and B guard rail.

**REVISED DRAWING**

**REVISION**

C-10.44 Hardware for Guard Rail Extruder Terminal	New standard.
C-10.45 Guardrail Anchor Assembly Steel Terminal Post	New standard from old Std C-10.21. Added note referring to measurement limits on Std C-10.03. Removed references to BCT.
C-10.60 Half Barrier, Cast in Place Slip Form & Fixed Form	New standard from old Std C-10.09. Changed to both slip form and fixed form. Widened base to offset the B joint 2 inches away from the face of the barrier. Added detail for barrier with 2'-6" wide gutter. Revised joint to a type B joint with rebar.
C-10.61 Half Barrier, Precast	New standard from old Std C-10.11. Added General Notes and rebar details.
C-10.64 Half Barrier (At Piers)	New standard from portion of old Std C-10.20. Can be cast-in-place with continuous reinforcing or precast in sections.
C-10.65 Half Barrier with Sidewalk	New standard regarding the "special concrete barrier" from old Std C-10.99.
C-10.66 Median Barrier, Cast in Place Slip Form & Fixed Form	New standard from old Std C-10.12. Changed to both slip form and fixed form.
C-10.68 Median Barrier, Precast	New standard from old Std C-10.14. Added rebar detail.

**REVISED DRAWING**

**REVISION**

C-10.75 Barrier Transition-Tangent  
Departure

New standard from old Std C-10.98.  
All transitions this standard are for departure condition.  
Changed Type A to Type 1 and Type B to Type 2.  
Shortened length of Type 2 from 30' to 20'.  
Added new Type 3 transition, which is a 20' long transition from half barrier to  
freeway curb and without sidewalk.

C-10.76 Barrier Transition-Curve

New standard from old Std C-10.99 and shows only the transition.  
Revised the elevation of the sidewalk to match that of the gutter.  
Shows limits of the barrier gutter transition.

C-11.10 Roadway Cattle Guard

Added details for the angle assemblies.  
Incorporated elements from Stds C-11.11 & C-11.12.  
Deleted note referring to Stds C-11.11 & C-11.12.  
Added note describing Angle Assembly Detail No. 2.

C-11.20 Cattle Guard, Drainage

Revised note that the transition of the C-04.10 spillway shall be symmetrical about  
the subgrade/slope hinge point.

C-12.10 Fence, Woven Wire

Added ASTM design numbers to the fence fabric dimensions.

C-13.10 Pipe Culvert Installations

Revised reference in note from C-14.00 to B-11.11 and B-11.14.  
Revised note 3 so that dimensions W and E are for all conditions.  
Added note that defines the minimum cover to be 12 inches.  
Added note and detail that defines pipe berm requirements.  
Added note that plating of slopes at pipe locations are similar for pipes without  
end sections and for multiple pipe installations.  
Revised and expanded table for multiple pipe installations.  
Moved several details to new sheet 2.  
Removed two dimensions from the perforated CMP detail.  
Added a detail and note for multiple end sections.



**REVISED DRAWING**

**REVISION**

C-13.15 Typical Pipe Installation	Added new note defining the construction requirements for non-trench condition. Added dimensional note in the non-trench condition detail showing minimum width for pipe stability for trench and non-trench condition.
C-13.60 Slotted Drain Details	Changed welding of bearing bars to pipe to a continuous weld as per Std Specs.
C-13.75 Storm Drain Outlet Details	Added a table showing dimensions for gates for various sizes of pipes. Deleted note with duplicate information shown in the anchor bolt detail. Deleted note to see plans for access barrier gate dimension schedule. Added note to space the barrier bars evenly. Added note on hinge pin material and installation. Added overall width dimension of the hinge. Deleted three notes about the outlet collar that are in Std C-13.80. Deleted drainage outlet detail.
C-13.80 Pipe Collar Details	Revised clear cover dimension in general note 3 from 2" to 3" to match drawings. Added drainage outlet detail from Std C-13.75.
C-15.10 Catch Basin, Type 1	Added location reference point.
C-15.20 Catch Basin, Type 3	Added location reference point.
C-15.30 Catch Basin, Type 4	Added note identifying stove bolts and added location reference point.
C-15.40 Catch Basin, Type 5	Added location reference point.

**REVISED DRAWING**

**REVISION**

C-15.70 Catch Basin Miscellaneous Details	<p>Added note indicating maximum gutter depression of 3 inches.</p> <p>Added note regarding distance for full depression along curb.</p> <p>Added note regarding non-use of apron on this standard with C-15.80.</p> <p>Revised length of gutter depression transition from 3 feet minimum to 3 feet.</p>
C-15.75 Catch Basin, Drop Inlet	<p>New standard from old Std C-14.30.</p>
C-15.80 Catch Basin, Median, Flush	<p>Revised the perspective view, concentrating on the apron.</p> <p>Revised back slope of apron on median dike to 10:1.</p> <p>Revised fore slope of apron from 6:1 to match profile of median.</p> <p>Added note to see plans for the grate elevation of the catch basin.</p> <p>Added note that states that the top elevation of the back portion of the apron is controlled by the sides of the apron.</p> <p>Added a median ditch grade detail.</p> <p>Revised the 'H' dimension to reflect the inside catch basin wall height.</p> <p>Added a variable dimension for the back portion of the apron, which reflects the fact that the back slope is fixed at 10:1 and the side slopes are variable.</p> <p>Added note indicating location on catch basin for station referencing.</p>
C-15.81 Catch Basin, Median, Side Slope	<p>New standard for use on narrow medians where the roadways are superelevated.</p>
C-15.90 Catch Basin, Median Dike, Precast	<p>Added location reference point.</p>
C-15.91 Freeway Catch Basin Details	<p>Revised location of location reference point to lip of gutter.</p> <p>Moved frame and grate details to sheet 2.</p>
C-16.40 Irrigation Sleeves	<p>Added note 6 defining material to be used for caps or plugs is to be recommended by pipe supplier and approved by the Engineer.</p>

**REVISED DRAWING**

**REVISION**

C-17.10 Bank Protection, Rail Types 1,2,3	Added callouts in perspective view for single and double wrapped wire ties. Modified table, eliminating the embankment slope rate.
C-18.10 Manhole Details	Revised general note 4. Changed from Std C-07.30, which does not exist, to Std C-18.30. Also changed note to reference C-18.30 for other information. Added note to see Std C-18.40 for location reference point. Added note that defines height of manhole.
C-19.10 Ford - Concrete Walls	Changed callout in elevation view from "Upstream" to "Downstream". Added joint detail.
C-22.15 Sanitary Sewer Encasement	Rearranged general note 4.
C-22.20 Pipe Support Across Trenches	Revised rebar in Type B from two bars to one bar.
C-23.30 Valve Box Installation	Moved three notes from sheets 2 and 3 to sheet 1.
C-23.55 Waterline Cut and Plug for 12" Diameter Main and Smaller	Removed note about dry blocks being shimmed.

The following existing Construction Standard Drawings are being deleted.

**DELETED DRAWINGS**

C-02.40 Pavement Crown, Parabolic (Rev. 1/83)

C-10.04 G4(1W) and G4(2W) Blocked Out W Beam (Timber Post) (Rev. 7/85)

C-10.05 G4(1S) and G4(2S) Blocked Out W Beam (Steel Post) (Rev. 7/85)

C-10.06 G4(1S-Modified) Blocked Out W Beam (Steel Post) with Special Curb and Gutter (Rev. 7/85)

C-10.07 G9(A) and G9(B) Blocked Out Thrie Beam (Steel Post) (Rev. 7/85)

C-10.08 G9(C) Blocked Out Thrie Beam (Steel Post) (Rev. 7/85)

C-10.09 Half Barrier, Cast in Place, Slip Form (Rev. 10/89)

C-10.10 Half Barrier, Cast in Place, Fixed Form (Rev. 11/83)

C-10.11 Half Barrier, Precast (Rev. 1/83)

C-10.12 Median Barrier, Cast in Place, Slip Form (Rev. 1/93)

C-10.13 Median Barrier, Cast in Place, Fixed Form (Rev. 1/91)

C-10.14 Median Barrier, Precast (Rev. 1/91)

C-10.15 Flared Breakaway Cable Terminal Assembly (Timber Post) (Rev. 7/85)

C-10.16 Flared Breakaway Cable Terminal Assembly (Steel Post) (Rev. 7/85)

C-10.17 BCT Assembly, Steel (Rev. 3/87)

C-10.18 BCT Assembly, Timber (Rev. 10/87)

C-10.19 Guardrail Assembly (Rev. 10/89)

C-10.20 Barrier Details at Piers (Rev. 10/89)

C-10.21 Guardrail Anchor Assembly, Steel Terminal Post (Rev. 3/87)

C-10.22 Guardrail Anchor Assembly, Timber Terminal Post (Rev. 6/86)

C-10.98 Barrier Transition - Tangent (Rev. 10/89)

C-10.99 Barrier Transition, Curve (Rev. 10/89)

C-11.11 Roadway Cattle Guard - Grill & Grill Clamp Detail (Rev. 1/83)

C-11.12 Roadway Cattle Guard - Footing Type, Misc. Details (Rev. 1/83)

C-14.30 Headwall, Drop Inlet (Rev. 1/83)

# CONSTRUCTION STANDARD - INDEX

DRAWING NO.	TITLE	DRAWING NO.	TITLE
C-01.10	SYMBOL LEGEND	C-10.01	TYPE A GUARD RAIL INSTALLATION, REFLECTOR TAB
C-01.11	SYMBOL LEGEND	C-10.02	TYPE B GUARD RAIL INSTALLATION, REFLECTOR TAB
C-01.12	SYMBOL LEGEND	C-10.03	MEASUREMENT LIMITS FOR W BEAM AND THRIE BEAM SYSTEM (2 SHEETS)
C-01.13	SYMBOL LEGEND	C-10.06	HALF BARRIER TERMINAL W/TYPE B OR C CURB & GUTTER
C-01.30	GENERAL ABBREVIATIONS	C-10.15	BARRIER DETAILS AT PIERS
C-01.31	GENERAL ABBREVIATIONS	C-10.20	G4(1W) AND G4(2W) BLOCKED OUT W BEAM (TIMBER POST)
C-01.32	GENERAL ABBREVIATIONS	C-10.21	G4(1S) AND G4(2S) BLOCKED OUT W BEAM (STEEL POST)
		C-10.22	G4(MODIFIED) BLOCKED OUT W BEAM WITH SPECIAL CURB AND CUTTER (2 SHEETS)
C-02.10	SLOPES, INTERSTATE	C-10.23	G9(A) AND G9(B) BLOCKED OUT THRIE BEAM (STEEL POST)
C-02.20	SLOPES, PRIMARY ROADWAYS	C-10.24	G9(C) BLOCKED OUT THRIE BEAM (STEEL POST)
C-02.30	SLOPES, SECONDARY/MISC ROADWAYS	C-10.28	NESTED STEEL W BEAM (2 SHEETS)
C-02.50	SUPERELEVATION DISTRIBUTION	C-10.29	BOLTED ANCHOR GUARD RAIL (2 SHEETS)
C-03.10	DITCHES, CHANNELS, DIKES AND BERMS (5 SHEETS)	C-10.30	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (APPROACH) (3 SHEETS)
		C-10.31	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (APPROACH) (WITH CURB) (3 SHEETS)
C-04.10	SPILLWAY, EMBANKMENT	C-10.32	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (DEPARTURE) (3 SHEETS)
C-04.20	DOWNDRAIN, EMBANKMENT	C-10.39	HARDWARE FOR W BEAM TRANSITION TO CONCRETE BARRIER
C-04.30	SPILLWAY LENGTH TABLE	C-10.40	GUARD RAIL EXTRUDER TERMINAL, GET-1 (2 SHEETS)
C-04.40	DOWNDRAIN LENGTH TABLE	C-10.41	GUARD RAIL EXTRUDER TERMINAL, GET-2 (2 SHEETS)
C-04.50	DOWNDRAIN ENERGY DISSIPATOR	C-10.44	HARDWARE FOR GUARD RAIL EXTRUDER TERMINAL (3 SHEETS)
		C-10.45	GUARD RAIL ANCHOR ASSEMBLY STEEL TERMINAL POST
C-05.10	SINGLE CURB, CURB & GUTTER EMBANKMENT CURB	C-10.60	HALF BARRIER, CAST IN PLACE, SLIP FORM & FIXED FORM
C-05.11	RAMP CURB & GUTTER LAYOUT (2 SHEETS)	C-10.61	HALF BARRIER, PRECAST
C-05.12	CURB & GUTTER TRANSITIONS (3 SHEETS)	C-10.62	CONCRETE HALF BARRIER WITH GUTTER
C-05.20	CONCRETE DRIVEWAYS & SIDEWALKS (2 SHEETS)	C-10.64	HALF BARRIER (AT PIERS) (2 SHEETS)
C-05.30	SIDEWALK RAMP (4 SHEETS)	C-10.65	HALF BARRIER WITH SIDEWALK
C-05.40	MEDIAN PAVING AND NOSE TRANSITION	C-10.66	MEDIAN BARRIER, CAST IN PLACE, SLIP FORM & FIXED FORM
C-05.50	CONCRETE BUS BAY	C-10.68	MEDIAN BARRIER, PRECAST
		C-10.70	CONCRETE HALF BARRIER TRANSITION (4 SHEETS)
C-06.10	DRIVEWAY & TURNOUT LAYOUTS (2 SHEETS)	C-10.71	CONCRETE HALF BARRIER TRANSITION (3 SHEETS)
C-07.01	PCCP JOINTS (2 SHEETS)	C-10.74	HARDWARE FOR CONCRETE BARRIER TRANSITIONS
C-07.02	LOAD TRANSFER DOWEL ASSEMBLY	C-10.75	BARRIER TRANSITION-TANGENT-DEPARTURE TYPES 1, 2, AND 3 (3 SHEETS)
C-07.03	MAINLINE PCCP JOINT LOCATIONS (8 SHEETS)	C-10.76	BARRIER TRANSITION-CURVE
C-07.04	ENTRANCE RAMP PCCP JOINTS	C-10.80	RUB RAIL (2 SHEETS)
C-07.05	EXIT RAMP PCCP JOINTS	C-10.83	HARDWARE FOR RUB RAIL
C-07.06	TRENCH BACKFILL AND PAVEMENT REPLACEMENT	C-10.97	GLARE SCREEN, CONCRETE MEDIAN BARRIER (3 SHEETS)
C-07.10	CROSSROAD PCCP JOINTS	C-11.10	ROADWAY CATTLE GUARD (3 SHEETS)
		C-11.20	CATTLE GUARD, DRAINAGE
C-08.10	RAMP GEOMETRICS	C-11.30	CATTLE GUARD, RAILROAD
C-08.20	PAVED GORE AREA		
C-09.10	GROOVING FOR BITUMINOUS SHOULDERS	C-12.10	FENCE, WOVEN AND BARBED WIRE WITH GATES (5 SHEETS)
		C-12.20	FENCE, CHAIN LINK TYPES 1 AND 2 WITH GATES (3 SHEETS)
		C-12.30	CHAIN LINK CABLE BARRIER (3 SHEETS)

# CONSTRUCTION STANDARD - INDEX

DRAWING NO.	TITLE	DRAWING NO.	TITLE
C-01.10	SYMBOL LEGEND	C-10.01	TYPE A GUARD RAIL INSTALLATION, REFLECTOR TAB
C-01.11	SYMBOL LEGEND	C-10.02	TYPE B GUARD RAIL INSTALLATION, REFLECTOR TAB
C-01.12	SYMBOL LEGEND	C-10.03	MEASUREMENT LIMITS FOR W BEAM AND THRIE BEAM SYSTEM (2 SHEETS)
C-01.13	SYMBOL LEGEND	C-10.06	HALF BARRIER TERMINAL W/TYPE B OR C CURB & GUTTER
C-01.30	GENERAL ABBREVIATIONS	C-10.15	BARRIER DETAILS AT PIERS
C-01.31	GENERAL ABBREVIATIONS	C-10.20	G4(1W) AND G4(2W) BLOCKED OUT W BEAM (TIMBER POST)
C-01.32	GENERAL ABBREVIATIONS	C-10.21	G4(1S) AND G4(2S) BLOCKED OUT W BEAM (STEEL POST)
C-02.10	SLOPES, INTERSTATE	C-10.22	G4(1S-MODIFIED) BLOCKED OUT W BEAM (STEEL POST) WITH SPECIAL CURB AND GUTTER
C-02.20	SLOPES, PRIMARY ROADWAYS	C-10.23	G9(A) AND G9(B) BLOCKED OUT THRIE BEAM (STEEL POST)
C-02.30	SLOPES, SECONDARY/MISC ROADWAYS	C-10.24	G9(C) BLOCKED OUT THRIE BEAM (STEEL POST)
C-02.50	SUPERELEVATION DISTRIBUTION	C-10.28	NESTED STEEL W BEAM (2 SHEETS)
C-03.10	DITCHES, CHANNELS, DIKES AND BERMS (5 SHEETS)	C-10.29	BOLTED ANCHOR GUARD RAIL (2 SHEETS)
C-04.10	SPILLWAY, EMBANKMENT	C-10.30	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (APPROACH) (3 SHEETS)
C-04.20	DOWNDRAIN, EMBANKMENT	C-10.31	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (APPROACH) (WITH CURB) (3 SHEETS)
C-04.30	SPILLWAY, EMBANKMENT LENGTH TABLE	C-10.32	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (DEPARTURE) (3 SHEETS)
C-04.40	DOWNDRAIN, EMBANKMENT LENGTH TABLE	C-10.39	HARDWARE FOR W BEAM TRANSITION TO CONCRETE BARRIER
C-04.50	DOWNDRAIN ENERGY DISSIPATOR	C-10.40	GUARD RAIL EXTRUDER TERMINAL, GET-1 (2 SHEETS)
C-05.10	SINGLE CURB, CURB & GUTTER EMBANKMENT CURB	C-10.41	GUARD RAIL EXTRUDER TERMINAL, GET-2 (2 SHEETS)
C-05.11	RAMP CURB & GUTTER LAYOUT (2 SHEETS)	C-10.44	HARDWARE FOR GUARD RAIL EXTRUDER TERMINAL (3 SHEETS)
C-05.12	CURB & GUTTER TRANSITIONS (3 SHEETS)	C-10.45	GUARD RAIL ANCHOR ASSEMBLY STEEL TERMINAL POST
C-05.20	CONCRETE DRIVEWAYS & SIDEWALKS (2 SHEETS)	C-10.60	HALF BARRIER, CAST IN PLACE, SLIP FORM & FIXED FORM
C-05.30	SIDEWALK RAMP (4 SHEETS)	C-10.61	HALF BARRIER, PRECAST
C-05.40	MEDIAN PAVING AND NOSE TRANSITION	C-10.64	HALF BARRIER (AT PIERS) (2 SHEETS)
C-05.50	CONCRETE BUS BAY	C-10.65	HALF BARRIER WITH SIDEWALK
C-06.10	DRIVEWAY & TURNOUT LAYOUTS (2 SHEETS)	C-10.66	MEDIAN BARRIER, CAST IN PLACE, SLIP FORM & FIXED FORM
C-06.20	GEOMETRICS, DETOUR	C-10.68	MEDIAN BARRIER, PRECAST
C-07.01	PCCP JOINTS (2 SHEETS)	C-10.70	CONCRETE HALF BARRIER TRANSITION (4 SHEETS)
C-07.02	LOAD TRANSFER DOWEL ASSEMBLY	C-10.74	HARDWARE FOR CONCRETE BARRIER TRANSITIONS
C-07.03	MAINLINE PCCP JOINT LOCATIONS (8 SHEETS)	C-10.75	BARRIER TRANSITION-TANGENT-DEPARTURE TYPES 1, 2, AND 3 (3 SHEETS)
C-07.04	ENTRANCE RAMP PCCP JOINTS	C-10.76	BARRIER TRANSITION-CURVE
C-07.05	EXIT RAMP PCCP JOINTS	C-10.80	RUB RAIL (2 SHEETS)
C-07.06	TRENCH BACKFILL AND PAVEMENT REPLACEMENT	C-10.83	HARDWARE FOR RUB RAIL
C-07.10	CROSSROAD PCCP JOINTS	C-10.97	GLARE SCREEN, CONCRETE MEDIAN BARRIER (3 SHEETS)
C-08.10	RAMP GEOMETRICS	C-11.10	ROADWAY CATTLE GUARD (3 SHEETS)
C-08.20	PAVED GORE AREA	C-11.20	CATTLE GUARD, DRAINAGE
C-09.10	GROOVING FOR BITUMINOUS SHOULDERS	C-11.30	CATTLE GUARD, RAILROAD
		C-12.10	FENCE, WOVEN AND BARBED WIRE WITH GATES (5 SHEETS)
		C-12.20	FFNCF, CHAIN LINK TYPES 1 AND 2 WITH GATES (3 SHEETS)
		C-12.30	CHAIN LINK CABLE BARRIER (3 SHEETS)

# CONSTRUCTION STANDARD - INDEX

DRAWING NO.	TITLE	DRAWING NO.	TITLE
C-13.10	PIPE CULVERT INSTALLATION (2 SHEETS)	C-18.10	MANHOLE DETAILS
C-13.15	TYPICAL PIPE INSTALLATION	C-18.20	MANHOLE FRAME & COVER DETAILS
C-13.20	PIPE, REINFORCED CONCRETE END SECTION	C-18.30	MISCELLANEOUS MANHOLE DETAILS
C-13.25	PIPE, CORRUGATED METAL, END SECTION	C-18.40	MANHOLE RISER DETAILS
C-13.30	PIPE & PIPE ARCH, CORRUGATED METAL CONCRETE INVERT PAVING	C-19.10	FORD - CONCRETE WALLS
C-13.55	PIPE, CATTLE-VEHICLE PASS, MITERED END TREATMENT	C-19.20	FORDS - TYPES 1 & 2
C-13.60	SLOTTED DRAIN DETAILS	C-21.10	SURVEY MONUMENT, FRAME AND COVER, RIGHT OF WAY MARKER
C-13.65	SLOTTED DRAIN INSTALLATION DETAILS	C-21.20	STANDARD MARKER
C-13.70	STORM DRAIN CONNECTION DETAILS	C-22.10	UTILITY LINE, PROTECTIVE CONCRETE SLAB
C-13.75	STORM DRAIN OUTLET DETAILS (2 SHEETS)	C-22.15	SANITARY SEWER ENCASEMENT
C-13.80	PIPE COLLAR DETAILS	C-22.20	PIPE SUPPORT ACROSS TRENCHES (3 SHEETS)
C-15.10	CATCH BASIN, TYPE 1	C-22.25	PRECAST SANITARY SEWER MANHOLES
C-15.20	CATCH BASIN, TYPE 3	C-22.30	STUB OUT AND PLUG
C-15.30	CATCH BASIN, TYPE 4	C-22.35	DROP SEWER CONNECTIONS
C-15.40	CATCH BASIN, TYPE 5	C-22.40	SEWER CLEANOUT
C-15.50	CATCH BASIN, GRATES, LONGITUDINAL BARS	C-23.10	THRUST BLOCKS FOR WATER LINES
C-15.60	CATCH BASIN, GRATES, TRANSVERSE BARS	C-23.15	BLOCKING FOR WATER VALVES GATE AND BUTTERFLY
C-15.70	CATCH BASIN MISC. DETAILS	C-23.20	ANCHOR BLOCK FOR VERTICAL BENDS
C-15.75	CATCH BASIN, DROP INLET	C-23.25	VERTICAL REALIGNMENT FOR WATER MAINS
C-15.80	CATCH BASIN, MEDIAN FLUSH	C-23.30	VALVE BOX INSTALLATION (2 SHEETS)
C-15.81	CATCH BASIN, MEDIAN, SIDE SLOPE	C-23.35	TAPPING SLEEVE AND VALVE INSTALLATION
C-15.90	CATCH BASIN, MEDIAN DIKE, PRECAST	C-23.40	JOINT RESTRAINT WITH TIE RODS
C-15.91	FREEWAY CATCH BASIN DETAILS (2 SHEETS)	C-23.45	CONCRETE WATER METER BOX
C-15.92	SPECIAL CATCH BASIN WITH HALF BARRIER	C-23.50	STEEL COVER FOR WATER METER BOX
C-16.10	IRRIGATION HEADWALLS 18" TO 60" DIAMETER PIPES	C-23.55	WATERLINE-CUT AND PLUG 12" DIA. MAIN AND SMALLER
C-16.20	IRRIGATION STANDPIPES	C-23.60	HYDRANT INSTALLATION
C-16.30	IRRIGATION VALVE AND GATE	C-23.65	FIRE HYDRANT LOCATIONS
C-16.40	IRRIGATION SLEEVES		
C-17.10	BANK PROTECTION, RAIL TYPES 1, 2 & 3		
C-17.20	BANK PROTECTION, RAIL TYPES 4, 5 & 6		



# CONSTRUCTION STANDARD - INDEX

DRAWING NO.	TITLE	DRAWING NO.	TITLE
C-13.10	PIPE CULVERT INSTALLATION (2 SHEETS)	C-18.10	MANHOLE DETAILS
C-13.15	TYPICAL PIPE INSTALLATION	C-18.20	MANHOLE FRAME & COVER DETAILS
C-13.20	PIPE, REINFORCED CONCRETE END SECTION	C-18.30	MISCELLANEOUS MANHOLE DETAILS
C-13.25	PIPE, CORRUGATED METAL, END SECTION	C-18.40	MANHOLE RISER DETAILS
C-13.30	PIPE & PIPE ARCH, CORRUGATED METAL CONCRETE INVERT PAVING		
C-13.55	PIPE, CATTLE-VEHICLE PASS, MITERED END TREATMENT	C-19.10	FORD - CONCRETE WALLS
C-13.60	SLOTTED DRAIN DETAILS	C-19.20	FORDS - TYPES 1 & 2
C-13.65	SLOTTED DRAIN INSTALLATION DETAILS		
C-13.70	STORM DRAIN CONNECTION DETAILS	C-21.10	SURVEY MONUMENT, FRAME AND COVER, RIGHT OF WAY MARKER
C-13.75	STORM DRAIN OUTLET DETAILS (2 SHEETS)	C-21.20	STANDARD MARKER
C-13.80	PIPE COLLAR DETAILS		
		C-22.10	UTILITY LINE, PROTECTIVE CONCRETE SLAB
C-15.10	CATCH BASIN, TYPE 1	C-22.15	SANITARY SEWER ENCASEMENT
C-15.20	CATCH BASIN, TYPE 3	C-22.20	PIPE SUPPORT ACROSS TRENCHES (3 SHEETS)
C-15.30	CATCH BASIN, TYPE 4	C-22.25	PRECAST SANITARY SEWER MANHOLES
C-15.40	CATCH BASIN, TYPE 5	C-22.30	STUB OUT AND PLUG
C-15.50	CATCH BASIN, GRATES, LONGITUDINAL BARS	C-22.35	DROP SEWER CONNECTIONS
C-15.60	CATCH BASIN, GRATES, TRANSVERSE BARS	C-22.40	SEWER CLEANOUT
C-15.70	CATCH BASIN MISC. DETAILS		
C-15.75	CATCH BASIN, DROP INLET	C-23.10	THRUST BLOCKS FOR WATER LINES
C-15.80	CATCH BASIN, MEDIAN FLUSH	C-23.15	BLOCKING FOR WATER VALVES GATE AND BUTTERFLY
C-15.81	CATCH BASIN, MEDIAN, SIDE SLOPE	C-23.20	ANCHOR BLOCK FOR VERTICAL BENDS
C-15.90	CATCH BASIN, MEDIAN DIKE, PRECAST	C-23.25	VERTICAL REALIGNMENT FOR WATER MAINS
C-15.91	FREEWAY CATCH BASIN DETAILS (2 SHEETS)	C-23.30	VALVE BOX INSTALLATION (2 SHEETS)
C-15.92	SPECIAL CATCH BASIN WITH HALF BARRIER	C-23.35	TAPPING SLEEVE AND VALVE INSTALLATION
		C-23.40	JOINT RESTRAINT WITH TIE RODS
C-16.10	IRRIGATION HEADWALLS 18" TO 60" DIAMETER PIPES	C-23.45	CONCRETE WATER METER BOX
C-16.20	IRRIGATION STANDPIPES	C-23.50	STEEL COVER FOR WATER METER BOX
C-16.30	IRRIGATION VALVE & GATE	C-23.55	WATERLINE-CUT AND PLUG 12" DIA. MAIN AND SMALLER
C-16.40	IRRIGATION SLEEVES	C-23.60	HYDRANT INSTALLATION
		C-23.65	FIRE HYDRANT LOCATIONS
C-17.10	BANK PROTECTION, RAIL TYPES 1, 2 & 3		
C-17.20	BANK PROTECTION, RAIL TYPES 4, 5 & 6		

CONSTRUCTION DRAWING SYMBOLS		CONSTRUCTION DRAWING SYMBOLS	
NEW FEATURES	EXISTING FEATURES	NEW FEATURES	EXISTING FEATURES
City Limits .....	.....	Section Corner .....	.....
County Line .....	.....	Survey Control Point .....	.....
Forest or Reservation Boundry .....	.....	Bench Mark .....	.....
Property Line .....	.....	Access Control .....	.....
Mid Section or Quarter Section Line .....	.....	Sidewalk, Curb & Gutter w/Depressed Curb (1"=50' or larger) .....	.....
Right of Way Line .....	.....	Curb & Gutter with Depressed Curb (1"=100') .....	.....
Section Line .....	.....	Curb, Single with Depressed Area .....	.....
Sixteenth Line .....	.....	Pavement and Sidewalk Edge .....	.....
National, State Boundry .....	.....	Turnout .....	.....
Township or Range Line .....	.....	Top of Cut .....	.....
Temporary Construction Easement .....	.....	Toe of Fill .....	.....
Mile Post Marker .....	▲ MP	Transition, Cut to Fill .....	.....
Right of Way Marker .....	●	Railroad Track (1"=50' or larger) .....	.....
Survey Monument .....	⊕	Railroad Track (1"=100') .....	.....
Angle Point or PI .....	△	Bank Protection .....	.....
Centerline, Station Marks .....	.....	Bridge .....	.....
Quarter Corner .....	○	Building .....	.....

DESIGN APPROVED

*James H. Ottensm*

APPROVED FOR DISTRIBUTION

*Randy Hall*

STATE OF ARIZONA

DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

STANDARD DRAWINGS

① SYMBOL LEGEND

































































REV.

7/94


DRAWING NO.

C-01.10


NO.	DESCRIPTION OF REVISIONS	NAME BY	DATE
1	MISSILE STD	PHB	7/94
2			
3			

	CONSTRUCTION DRAWING SYMBOLS			CONSTRUCTION DRAWING SYMBOLS	
	NEW FEATURES	EXISTING FEATURES		NEW FEATURES	EXISTING FEATURES
Catch Basin, Curb & Gutter .....			Straight Hdwl w/End Sct, Pipe (1"=20') (All Dia) .....		
Catch Basin, Median Dike .....			Straight Hdwl w/End Sct, Pipe (1"=50' or smaller) (Dia=42" and larger) .....		
Catch Basin, Off Roadway, Flush .....			Straight Hdwl w/End Sct, Pipe (1"=50' or smaller) (Dia=36" and smaller) .....		
Catch Basin, Single Curb .....			"U" Hdwl w/End Sct, Pipe (1"=20') (All Dia) .....		
Cattle Guard .....			"U" Hdwl w/End Sct, Pipe (1"=50' or smaller) (Dia=42" and larger) .....		
Concrete Box Culvert .....			"U" Hdwl w/End Sct, Pipe (1"=50' or smaller) (Dia=36" and smaller) .....		
Dike, Median .....			Wing Hdwl w/End Sct, Pipe (1"=20') (All Dia) .....		
Dike .....			Wing Hdwl w/End Sct, Pipe (1"=50' or smaller) (Dia=42" and larger) .....		
Downdrain, one way .....			Wing Hdwl w/End Sct, Pipe (1"=50' or smaller) (Dia=36" and smaller) .....		
Downdrain, two way .....			"L" Hdwl w/End Sct, Pipe (1"=20') (All Dia) .....		
Manhole .....			"L" Hdwl w/End Sct, Pipe (1"=50' or smaller) (Dia=42" and larger) .....		
Manhole, Frame & Cover, Reset .....			"L" Hdwl w/End Sct, Pipe (1"=50' or smaller) (Dia=36" and smaller) .....		
Retaining Wall .....			Pipe Ext W/End Sct & Berm (1"=20') (All Dia) .....		
Rock Riprap .....			Pipe Ext W/End Sct & Berm (1"=20') (1"=50' or smaller) (Dia=42" and larger) .....		
Spillway, one way .....			Pipe Ext W/End Sct & Berm (1"=20') (1"=50' or smaller) (Dia=36" and smaller) .....		
Spillway, two way .....			Pipe Ext W/End Sct Roadway Widening (1"=20') .....		

DESIGN APPROVED



APPROVED FOR DISTRIBUTION



STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV.

7/94

①

SYMBOL LEGEND

DRAWING NO.

C-01.11

NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	ADDED SYMBOL FOR GUARD RAIL EXTRUDER TERMINAL	PMH	10/95
2			
3			
4			

	CONSTRUCTION DRAWING SYMBOLS			CONSTRUCTION DRAWING SYMBOLS	
	NEW FEATURES	EXISTING FEATURES		NEW FEATURES	EXISTING FEATURES
Plan View, Bituminous Pavement.....			Irrigation Ditch, Concrete .....		
Plan View, Concrete Pavement.....			Irrigation Ditch, Earth .....		
Plan View, Graded Surface .....			Irrigation Line (I'=20') .....		
Plan View, Obliterate Pavement.....			Irrigation Line (I'=100') .....		
Plan View, Wood .....			Overhead Power/Joint Use Line .....		
Section, Asphaltic Concrete Friction Course .....			Overhead Telephone Line .....		
Section, Bituminous Pavement.....			Sanitary Sewer (I'=20') .....		
Section, Concrete .....			Sanitary Sewer (I'=100') .....		
Section, Metal .....			Storm Drain (I'=20') & (I'=50') .....		
Section, Wood .....			Storm Drain (I'=100') .....		
Section, Aggregate Base .....			Street Light and With Mast Arm .....		
Section, Ground Line .....			Telephone/Power Pedestal .....		
Ground Line Profile .....			Utility Pole with Down Guy and Anchor .....		
Barbed Wire Fence & Gate .....			Underground Power/Joint Use Line .....		
Chain Link Fence & Gate .....			Underground Telephone Line .....		
Guard Rail & Breakaway Cable Terminal.....			Water/Gas Meter Box .....		
① Guard Rail & Guard Rail Extruder Terminal.....			Water/Gas Valve .....		
Gas Line .....					

DESIGN APPROVED  
  
 APPROVED FOR  
 DISTRIBUTION

STATE OF ARIZONA  
 DEPARTMENT OF TRANSPORTATION  
 DIVISION OF HIGHWAYS  
 STANDARD DRAWINGS

REV.  
 10/95

SYMBOL LEGEND

DRAWING NO.  
 C-01.12

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	RELEASE STD	PHG	7/94
2			
3			
4			

	CONSTRUCTION DRAWING SYMBOLS			CONSTRUCTION DRAWING SYMBOLS	
	NEW FEATURES	EXISTING FEATURES		NEW FEATURES	EXISTING FEATURES
Plan View, Bituminous Pavement.....			Irrigation Ditch, Concrete .....		
Plan View, Concrete Pavement.....			Irrigation Ditch, Earth .....		
Plan View, Graded Surface .....			Irrigation Line (1"=20') .....		
Plan View, Obliterate Pavement.....			Irrigation Line (1"=100') .....		
Plan View, Wood .....			Overhead Power/Joint Use Line .....		
Section, Asphaltic Concrete Friction Course .....			Overhead Telephone Line .....		
Section, Bituminous Pavement .....			Sanitary Sewer (1"=20') .....		
Section, Concrete .....			Sanitary Sewer (1"=100') .....		
Section, Metal .....			Storm Drain (1"=20') & (1"=50') .....		
Section, Wood .....			Storm Drain (1"=100') .....		
Section, Aggregate Base .....			Street Light and With Mast Arm .....		
Section, Ground Line .....			Telephone/Power Pedestal .....		
Ground Line Profile .....			Utility Pole with Down Guy and Anchor .....		
Barbed Wire Fence & Gate .....			Underground Power/Joint Use Line .....		
Chain Link Fence & Gate .....			Underground Telephone Line .....		
Guard Rail & Breakaway Cable Terminal.....			Water/Gas Meter Box .....		
Gas Line .....			Water/Gas Valve .....		

DESIGN APPROVED  
*Terry H. Ottaviano*  
 APPROVED FOR  
 DISTRIBUTION  
*Ronald Williams*

STATE OF ARIZONA  
 DEPARTMENT OF TRANSPORTATION  
 DIVISION OF HIGHWAYS  
 STANDARD DRAWINGS

REV.  
 7/94

① SYMBOL LEGEND C-01.12

1	DESCRIPTION OF REVISION	DATE BY	REV
2	MODIFIED SYMBOLS	PHB	10/95
3			
4			

	CONSTRUCTION DRAWING SYMBOLS			CONSTRUCTION DRAWING SYMBOLS	
	NEW FEATURES	EXISTING FEATURES		NEW FEATURES	EXISTING FEATURES
Water Line .....			① Depressed Index Contour Line .....		
Drainage Channel .....			Depressed Intermediate Contour Line .....		
Drainage Ditch .....			Block Wall (1'=20') .....		
Major Wash .....			Median Barrier .....		
Minor Wash .....			Fire Hydrant .....		
± Grade, Profile .....			Standpipe .....		
Hedge .....			Transmission Tower .....		
Palm Tree .....			Windmill .....		
Shrubby .....			Mall Box .....		
Unclassified Tree .....			Flag Pole .....		
Sign, Single Post .....			North Arrow .....		
Sign, Multiple Post .....					
Dimensions .....					
Visible Outlines, Sections, etc... ..					
Index Contour Line .....					
① Intermediate Contour Line .....					

DESIGN APPROVED  AUTHORIZED FOR DISTRIBUTION 	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS		REV.
	SYMBOL LEGEND		10/95 DRAWING NO. C-0113

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REISSUE STD	PHB	7/94
2			
3			
4			

Water Line	-----
Drainage Channel	-----
Drainage Ditch	-----
Major Wash	-----
Minor Wash	-----
± Grade, Profile	-----
Hedge	-----
Palm Tree	-----
Shrubbery	-----
Unclassified Tree	-----
Sign, Single Post	-----
Sign, Multiple Post	-----
Dimensions	-----
Visible Outlines, Sections, etc...	-----
Index Contour Line	-----
Intermediate Contour Line	-----

CONSTRUCTION DRAWING SYMBOLS	
NEW FEATURES	EXISTING FEATURES

Depressed Index Contour Line	-----
Depressed Intermediate Contour Line	-----
Block Wall (1"=20')	-----
Median Barrier	-----
Fire Hydrant	-----
Standpipe	-----
Transmission Tower	-----
Windmill	-----
Mail Box	-----
Flag Pole	-----
North Arrow	-----

CONSTRUCTION DRAWING SYMBOLS	
NEW FEATURES	EXISTING FEATURES

DESIGN APPROVED 	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION 	① SYMBOL LEGEND	DRAWING NO. C-01.13

(2)	DESCRIPTION OF REVISIONS	DATE BY	DATE
(1)	CORRECTED SPELLING	PHB	10/95
(2)	DELETED ABBREVIATION	PHB	10/95
(3)	REVISED ABBREVIATION	PHB	10/95
(4)	ADDED ABBREVIATION	PHB	10/95

WORDS	ABBREVIATION	WORDS	ABBREVIATION	WORDS	ABBREVIATION
<b>A</b>		<b>B (cont)</b>		<b>C (cont)</b>	
Abutment	Abt	Bituminous Surface Treatment	BST	④ Corrugated High Density Polyethylene Plastic Pipe	CHDPEPP
Acceleration	Acc	Bituminous Treated Base	BTB	Corrugated Steel Pipe	CSP
Acres	Ac	Black Steel Pipe	BSP	Corrugated Steel Pipe Arch	CSPA
Aggregate	Agg	Borrow	Bor	County	Co
Aggregate Base	AB	Boulevard	BLVD, Blvd	Crossing	X-ING
Ahead	AHD, Ahd	Boundary	③ Bdry	Cross Section	X-SECT
Alternate	Alt	Brass Cap	BC	Crown	Cr
Aluminum	Al	Breakaway Cable Terminal	BCT	Cubic	Cu
American Association of State Highway and Transportation Officials	AASHTO	Bridge	Br	Cubic Feet Per Second	CFS
American Concrete Institute	ACI	Building	Bldg	Cubic Yard or Cubic Yards	CY, Cu Yd
American Institute of Steel Construction	AISC	<b>C</b>		Culvert	③ Culv
① American Road and Transportation Builders Association	ARTBA	Calculated	Calc	Curb and Gutter	C&G
American Society for Testing Materials	ASTM	Cast-in-Place	C-I-P	Curve to Spiral	CS
Amount	Amt	Cast Iron	CI	<b>D</b>	
Approach	Appr	Cast Iron Pipe	CIP	Deceleration	Dcl
Approximate	Approx	Catch Basin	CB	Deflection	Def
Asphalt	Asph	Cattle Guard	CG	Deflection of Total Curve	I
Asphalt Rubber	AR	Cement	Cem	Degree of Curve	D
Asphalt Rubber ACFC	ARACFC	Cement Treated Base	CTB	Delineator	Del
Asphaltic Concrete	AC	Center	Ctr	Delta	Δ
Asphaltic Concrete Base	ABC	Center Line	℄	Depressed Curb	DC
Asphaltic Concrete Friction Course	ACFC	Center to Center	C to C	Design Speed	Des Spd
Asphaltic Concrete Surface Course	ACSC	Channel	Chan	Detail	Dtl
Avenue	AVE, Ave	Class	Cl	Diameter	Dia
Average Daily Traffic	ADT	Clear	Clr	Distance	Dist
<b>B</b>		Column	Col	Division	Div
Back	BK, BK	Compact or Compaction	Comp	Double	Dbi
Backfill	Bkfl	Complete in Place	C in P	Drain or Drainage	Drn
② Balance	Bal	Concrete	Conc	Drainage Area	DA
Bank Protection	Bank Prt	Concrete Box Culvert	CBC	Drawing	Dwg
Barbed Wire	BW	Concrete Treated Base	CTB	Drive	Dr
Bearing	Brg	Connection	Conn	Driveway	Dwy
Begin	Bgn	Conduit	Cond	Ductile Iron Pipe	DIP
Begin Curb Return	BCR	Construct or Construction	Cst	<b>E</b>	
Begin Full Super	BFS	Continuous	Cont	Each	Ea
Bench Mark	BM	Coordinate	Coord	Easement	Esmt
Bevel or Beveled	Bev	Corner	Cor	East	E
Bituminous	Bit	Correction	Corr	Eastbound	EB
Bituminous Mixture	Bit Mix	Corrugated Aluminum Pipe	CAP		
		Corrugated Aluminum Pipe Arch	CAPA		

DESIGN APPROVED <i>Joseph H. Ottobene</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISSEMINATION <i>Donald L. Williams</i>	GENERAL ABBREVIATIONS	DRAWING NO. C-01.30



NO.	DESCRIPTION OF REVISIONS	DATE	SITE
1	REVISION 1	7/94	
2			
3			
4			

## WORDS

### A

Abutment  
Acceleration  
Acres  
Aggregate  
Aggregate Base  
Ahead  
Alternate  
Aluminum  
American Association of State Highway  
and Transportation Officials  
American Concrete Institute  
American Institute of Steel Construction  
American Road and Transportation  
Builders Association  
American Society for Testing Materials  
Amount  
Approach  
Approximate  
Asphalt  
Asphalt Rubber  
Asphalt Rubber ACFC  
Asphaltic Concrete  
Asphaltic Concrete Base  
Asphaltic Concrete Friction Course  
Asphaltic Concrete Surface Course  
Avenue  
Average Daily Traffic

### B

Back  
Backfill  
Balance  
Balance Point  
Bank Protection  
Barbed Wire  
Bearing  
Begin  
Begin Curb Return  
Begin Full Super  
Bench Mark  
Bevel or Beveled

## ABBREVIATION

Abt  
Acc  
Ac  
Agg  
AB  
AHD, Ahd  
Alt  
Al  
AASHTO  
ACI  
AISC  
ARTBA  
ASTM  
Amt  
Appr  
Approx  
Asph  
AR  
ARACFC  
AC  
ABC  
ACFC  
ACSC  
AVE, Ave  
ADT  
BK, Bk  
Bkfi  
Bal  
BP  
Bank Pnt  
BW  
Brq  
Bgn  
BCR  
BFS  
BM  
Bev

## WORDS

### B (cont)

Bituminous  
Bit Mix  
Bituminous Surface Treatment  
Bituminous Treated Base  
Black Steel Pipe  
Borrow  
Boulevard  
Boundary  
Brass Cap  
Breakaway Cable Terminal  
Bridge  
Building  
C  
Calculated  
Cast-In-Place  
Cast Iron  
Cast Iron Pipe  
Catch Basin  
Cattle Guard  
Cement  
Cement Treated Base  
Center  
Center Line  
Center to Center  
Channel  
Class  
Clear  
Column  
Compact or Compaction  
Complete In Place  
Concrete  
Concrete Box Culvert  
Concrete Treated Base  
Connection  
Conduit  
Construct or Construction  
Continuous  
Coordinate  
Corner  
Correction  
Blt  
Blt Mix  
BST  
BTB  
BSP  
Bor  
BLVD, Blvd  
Bdy  
BC  
BCT  
Br  
Blq  
Calc  
C-I-P  
Cl  
CIP  
CB  
CG  
Cam  
CTB  
Ctr  
C  
C to C  
Chan  
Cl  
Clr  
Col  
Comp  
C in P  
Conc  
CBC  
CTB  
Conn  
Cond  
Cst  
Cont  
Coord  
Cor  
Corr

## ABBREVIATION

## WORDS

### C (cont)

Corrugated Aluminum Pipe  
Corrugated Aluminum Pipe Arch  
Corrugated Steel Pipe  
Corrugated Steel Pipe Arch  
County  
Crossing  
Cross Section  
Crown  
Cubic  
Cubic Feet Per Second  
Cubic Yard or Cubic Yards  
Culvert  
Curb and Gutter  
Curve to Spiral  
D  
Deceleration  
Deflection  
Deflection of Total Curve  
Degree of Curve  
Delineator  
Delta  
Depressed Curb  
Design Speed  
Detail  
Diameter  
Distance  
Division  
Double  
Drain or Drainage  
Drainage Area  
Drawing  
Drive  
Driveway  
Ductile Iron Pipe  
E  
Each  
Easement  
East  
Eastbound  
CAP  
CAPA  
CSP  
CSPA  
Co  
X-ING  
X-SECT  
Cr  
Cu  
CFS  
CY, Cu Yd  
Civ  
C&G  
CS  
Dcl  
Def  
I  
D  
Del  
A  
DC  
Des Spd  
Dtl  
Dia  
Dist  
Div  
Dbl  
Dnn  
DA  
Dwg  
Dr  
Dwy  
DIP  
Ea  
Eamt  
E  
EB

DESIGN APPROVED <i>James H. Ottensm</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>James H. Ottensm</i>	GENERAL ABBREVIATIONS	DRAWING NO. C-01.30

1	REVISED SPELLING	PHB	10/95
2	REVISED ABBREVIATION	PHB	10/95
3	ADDED ABBREVIATION	PHB	10/95
4			

WORDS	ABBREVIATION	WORDS	ABBREVIATION	WORDS	ABBREVIATION
<b>E (cont)</b>		<b>G (cont)</b>		<b>M (cont)</b>	
Edge of Pavement	EP	Ground	Gnd	Mile or Miles	MI
Electric, Electricity	Elec. E	① Ground Compaction	Gnd Comp	Mile Post	MP
Elevation	Elev	Grubbing	Grb	Miles Per Hour	MPH
Embankment	Emb	Guard	Grd	Mineral Aggregate	MA
End Curb Return	ECR	Guard Rail	GR	Minimum	Min
① End Full Superelevation	EFS	① Guard Rail Extruder Terminal	GET	Miscellaneous	Misc
Engineer	Engr	H		Modify or Modified	Mod
Entrance	Ent	Headwall	Hdwl	Monument	Mon
Equation	Eq, Eq	Height	Ht, H, h	Mountain	Mt
Estimate	Est	Height of Instrument	HI	N	
Excavation	② Exc	Head Water	HW	National	Nati
Existing	Exst	Highway	Hwy	Non-Reinforced Cast-in-Place Concrete Pipe	NRCIPCP
Expansion Joint	Exp Jt	Horizontal	② HorZ	Normal Crown	NC
Extend or Extension	Ext	Horizontal Elliptical Reinforced Concrete Pipe	HERCP	North	N
External	Ext			Northbound	NB
<b>F</b>		<b>I</b>		Number	No
Federal	Fed	Improvement	Impr	<b>O</b>	
Feet or Foot	Ft	Inch or Inches	In	Obliterate	Obl
Feet per Foot	W	Include, Included or Inclusive	Incl	Original	Orig
Feet Per Second	FPS	Inside Diameter	ID	Outside Diameter	OD
Figure	Fig	Invert	Inv	Overhead	OH
Finish	Fin	Irrigation	Irr	Overpass	OP
Floor	Fl	J		<b>P</b>	
Flow Line	FL	Joint	Jt	Parkway	Pkwy
Footing	Ftg	Junction	Jct	Pavement	Pvmt
Forest	Fst	<b>L</b>		Pedestrian	Ped
Found	Fnd	Laboratory	Lab	Place	Pl
Frame	Fr	Lateral	Lat	Point	Pt
Freeway	Fwy	Left	Lt	Point of Compound Curvature	PCC
Frontage	Frt	Length or Length of Curve	L	Point of Curvature	PC
Furnish or Furnished	Furn	③ Length of Normal Crown Removal	L <sub>C</sub>	Point of Intersection	PI
Futura	Fut	③ Length of Spiral	L <sub>S</sub>	Point of Reverse Curvature	PRC
<b>G</b>		③ Length of Superelevation Runoff	L <sub>S</sub>	Point of Tangency	PT
Gas	G	Line	Ln	Point on Curve	POC
Gas Meter	GM	Linear or Lineal	Lin	① Point on Semi-Tangent	POST
Gas Valve	GV	Linear Feet	Lin Ft	Point on Spiral	POS
Galvanize or galvanized	Galv	Location	Loc	Point on Tangent	POT
Gauge	Ga	<b>M</b>		Polyethylene	PE
Government	② Gov't	Manhole	MH		
Grade	Gr	Material	Mtl		
Grade Separation	GS	Maximum	Max		
		Median	Med		

DESIGN APPROVED <i>Luigi H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>David Williams</i>	GENERAL ABBREVIATIONS	DRAWING NO. C-01.31

NO.	DESCRIPTION OF REVISION	DATE	BY
1	REVISION 1		
2			
3			
4			

## WORDS

### E (cont)

Edge of Pavement  
Electric, Electricity  
Elevation  
Embankment  
End Curb Return  
End Full Super  
Engineer  
Entrance  
Equation  
Estimate  
Excavation  
Existing  
Expansion Joint  
Extend or Extension  
External

### F

Federal  
Feet or Foot  
Feet per Foot  
Feet Per Second  
Figure  
Finish  
Floor  
Flow Line  
Footing  
Forest  
Found  
Frame  
Freeway  
Frontage  
Furnish or Furnished  
Future

### G

Gas  
Gas Meter  
Gas Valve  
Galvanize or galvanized  
Gauge  
Government

## ABBREVIATION

EP  
Elec, E  
Elev  
Emb  
ECR  
EFS  
Engr  
Ent  
EQ, Eq  
Est  
Ex  
Exst  
Exp Jt  
Ext  
Ext

Fed  
Ft  
ft  
FPS  
Fig  
Fln  
Fl  
FL  
Ftg  
Fst  
Fnd  
Fr  
Fwy  
Frt  
Furn  
Fut

G  
GM  
GV  
Galv  
Ga  
Govt

## WORDS

### G (cont)

Grade  
Grade Separation  
Ground  
Grubbing  
Guard  
Guard Rail  
H  
Headwall  
Height  
Height of Instrument  
Head Water  
Highway  
Horizontal  
Horizontal Elliptical Reinforced  
Concrete Pipe

### I

Improvement  
Inch or Inches  
In  
Include, Included or Inclusive  
Inside Diameter  
Invert  
Irrigation  
J  
Joint  
Junction  
L  
Laboratory  
Lateral  
Left  
Length or Length of Curve  
Line  
Linear or Lined  
Linear Feet  
Location

M  
Manhole  
Material  
Maximum  
Median

## ABBREVIATION

Gr  
GS  
Gnd  
Grb  
Grd  
GR  
Hdwl  
Ht, H, h  
HI  
HW  
Hwy  
Hor  
HERCP

Impr  
In  
Incl  
ID  
Inv  
Irr  
Jt  
Jct  
Lab  
Lat  
Lt  
L  
Ln  
Lin  
Lin Ft  
Loc  
MH  
Mtl  
Max  
Med

## WORDS

### M (cont)

Mile or Miles  
Mile Post  
Miles Per Hour  
Mineral Aggregate  
Minimum  
Miscellaneous  
Modify or Modified  
Monument  
Mountain  
N  
National  
Non-Reinforced Cast-In-Place  
Concrete Pipe

Normal Crown  
North  
Northbound  
Number  
O  
Obsolete  
Original  
Outside Diameter  
Overhead  
Overpass  
P

Parkway  
Pavement  
Pedestrian  
Place  
Point  
Point of Compound Curvature  
Point of Curvature  
Point of Intersection  
Point of Reverse Curvature  
Point of Tangency  
Point on Curve  
Point on Semi-Tangency  
Point on Spiral  
Point on Tangent  
Polyethylene

## ABBREVIATION

MI  
MP  
MPH  
MA  
Min  
Misc  
Mod  
Mon  
Mt  
Nati  
NRC/PCP  
NC  
N  
NB  
No  
Obi  
Orig  
OD  
OH  
OP  
Pkw  
Pvmt  
Ped  
Pl  
Pt  
PCC  
PC  
PI  
PRC  
PT  
POC  
POST  
POS  
POT  
PE

DESIGN APPROVED <i>James L. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Robert L. Smith</i>	① GENERAL ABBREVIATIONS	DRAWING NO. C-01.31

	REVISIONS	DATE
1	REVISED SPELLING	PMB 10/95
2	DELETED TWO ABBREVIATIONS	PMB 10/95
3	REVISED ABBREVIATION	PMB 10/95

WORDS	ABBREVIATION	WORDS	ABBREVIATION	WORDS	ABBREVIATION
<b>P (cont)</b>		<b>S</b>		<b>T (cont)</b>	
Polyvinyl Chloride	PVC	Salvage	Salv	Telephone	Tel
Portland Cement Concrete	PCC	Section	Sc†	Temporary	Temp
Portland Cement Concrete Pavement	PCCP	Select Material	SM	Temporary Construction Easement	TCE
Pounds	Lbs	Sheet	Sh	Timber	Tbr
Pounds Per Square Inch	PSI	Shoulder	Shldr	Top of Curb	TC
Preliminary	Prelim	Shrinkage	Shrk	Topography	Topo
① Prestress, Prestressed or Prestressing	PS	Sidewalk	Swk	Township	T
Project	Prj	② Sight Distance-Stopping	SD <sub>s</sub>	Traffic Interchange	TI
Property Line	P/L	Single	Sgl	Transition	Trns
Proposed	Prop	Skew	Sk	Turning Point	TP
Protection	Prt	South	S	Turnout	TO
Provision or Provide	Prv	Southbound	SB	Typical	Typ
<b>Q</b>		Special	Spcl	<b>U</b>	
Quadrant	Quad	Specification	Spec	Underground	Ugnd
Quantity or Quantities	Quan	Spiral Rate of Change	a	Underpass	UP
Quantity of Drainage Runoff	Q	Spiral To Curve	SC	<b>V</b>	
<b>R</b>		Spiral To Tangent	ST	Variable	Var
Radius	R	Square	Sq	Vertical	Vert
Railroad	RR	Square Feet	Sq Ft	Vertical Curve	VC
Range	R	Square Yard	Sq Yd	Vertical Elliptical Reinforced	VERCP
Reconstruct	Recst	Standard	Std	Concrete Pipe	
Reference	Ref	State Route	SR	Vertical Point of Intersection	VPI
Reinforced or Reinforcing	Reinf	Station	Sta	Viaduct	Via
Reinforced Concrete	RC	Street	St	Vitrified Clay Pipe	VCP
Reinforced Concrete Pipe	RCP	Structure or Structural	Str	Volume	Vol
Reinforced Concrete Pipe Arch	RCPA	Subdivision	Subdiv	<b>W</b>	
Reinforcing Bar	Rebar	Subgrade	SG	Water	W
Relocate, Relocation or Relocated	Reloc	Subgrade Seal	SS	Water Meter	WM
Remove	Rem	Superelevation	③ e or Super	Water Valve	WV
Required	Reqd	Surface	Surf	Welded Wire Fabric	WWF
Reservation	Resv	Survey	Sur	West	W
Residence	Res	Swell	Sw	Westbound	WB
Retain or Retaining	Ret	① Symmetrical	Sym	Western Wood Products Association	WWPA
Revised or Revision	Rev	T		Wide or Width	W
Right	Rt	Tangent	Tan	Wood	Wd
Right of Way	R/W	Tangent Length	T	Y	
Road	Rd	Tangent to Spiral	TS	Yard	Yd
Roadway	Rdwy	Telegraph	Tlg		
Route	Rte				
Rubber Gasket Reinforced Concrete Pipe	RGRCP				

DESIGN APPROVED <i>Henry H. Ottman</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Frank Williams</i>	GENERAL ABBREVIATIONS	DRAWING NO. C-01.32

NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	REVISION 2/79	7/79	
2			
3			

# WORDS

## P (cont)

Polyvinyl Chloride  
Portland Cement Concrete  
Portland Cement Concrete Pavement  
Pounds  
Pounds Per Square Inch  
Preliminary  
Prestress, Prestressed or Prestressing  
Project  
Property Line  
Proposed  
Protection  
Provision or Provide

## Q

Quadrant  
Quantity or Quantities  
Quantity of Drainage Runoff

## R

Radius  
Railroad  
Range  
Reconstruct  
Reference  
Reinforced or Reinforcing  
Reinforced Concrete  
Reinforced Concrete Pipe  
Reinforced Concrete Pipe Arch  
Reinforcing Bar  
Relocate, Relocation or Relocated  
Remove  
Required  
Reservation  
Residence  
Retain or Retaining  
Revised or Revision  
Right  
Right of Way  
Road  
Roadway  
Route  
Rubber Gasket Reinforced Concrete Pipe

# ABBREVIATION

PVC  
PCC  
PCCP  
Lbs  
PSI  
Prelim  
PS  
Prj  
P/L  
Prop  
Prt  
Prv  
Qued  
Quen  
Q  
R  
RR  
R  
Recst  
Ref  
Reinf  
RC  
RCP  
RCPA  
Rebar  
Reloc  
Rem  
Reqd  
Resv  
Res  
Ret  
Rev  
Rt  
R/W  
Rd  
Rowy  
Rte  
RGRCP

# WORDS

## S

Salvage  
Section  
Select Material  
Sheet  
Shoulder  
Shrinkage  
Sidewalk  
Sight Distance-Intersection  
Sight Distance-Passing  
Sight Distance-Stopping  
Single  
Skew  
South  
Southbound  
Special  
Specification  
Spiral Rate of Change  
Spiral To Curve  
Spiral To Tangent  
Square  
Square Feet  
Square Yard  
Standard  
State Route  
Station  
Street  
Structure or Structural  
Subdivision  
Subgrade  
Subgrade Seal  
Super-elevation  
Surface  
Survey  
Swall  
Symmetrical  
T  
Tangent  
Tangent Length  
Tangent to Spiral  
Telegraph

# ABBREVIATION

Salv  
Sct  
SM  
Sh  
Shldr  
Shr  
Swlk  
SD<sub>i</sub>  
SD<sub>p</sub>  
SD<sub>s</sub>  
Sgl  
Sk  
S  
SB  
Spcl  
Spec  
a  
SC  
ST  
Sq  
Sq Ft  
Sq Yd  
Std  
SR  
Sta  
St  
Str  
Subdlv  
SC  
SS  
Super  
Surf  
Sur  
Sw  
Sym  
Tan  
T  
TS  
Tlg

# WORDS

## T (cont)


Telephone  
Temporary  
Temporary Construction Easement  
Timber  
Top of Curb  
Topography  
Township  
Traffic Interchange  
Transition  
Turning Point  
Turnout  
Typical  
U  
Underground  
Underpass  
V  
Variable  
Vertical  
Vertical Curve  
Vertical Elliptical Reinforced Concrete Pipe  
Vertical Point of Intersection  
Viaduct  
Vitrified Clay Pipe  
Volume  
W  
Water  
Water Meter  
Water Valve  
Welded Wire Fabric  
West  
Westbound  
Western Wood Products Association  
Wide or Width  
Wood  
Y  
Yard

# ABBREVIATION


Tel  
Temp  
TCE  
Tbr  
TC  
Topo  
T  
TI  
Trns  
TP  
TO  
Typ  
Ugnd  
UP  
Var  
Vert  
VC  
VERCP  
VPI  
Via  
VCP  
Vol  
W  
WM  
WV  
WWF  
W  
WB  
WNPA  
W  
Wd  
Yd

DESIGN APPROVED <i>Henry H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>R. Williams</i>	GENERAL ABBREVIATIONS	DRAWING NO. C-01.32


NO.	DESCRIPTION OF INCLUSION	DATE BY	DATE
1	ADDED SLOPE ROUNDING DETAIL	PMB	1/83
2	MODIFIED SHOULDER WEDGE DETAIL	TC	1/83
3			




MINIMUM SLOPES




INTERMEDIATE SLOPES



MAXIMUM SLOPES



SUBGRADE/SLOPE HINGE TREATMENT DETAIL




$$W = D \times \text{Slope (6\%)}$$

$$D = \text{Str Sec Depth (ft) excluding ACFC}$$

$$SW = 2 \times W + \text{Roadway Width}$$


SHOULDER WEDGE DETAIL



MINIMUM DITCH CONDITIONS DETAIL

## GENERAL NOTES


- Roadway width, cut ditch width, cross slope, and pavement structure section will be shown on project plans.
  - Design highwater should not be located above the subgrade in unpaved ditch.
  - Pavement structure slope is nominal. Actual slope is controlled by (D). See Shoulder Wedge Detail.
  - Slopes beyond the pavement structure, such as embankment and cut slopes, are relative to horizontal.
  - For slope controls within interchange areas, see project plans.
  - When median slopes intersect, see project plans for controls.
  - These slopes are intended to be used with new or reconstructed roadways.
- The 9' min is required when guard rail is utilized on the project. Treatment shall be uniform throughout the project length. The 9' requirement may be waived under special conditions where guard rail is not utilized. The 9' min shall not be waived when the thickness of structure section has not been finalized.




SLOPE ROUNDING DETAIL

Except in solid rock, or as directed by the Engineer, the intersection of roadway cut slopes with the ground surfaces shall be rounded. For cuts up to 6', use 5' semi-tangents for slope rounding. For each additional foot of cut add 1' to semi-tangent to 11' maximum.

DESIGN APPROVED <i>James H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 1/93
APPROVED FOR DISTRIBUTION <i>Christopher H. Harts</i>	SLOPES INTERSTATE	DRAWING NO. C-02.10




MINIMUM SLOPES




SUBGRADE/SLOPE HINGE TREATMENT DETAIL

1. Roadway width, cut ditch width, cross slope, and pavement structure section will be shown on project plans.
2. Design highwater should not be located above the subgrade in unpaved ditch.
3. Pavement structure slope is nominal. Actual slope is controlled by (D). See Shoulder Wedge Detail.
4. Slopes beyond the pavement structure, such as embankment and cut slopes, are relative to horizontal.
5. These slopes are intended to be used with new or reconstructed roadways.

① ■ The 6' min is required when guard rail is utilized on the project. Treatment shall be uniform throughout the project length. The 6' requirement may be waived under special conditions where guard rail is not utilized. The 6' min shall not be waived when the thickness of structure section has not been finalized.



INTERMEDIATE SLOPES




$$W = D \times \text{Slope (4:1)}$$


$$D = \text{Str. Sec Depth (ft) excluding ACFC}$$

$$SW = 2 \times W + \text{Roadway Width}$$


SHOULDER WEDGE DETAIL



MAXIMUM SLOPES



MINIMUM DITCH CONDITIONS DETAIL




■ SLOPE ROUNDING DETAIL


Except in solid rock, or as directed by the Engineer, the intersection of roadway cut slopes with the ground surfaces shall be rounded. For cuts up to 6', use 5' semi-tangents for slope rounding. For each additional foot of cut add 1' to semi-tangent to 11' maximum.

DESIGN APPROVED <i>Joseph Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>David Williams</i>	SLOPES SECONDARY/MISC ROADWAYS	DRAWING NO. C-02.30


NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	CORRECTED SLOPE CALCULATIONS	OKS	1/73
2	ADDED SLOPE ROUNDING DETAIL	PHB	1/73
3	ADDED SHOULDER WEDGE DETAIL	TC	1/73




MINIMUM SLOPES




INTERMEDIATE SLOPES



MAXIMUM SLOPES



SUBGRADE/SLOPE HINGE TREATMENT DETAIL




$$W = D \times \text{Slope (4:1)}$$

$$D = \text{Str. Sec. Depth (ft) excluding ACFC}$$


$$SW = 2 \times W + \text{Roadway Width}$$

SHOULDER WEDGE DETAIL



SLOPE ROUNDING DETAIL

Except in solid rock, or as directed by the Engineer, the intersection of roadway cut slopes with the ground surfaces shall be rounded. For cuts up to 6', use 5' semi-tangents for slope rounding. For each additional foot of cut add 1' to semi-tangent to 11' maximum.



MINIMUM DITCH CONDITIONS DETAIL


## GENERAL NOTES

- Roadway width, cut ditch width, cross slope, and pavement structure section will be shown on project plans.
  - Design highwater should not be located above the subgrade in unpaved ditch.
  - Pavement structure slope is nominal. Actual slope is controlled by (D). See Shoulder Wedge Detail.
  - Slopes beyond the pavement structure, such as embankment and cut slopes, are relative to horizontal.
  - These slopes are intended to be used with new or reconstructed roadways.
- The 9' min is required when guard rail is utilized on the project. Treatment shall be uniform throughout the project length. The 9' requirement may be waived under special conditions where guard rail is not utilized. The 9' min shall not be waived when the thickness of structure section has not been finalized.


DESIGN APPROVED <i>Henry H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 1/93
APPROVED FOR DISTRIBUTION <i>George M. Hunter</i>	SLOPES SECONDARY/MISC. ROADWAYS	DRAWING NO. C-02.30



NO.	DESCRIPTION OF REVISIONS	DATE
1	ADDED ABBREVIATION TO LEGEND	10/95
2	REPLACED TEXT WITH ABBREVIATION	10/95
3		
4		




SPIRAL CURVE TRANSITION




CIRCULAR CURVE TRANSITION

1-WAY ROADWAY-AXIS OF ROTATION AT CONSTR. &  
HIGH POINT OF NORMAL CROWN ON OUTSIDE OF CURVE  
RIGHT TURNING ROADWAY




SPIRAL CURVE TRANSITION



CIRCULAR CURVE TRANSITION

1-WAY ROADWAY-AXIS OF ROTATION AT CONSTR. &  
HIGH POINT OF NORMAL CROWN ON INSIDE OF CURVE  
LEFT TURNING ROADWAY



CIRCULAR CURVE TRANSITION

2-WAY ROADWAY-AXIS OF ROTATION AT &  
(FOR OPPOSITE DEFLECTING CURVE, E.T.L. PROFILES ARE REVERSED)


## GENERAL NOTES

1. Round edge profile intersections with vertical curves having an approximate length in feet equal to the design speed in m.p.h.
2. For main roadway curves without spirals,  $L_s$  is the same as for spiraled curves but with  $0.7 L_s$  on tangent and  $0.3 L_s$  on curve.
3. Shoulders transition with the adjacent travel lane when their normal cross slopes are the same.
4. If shoulders have a normal cross slope steeper than the adjacent lane, the shoulder transition will begin at a different point than that of the adjacent lane. See shoulder transition detail.

## LEGEND


- A - Point at which adverse crown removal begins.
- B - Point at which superelevation transition begins.
- C - Point of equality between superelevation and normal crown
- D - P.C. location for circular curve transition.
- E - Point at which full superelevation is reached.

- ①  $L_c$  - Length of Normal Crown Removal
- ①  $L_s$  - Length of Superelevation Runoff
- E.T.L. - Edge of traveled lane
- - Distance BC =  $(NC) (L_s) / e$
- - Length of Shoulder Transition =  $(NC) (L_s) / (NC \text{ of shoulder})$




SHOULDER TRANSITION DETAIL

DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR REPRODUCTION <i>[Signature]</i>	SUPERELEVATION DISTRIBUTION	DRAWING NO. C-02.50




SPIRAL CURVE TRANSITION




CIRCULAR CURVE TRANSITION

1-WAY ROADWAY-AXIS OF ROTATION AT CONSTR. & HIGH POINT OF NORMAL CROWN ON OUTSIDE OF CURVE  
RIGHT TURNING ROADWAY




SPIRAL CURVE TRANSITION

2-WAY ROADWAY-AXIS OF ROTATION AT &  
(FOR OPPOSITE DEFLECTING CURVE, E.T.L. PROFILES ARE REVERSED)




SPIRAL CURVE TRANSITION



CIRCULAR CURVE TRANSITION

1-WAY ROADWAY-AXIS OF ROTATION AT CONSTR. & HIGH POINT OF NORMAL CROWN ON INSIDE OF CURVE  
LEFT TURNING ROADWAY




CIRCULAR CURVE TRANSITION

## GENERAL NOTES

1. Round edge profile intersections with vertical curves having length in feet equal to design speed in m.p.h.
2. For main roadway curves without spirals,  $L_s$  is the same as for spiraled curves but with  $0.7 L_s$  on tangent and  $0.3 L_s$  on curve.
3. Shoulders transition with the adjacent travel lane when their normal cross slopes are the same.
4. If shoulders have a normal cross slope steeper than the adjacent lane, the shoulder transition will begin at a different point than that of the adjacent lane. See shoulder transition detail.

## LEGEND

- A - Point at which adverse crown removal begins.
- B - Point at which superlevation transition begins.
- C - Point of equality between superlevation and normal crown
- D - P.C. location for circular curve transition.
- E - Point at which full superlevation is reached.
- E.T.L. - Edge of traveled lane
- - Distance  $BC = (NC) (L_s) / e$
- ⊙ - Length of Shoulder Transition =  $(NC) (L_s) / (NC \text{ of shoulder})$



SHOULDER TRANSITION DETAIL


DESIGN APPROVED <i>Joseph Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>Frederick Blum</i>	SUPERELEVATION DISTRIBUTION	DRAWING NO. C-02.50

NO.	DESCRIPTION OF REVISIONS	DATE BY	DATE
1	REMOVED NOTE	PMB	3/94
2	ADDED SLOPE ROUNDING	PMB	3/94
3			
4			


## GENERAL NOTES

1. Dimensions of ditches shall be shown on the plans, as bottom width, depth and length.
2. Ditches shall be constructed with a minimum grade to prevent erosion. Ditch outlet treatment shall be as provided on plans.


①




CROWN DITCH




GRADER DITCH



DITCH




CHANNEL




DITCH AND DIKE

DESIGN APPROVED <i>Henry H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 3/94
APPROVED FOR CONSTRUCTION <i>Cheryl A. Miller</i>	DITCHES, CHANNELS, DIKES AND BERMS DITCHES AND CHANNELS	DRAWING NO. C-03.10 Sheet 1 of 5

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED SLOPE	PMB	3/84
2	MODIFIED INSTALLATION DETAIL	PMB	1/84
3	ADDED PERSPECTIVE VIEW	PMB	3/84
4			




TYPE A DIKE




CROWN DIKE

SLOPE TABLE		
Inside Recovery Area	Outside Recovery Area	
	Desirable	Maximum
10:1	4:1	1 1/2:1




TYPE B TRANSVERSE MEDIAN DIKE

- Slope relative to grade of median at intersection with toe



② TYPICAL DIKE INSTALLATION AT STRUCTURE

Place dikes at structures to create water cushion.




③ TYPICAL TRANSVERSE MEDIAN DIKE INSTALLATION



DESIGN APPROVED <i>Henry H. Ottewill</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 3/94
APPROVED FOR CONSTRUCTION <i>David J. [Signature]</i>	DITCHES, CHANNELS, DIKES AND BERMS DIKES	DRAWING NO. C-03,10 Sheet 2 of 5

### GENERAL NOTES

1. Dimensions for ditch dikes shall be shown on the plans as dike stationing, height, length, dike back slope and top of dike elevation.
2. Dimensions for cut ditch widening shall be shown on the plans as beginning and ending stations.




CUT DITCH WIDENING DETAIL



## SECTION B-B

- Slope relative to grade of cut ditch at intersection with toe




SECTION A-A


SECTION C-C

DESIGN APPROVED <i>Terrell H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR CONSTRUCTION <i>John H. [Signature]</i>	DITCHES, CHANNELS, DIKES AND BERMS DITCH DIKE	DRAWING NO. C-0310 Sheet 3 of 5

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1			
2			
3			




SECTION A-A (WITH END SECTION)




SECTION A-A (WITHOUT END SECTION)

### GENERAL NOTES

1. Pipe berms not required when pipe projection is protected by guard rail.
2. Berm construction similar for multiple pipe installation and for pipes without end sections.
3. Berm construction shown is for pipe extensions. Berm construction similar for new pipe installation. See Pipe Berm Requirement Detail. If Point A is within the recovery area, then a pipe berm is required and Point B is set at the edge of the recovery area.




PIPE BERM REQUIREMENT DETAIL




STRAIGHT PIPE PLAN

Pipe Backfill and Bedding Material Limits  
See Std C-13.15.



ELEVATION

NOTE:  
Single Pipe Installation: D = Outside Diameter of Pipe  
Multiple Pipe Installation: D = Outside Edge to Outside Edge of Pipes




SKEWED PIPE PLAN

DESIGN APPROVED <i>Henry H. Ottensm</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>Greg A. Hester</i>	DITCHES, CHANNELS, DIKES AND BERMS PIPE BERMS	DRAWING NO. C-03.10 SHEET 2 OF 2


DESCRIPTION OF REVISION	DATE	BY

# GENERAL NOTES


1. Berm construction similar for box culvert and pipe with headwall.
2. Berm construction shown is for extension of existing facilities. Berm construction similar for new facilities.




STRAIGHT HEADWALL PLAN




SKEWED HEADWALL PLAN



ELEVATION





SECTION A-A (FOR CBC)




SECTION A-A (FOR PIPE WITH HEADWALL)

- ① Very slope. Slope shall match to top of wing wall.
- Slope shall match wing wall design slope (2:1, 4:1, or 6:1).
- ▨ Structure Backfill Limits See Std B-19.50

DESIGN APPROVED <i>James H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR CONSTRUCTION <i>Gregory A. [Signature]</i>	DITCHES, CHANNELS, DIKES AND BERMS HEADWALL BERMS	DRAWING NO. C-03.10 Sheet 5 of 5



OUTLET DETAIL




# GENERAL NOTES

- Concrete for the spillway inlet, spillway outlet shall be Class B.
- Where rock is encountered, the outlet may be omitted.
- When outlet is used, the wire mesh shall extend through the joint into the outlet in lieu of bending into the key.
- Spillway invert slope shall be uniformly downward from A to B.


DESIGN APPROVED <i>Lucretia Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Donald Sullivan</i>	SPILLWAY, EMBANKMENT	DRAWING NO. C-04.10



NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	CLARIFIED CURB TERMINUS	PHB	7/94
2			
3			
4			




SECTION A-A



SECTION ON SPILLWAY &  
DOUBLE INLET

### GENERAL NOTES


1. Concrete for the spillway inlet, spillway outlet shall be Class B.
2. Where rock is encountered, the outlet may be omitted.
3. When outlet is used, the wire mesh shall extend through the joint into the outlet in lieu of bending into the key.
4. Spillway Invert slope shall be uniformly downward from A to B.



OUTLET DETAIL


DESIGN APPROVED <i>Henry H. Ottewill</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV.  7/54
APPROVED FOR DISTRIBUTION <i>Ross D. Williams</i>	SPILLWAY, EMBANKMENT	DRAWING NO. C-0410

NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	CORRECTED SPELLING	PHB	10/95




PLAN-INLET

OUTLET DETAIL





CMP OUTLET ON ROCK




OUTLET-HEADWALL AND CONCRETE APRON

SECTION A-A




DETAIL ANCHOR

- ### GENERAL NOTES
1. Round all exposed concrete corners.
  2. Tank, stub, trash rack and angle supports shall be shop fabricated, welded and galvanized in accordance with AASHTO M 36.
  3. Stub shall be of annular corrugation. Downrain piping beyond stub may be either annular or helical corrugation.
  4. Permissible couplings shall be mechanical, heat-shrinkable polyolefin sheets; on place top type neoprene sheet or slip seam; all min 12' width and min 18 ga.
  5. Inlet invert slope shall be uniformly downward from one foot inside of embankment curb base.
  6. Inlet and outlet concrete shall be Class B. Embankment curb concrete shall be in accordance with Standard Specifications.




DETAIL TRASH RACK




DETAIL ANGLE SUPPORTS FOR TRASH RACK


DESIGN APPROVED <i>Henry H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISSEMINATION <i>Ronald C. Carlson</i>	DOWNDRAIN, EMBANKMENT	DRAWING NO. C-04.20




### PLAN-INLET




DETAIL ANCHOR




CMP OUTLET ON ROCK



OUTLET-HEADWALL  
AND CONCRETE APRON



DETAIL  
TRASH RACK



DETAIL  
ANGLE SUPPORTS  
FOR TRASH RACK

- ### GENERAL NOTES

1. Round all exposed concrete corners.
2. Tank, stub, trash rack and angle supports shall be shop fabricated, welded and galvanized in accordance with ASHTO M 36.
3. Stub shall be of annular corrugation. Downdrain piping beyond stub may be either annular or helical corrugation.
4. Permissible couplings shall be mechanical, heat-shrinkable polyethylene sheets or plate lap type neoprene sheet or slip seamy all min 12" width and min 18 ga.
5. Inlet invert slope shall be uniformly downward from one foot inside of embankment curb base.
6. Inlet and outlet concrete shall be Class B. Embankment curb concrete shall be in accordance with Standard Specifications.

# GENERAL NOTES

1. For C-02.10 slopes with embankment height over 24', use length for 24' embankment height from table + 2.24.
2. For C-02.20 slopes with embankment height over 32', use length for 32' embankment height from table + 1.8.
3. For C-02.30 slopes with embankment height over 13', use length for 13' embankment height from table + 1.8.
4. For spillway details, see Std C-04.10.

## LENGTH OF SPILLWAY


Thickness ①	Embankment Height																															
	5'	6'	7'	8'	9'	10'	11'	12'	13'	14'	15'	16'	17'	18'	19'	20'	21'	22'	23'	24'	25'	26'	27'	28'	29'	30'	31'	32'				
12"	32'	37'	43'	49'	50'	50'	51'	52'	52'	52'	53'	53'	53'	54'	54'	54'	55'	55'	56'	56'	57'	57'	58'	58'	59'	59'	60'	60'	61'			
13"	33'	38'	44'	50'	50'	50'	51'	52'	52'	53'	53'	53'	54'	54'	54'	55'	55'	56'	56'	57'	57'	58'	58'	59'	59'	60'	60'	61'	61'			
14"	33'	38'	44'	50'	51'	51'	51'	52'	52'	53'	53'	53'	54'	54'	54'	55'	55'	56'	56'	57'	57'	58'	58'	59'	59'	60'	60'	61'	61'			
15"	34'	39'	45'	51'	51'	51'	52'	52'	53'	53'	54'	54'	54'	55'	55'	56'	56'	56'	57'	57'	58'	58'	59'	59'	60'	60'	61'	61'	62'			
16"	34'	39'	45'	51'	52'	52'	53'	53'	53'	54'	54'	54'	55'	55'	56'	56'	56'	57'	57'	58'	58'	59'	59'	60'	60'	61'	61'	62'	62'			
17"	35'	40'	46'	52'	52'	53'	53'	54'	54'	55'	55'	55'	56'	56'	56'	57'	57'	57'	58'	58'	59'	59'	60'	60'	61'	61'	62'	62'	63'			
18"	35'	40'	46'	52'	53'	53'	54'	54'	55'	55'	55'	56'	56'	57'	57'	57'	58'	58'	59'	59'	60'	60'	61'	61'	62'	62'	63'	63'	63'			
19"	36'	41'	47'	53'	53'	54'	54'	55'	55'	56'	56'	57'	57'	58'	58'	58'	59'	59'	60'	60'	61'	61'	62'	62'	63'	63'	63'	63'	64'			
20"	36'	41'	47'	53'	54'	54'	55'	55'	56'	56'	56'	57'	57'	58'	58'	58'	59'	59'	60'	60'	61'	61'	62'	62'	63'	63'	64'	64'	64'			
21"	37'	42'	48'	54'	54'	55'	55'	56'	56'	57'	57'	57'	58'	58'	58'	59'	59'	60'	60'	61'	61'	62'	62'	63'	63'	64'	64'	65'	65'			
22"	37'	42'	48'	54'	55'	55'	56'	56'	57'	57'	57'	58'	58'	59'	59'	59'	60'	60'	61'	61'	62'	62'	62'	63'	63'	64'	64'	65'	65'			
23"	38'	43'	49'	55'	55'	56'	56'	57'	57'	58'	58'	58'	59'	59'	60'	60'	60'	61'	61'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
24"	38'	43'	49'	55'	56'	56'	57'	57'	58'	58'	58'	59'	59'	60'	60'	60'	61'	61'	61'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
25"	39'	44'	50'	56'	56'	57'	57'	58'	58'	59'	59'	60'	60'	61'	61'	61'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
26"	39'	44'	50'	56'	57'	57'	58'	58'	59'	59'	59'	60'	60'	61'	61'	61'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	66'	67'			
27"	40'	45'	51'	57'	57'	58'	58'	59'	59'	60'	60'	60'	61'	61'	62'	62'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
28"	40'	45'	51'	57'	58'	58'	59'	59'	60'	60'	60'	61'	61'	62'	62'	62'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
29"	41'	46'	52'	58'	58'	59'	59'	60'	60'	61'	61'	61'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
30"	41'	46'	52'	58'	59'	59'	60'	60'	61'	61'	61'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
31"	42'	47'	53'	59'	59'	60'	60'	61'	61'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
32"	42'	47'	53'	59'	60'	60'	61'	61'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
33"	43'	48'	54'	60'	60'	61'	61'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
34"	43'	48'	54'	60'	61'	61'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
35"	44'	49'	55'	61'	61'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			
36"	44'	49'	55'	61'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	62'	63'	63'	64'	64'	65'	65'	66'			

## LENGTH OF SPILLWAY

Thickness ①	Embankment Height												
	5'	6'	7'	8'	9'	10'	11'	12'	13'				
12"	22'	22'	22'	23'	23'	24'	24'	24'	25'				
13"	22'	22'	23'	23'	23'	24'	24'	24'	25'	25'	25'	25'	25'
14"	22'	23'	23'	23'	24'	24'	24'	25'	25'	26'	26'	26'	26'
15"	23'	23'	23'	24'	24'	24'	25'	25'	25'	26'	26'	26'	26'
16"	23'	23'	24'	24'	24'	25'	25'	25'	26'	26'	26'	26'	26'
17"	23'	24'	24'	24'	25'	25'	26'	26'	27'	27'	27'	27'	27'
18"	24'	24'	25'	25'	25'	26'	26'	27'	27'	27'	27'	27'	27'
19"	24'	24'	25'	25'	25'	26'	26'	27'	27'	27'	27'	27'	27'
20"	25'	25'	25'	25'	26'	26'	27'	27'	27'	28'	28'	28'	28'
21"	25'	25'	25'	26'	26'	27'	27'	28'	28'	28'	28'	28'	28'
22"	25'	25'	26'	26'	27'	27'	27'	28'	28'	28'	28'	28'	28'
23"	26'	26'	26'	26'	27'	27'	28'	28'	29'	29'	29'	29'	29'
24"	26'	26'	26'	27'	27'	28'	28'	29'	29'	29'	29'	29'	29'
25"	26'	27'	27'	27'	28'	28'	28'	29'	29'	29'	29'	29'	29'
26"	27'	27'	27'	28'	28'	28'	29'	29'	29'	30'	30'	30'	30'
27"	27'	27'	28'	28'	28'	29'	29'	29'	30'	30'	30'	30'	30'
28"	27'	28'	28'	28'	29'	29'	29'	30'	30'	30'	30'	30'	30'
29"	28'	28'	28'	29'	29'	29'	30'	30'	31'	31'	31'	31'	31'
30"	28'	28'	29'	29'	29'	30'	30'	30'	31'	31'	31'	31'	31'
31"	28'	29'	29'	29'	30'	30'	31'	31'	31'	32'	32'	32'	32'
32"	29'	29'	29'	30'	30'	30'	31'	31'	31'	32'	32'	32'	32'
33"	29'	29'	30'	30'	30'	31'	31'	31'	32'	32'	32'	32'	32'
34"	29'	30'	30'	30'	31'	31'	31'	32'	32'	33'	33'	33'	33'
35"	30'	30'	30'	31'	31'	31'	32'	32'	33'	33'	33'	33'	33'
36"	30'	30'	31'	31'	31'	32'	32'	33'	33'	33'	33'	33'	33'

C-02.10 AND C-02.20 SLOPES

C-02.30 SLOPES



DESIGN APPROVED  
*Joseph Ottaviano*  
APPROVED FOR DISTRIBUTION  
*Ronald K. Wilson*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV.  
7/94

① SPILLWAY LENGTH TABLE

DRAWING NO.  
C-04.30

LENGTH OF DOWNDRAIN

Thickness ①	Embankment Height																																	
	7'	8'	9'	10'	11'	12'	13'	14'	15'	16'	17'	18'	19'	20'	21'	22'	23'	24'	25'	26'	27'	28'	29'	30'	31'	32'								
12"	32	38	46	46	46	46	48	48	48	50	50	50	50	52	52	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58
13"	32	40	46	46	48	48	48	48	50	50	50	50	50	52	52	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58
14"	34	40	46	46	48	48	48	50	50	50	50	50	50	52	52	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58
15"	34	40	46	46	48	48	50	50	50	50	50	52	52	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58
16"	34	40	48	48	48	48	50	50	50	50	52	52	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58
17"	34	42	48	48	50	50	50	50	50	52	52	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58
18"	36	42	48	48	50	50	52	52	52	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
19"	36	42	48	48	50	50	52	52	52	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
20"	36	42	50	50	50	50	52	52	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
21"	36	44	50	50	52	52	52	52	54	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
22"	38	44	50	50	52	52	54	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
23"	38	44	50	50	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
24"	38	44	52	52	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
25"	38	46	52	52	54	54	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
26"	40	46	52	52	54	54	56	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
27"	40	46	52	52	54	54	56	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
28"	40	46	54	54	54	54	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
29"	40	48	54	54	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
30"	42	48	54	54	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
31"	42	48	54	54	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
32"	42	48	56	56	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
33"	42	50	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
34"	44	50	56	56	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
35"	44	50	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58
36"	44	50	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58	58


LENGTH OF DOWNDRAIN

Thickness ①	Embankment Height												
	5'	6'	7'	8'	9'	10'	11'	12'	13'				
12"	14'	16'	16'	16'	20'	20'	20'	20'	20'				
13"	14'	16'	16'	18'	20'	20'	20'	20'	22'				
14"	14'	16'	18'	18'	20'	20'	20'	20'	22'				
15"	14'	18'	18'	18'	20'	20'	20'	22'	22'				
16"	16'	18'	18'	18'	20'	20'	22'	22'	22'				
17"	16'	18'	18'	18'	20'	22'	22'	22'	22'				
18"	16'	18'	18'	18'	22'	22'	22'	22'	22'				
19"	16'	18'	18'	20'	22'	22'	22'	22'	24'				
20"	16'	18'	20'	20'	22'	22'	22'	24'	24'				
21"	16'	20'	20'	20'	22'	22'	24'	24'	24'				
22"	18'	20'	20'	20'	22'	22'	24'	24'	24'				
23"	18'	20'	20'	20'	22'	24'	24'	24'	24'				
24"	18'	20'	20'	20'	24'	24'	24'	24'	26'				
25"	18'	20'	20'	22'	24'	24'	24'	24'	26'				
26"	18'	20'	22'	22'	24'	24'	24'	26'	26'				
27"	18'	22'	22'	22'	24'	24'	26'	26'	26'				
28"	20'	22'	22'	22'	24'	26'	26'	26'	26'				
29"	20'	22'	22'	22'	26'	26'	26'	26'	26'				
30"	20'	22'	22'	24'	26'	26'	26'	26'	28'				
31"	20'	22'	24'	24'	26'	26'	26'	28'	28'				
32"	20'	24'	24'	24'	26'	26'	26'	28'	28'				
33"	22'	24'	24'	24'	26'	26'	28'	28'	28'				
34"	22'	24'	24'	24'	26'	28'	28'	28'	28'				
35"	22'	24'	24'	24'	28'	28'	28'	28'	28'				
36"	22'	24'	24'	26'	28'	28'	28'	28'	30'				

GENERAL NOTES

- 1. For C-02.10 slopes with embankment height over 24', use length for 24' embankment height from table + 2.24.
- 2. For C-02.20 slopes with embankment height over 32', use length for 32' embankment height from table + 1.8.
- 3. For C-02.30 slopes with embankment height over 13', use length for 13' embankment height from table + 1.8.
- 4. For downdrain details, see Std C-04.20.

C-02.10 AND C-02.20 SLOPES




C-02.30 SLOPES


NO.	REV.	DATE
1	ISSUE 015	7/94
2		
3		
4		
5		
6		
7		
8		
9		
10		

## GENERAL NOTES

1. Stub shall have annular corrugation. Downdrain piping beyond stub may be either annular or helical.
2. Couplings shall be mechanical heat-shrinkable polyolefin sheet; one piece lap type neoprene sheet or slip seam; all 12" min width and 18 ga min.
3. Maximum Q Allowable = 8 cfs  
Minimum V Allowable = 1 fps




PLAN




SECTION A-A

DESIGN APPROVED <i>Harry H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Frankie Williams</i>	① DOWNDRAIN ENERGY DISSIPATOR	DRAWING NO. C-04.50


REVISION	DESCRIPTION OF REVISION	DATE	BY
1	DELETED TYPE A CURB AND GUTTER	10/95	PME
2	REVISED GUTTER DEPRESSION	10/95	PME
3			
4			



CURB AND GUTTER  
TYPE D, D-1, D-2 & D-3




SINGLE CURB  
TYPE A & A1




CURB AND GUTTER  
TYPE B, C, B-1 & C-1

C & G TYPE	CURB HEIGHT "h"	SLOPE
B	6"	3:1
B-1	6"	3:1
C	3"	6:1
C-1	3"	6:1



CURB AND GUTTER  
TYPE G




SINGLE CURB  
TYPE G

C & G TYPE	CURB HEIGHT "h"	GUTTER WIDTH "w"	GUTTER DEPRESSION "d"
D	6"	2'-0"	1 1/2"
D-1	6"	2'-6"	1 3/4"
D-2	6"	4'-6"	1 3/4"
D-3	6"	2'-0"	N/A

See Plans

EXPANSION JOINT DETAIL



VALLEY GUTTER


## GENERAL NOTES

### SINGLE CURB AND CURB AND GUTTER


- Single curb, and curb and gutter may be constructed by the use of forms or the concrete may be extruded.
- When the pavement section slopes away from the gutter, the slope of the gutter shall match the pavement cross slope. Therefore, the gutter depression is not applicable.
- Two inch deep contraction joints shall be placed in the curb and the gutter at locations which match the joints in adjacent portland cement concrete pavement and at approximate 15 foot centers when adjacent to asphaltic concrete pavement. Joints shall be either hand tooled or sawed.
- Expansion joints shall be located at tangent points in curb returns, at structures and at maximum 60 foot intervals. The one-half inch joint filler shall extend the full depth at the concrete.
- Concrete shall be finished with a steel trowel followed by brushing with a fine brush along the length of the curb and gutter.
- All exposed edges and hand tooled joints shall be finished with a tool having a one-fourth inch radius unless a larger radius is indicated.

### EMBANKMENT CURB

- No additional finishing will be required after extrusion or removal of the forms when the curb presents a neat appearance and the surface is uniform in texture and color.
- The curb shall conform to the cross section as shown except that the horizontal dimensions shall not vary more than one-half inch.




EMBANKMENT CURB




CURB TERMINAL SECTION


DESIGN APPROVED <i>Joseph Ottoboni</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Robert Williams</i>	SINGLE CURB, CURB & GUTTER, EMBANKMENT CURB	DRAWING NO. C-05.10




**CURB AND GUTTER  
 TYPE A & D, D-1, D-2 & D-3**



**CURB AND GUTTER  
 TYPE B, C, B-1 & C-1**




**CURB AND GUTTER  
 TYPE G**



**SINGLE CURB  
 TYPE A & A1**


C & G TYPE	CURB HEIGHT "h"	SLOPE
B	6"	3:1
B-1	6"	3:1
C	3"	6:1
C-1	3"	6:1




**SINGLE CURB  
 TYPE G**

C & G TYPE	CURB HEIGHT "h"	GUTTER WIDTH "w"	GUTTER DEPRESSION "d"
A	1'	2'-0"	1"
D	1'	2'-0"	2"
D-1	1'	2'-6"	2"
D-2	1'	4'-6"	2"
D-3	1'	2'-0"	N/A

See Plans



**① EXPANSION JOINT DETAIL**



**VALLEY GUTTER**


## GENERAL NOTES

### SINGLE CURB AND CURB AND GUTTER


1. Single curb, and curb and gutter may be constructed by the use of forms or the concrete may be extruded.
2. When the pavement section slopes away from the gutter, the slope of the gutter shall match the pavement cross slope. Therefore, the gutter depression is not applicable.
3. Two inch deep contraction joints shall be placed in the curb and the gutter at locations which match the joints in adjacent portland cement concrete pavement and at approximate 15 foot centers when adjacent to asphaltic concrete pavement. Joints shall be either hand tooled or sawed.
4. Expansion joints shall be located at tangent points in curb returns, at structures and at maximum 60 foot intervals. The one-half inch joint filler shall extend the full depth at the concrete.
5. Concrete shall be finished with a steel trowel followed by brushing with a fine brush along the length of the curb and gutter.
6. All exposed edges and hand tooled joints shall be finished with a tool having a one-fourth inch radius unless a larger radius is indicated.

### EMBANKMENT CURB

1. No additional finishing will be required after extrusion or removal of the forms when the curb presents a neat appearance and the surface is uniform in texture and color.
2. The curb shall conform to the cross section as shown except that the horizontal dimensions shall not vary more than one-half inch.



**EMBANKMENT CURB**



**CURB TERMINAL SECTION**


DESIGN APPROVED <i>John H. O'Hara</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Frank C. Sullivan</i>	SINGLE CURB, CURB & GUTTER, EMBANKMENT CURB	DRAWING NO. C-0510



NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MOVED C & G TRANSITION TO C-05.12	PME	7/94
2	MOVED SIDEWALK DETAILS TO C-05.10	PME	7/94
3			
4			

## GENERAL NOTES

- See Std. C-05.10 for dimensions and other general notes.
- Expansion joint filler shall be  $\frac{1}{2}$ " bituminous type preformed expansion joint filler.
- Expansion joints shall be constructed at the end of all pours, at points of curvature, at adjoining structures, at driveways and at a maximum spacing of 50'. The expansion joint must provide for complete separation of the sidewalk from adjoining concrete.




ENTRANCE RAMP

COMPOUND CURVE RADIUS

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV 7/94
APPROVED FOR CONSTRUCTION <i>James H. Ottum</i>	①② ENTRANCE RAMP CURB AND GUTTER LAYOUT	DRAWING NO. C-05.11 Sheet 1 of 2

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE



# BARRIER TERMINATION ALTERNATE


## EXIT RAMP

DESIGN APPROVED <i>James H. Ott</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>James H. Ott</i>	EXIT RAMP CURB AND GUTTER LAYOUT	DRAWING NO. C-05.11 Sheet 2 of 2


NO	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED VIEW	PHB	7/94
2	ADDED NOTE	PHB	7/94
3	REVISED NOTE	PHB	7/94
4			

GENERAL NOTES


1. All gutter flow lines shall be constructed to an accurate grade.
2. See Slotted Drain Stds., C-13.60 and C-15.91, for curb and gutter with slotted drain.
3. See Std. C-05.10 for additional general notes and dimensions.



① PERSPECTIVE VIEW




SECTION A-A




TYPE 1 - CURB & GUTTER TRANSITION - AT RAMP TAPERS

\* Dimension may vary where exit occurs on curves, see plans




SECTION B-B




TYPE 2 - CURB & GUTTER TRANSITION

DESIGN APPROVED <i>Jerry H. Otto</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>[Signature]</i>	CURB & GUTTER TRANSITIONS	DRAWING NO. C-05.12 Sheet 1 of 3

REVISIONS		DATE
1	ADDED PERSPECTIVE VIEW	7/94
2	ADDED TYPE A TRANSITION	7/94




① PERSPECTIVE VIEW




◆ Curb height varies 0' to 7' max in depressed curb area beyond the end of barrier. See Plans for curb height.

SECTION A-A




PLAN VIEW  
TYPE 3 - CURB & GUTTER TRANSITION AT PAVED GORE




② TYPE 4 - CURB & GUTTER TRANSITION

DESIGN APPROVED <i>Amey H. Ottom</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>David M. Williams</i>	CURB & GUTTER TRANSITIONS	DRAWING NO. C-05.12 Sheet 2 of 3

NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	CHANGED TYPE A C&G TO TYPE D C&G	PHB	10/95
2			
3			
4			




TYPE 5 - CURB & GUTTER TRANSITION



TYPE 6 - CURB & GUTTER TRANSITION

DESIGN APPROVED <i>Joseph H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Donald Anderson</i>	CURB & GUTTER TRANSITIONS	DRAWING NO. C-05.12 Sheet 3 of 3


DESCRIPTION OF REVISIONS		DATE
1	ADDED TYPE 5 TRANSITION	7/94
2	ADDED TYPE 6 TRANSITION	7/94
3		
4		



Curb & Gutter  
Type B or C (Modified)  
Gutter Width = 4'-6"  
Std. C-05.10

Curb & Gutter  
Type B or C  
Std. C-05.10

① TYPE 5 - CURB & GUTTER TRANSITION




Curb & Gutter  
Type G or A  
Std. C-05.10  
See Plans

Curb & Gutter  
Type A, Std. C-05.10  
or Non-ADOT Std  
See Plans


② TYPE 6 - CURB & GUTTER TRANSITION

DESIGN APPROVED <i>Larry H. Ottman</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Robert Williams</i>	CURB & GUTTER TRANSITIONS	DRAWING NO. C-05.12 Sheet 3 of 3


NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	REVISED NOTE	7/94	PMB
2	REVISED DETAIL	7/94	PMB
3	ADDED NOTE	7/94	PMB



③ DRIVEWAY WITH SIDEWALK  
ADJACENT TO CURB



DRIVEWAY WITH SIDEWALK SETBACK




DEPRESSED CURB AT DRIVEWAY ENTRANCE

## GENERAL NOTES


1. Unless otherwise specified, driveways shall be 6 inches in depth.
- ① 2. Two inch deep transverse contraction joints shall be placed in driveways if the driveway width is over 20 feet. If the driveway thickness is greater than 6 inches, then the contraction joint depth shall be  $1/3$ , where  $T$  is the thickness of the driveway. Joints shall be either formed or sawed. Formed joints shall be finished with a tool having a  $1/4$ " radius. See sheet 2 of 2 for the Contraction Joint Detail.
- ① 3. Expansion joints shall be located between driveways and sidewalks and all abutting structures. The one-half inch joint filler shall extend the full depth of the concrete. See sheet 2 of 2 for the Expansion Joint Detail.
4. Concrete shall be finished by means of a float, then steel troweled and then broomed with a fine brush in a transverse direction.
- ④ 5. Top of curb (TC) and driveway elevations shown are in relation to the gutter, Gutter=0'.
- ④ 6. When curb heights of 6" or less are shown on plans, use dimensions shown in ( )'s.
- ④ 7. When curb heights of 7" or more are shown on plans, see plans.

## LEGEND

- Cross slope (0.01' Per Ft (Typ))\*
- Straight grade with downward slope.
- \* Maximum slope = 0.02' Per Ft.




② SECTION A-A




② SECTION B-B

DESIGN APPROVED <i>James L. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>James L. Ottum</i>	CONCRETE DRIVEWAYS & SIDEWALKS DRIVEWAYS	DRAWING NO. C-05.20 Sheet 1 of 2


REVISION	DESCRIPTION OF REVISION	DATE
1		
2		
3		
4		




SIDEWALK ADJACENT TO CURB



SIDEWALK SETBACK FROM CURB




CONTRACTION JOINT DETAIL




EXPANSION JOINT DETAIL

## GENERAL NOTES

1. Unless otherwise specified, sidewalks shall be 4 inches in depth.
2. One inch deep transverse contraction joints shall be placed in sidewalks at intervals of approximately 15 feet or at a spacing that matches adjacent curb and gutter. If the sidewalk is over 7 feet in width, a 2 inch deep longitudinal contraction joint shall be placed in the center of the sidewalk. The maximum area of sidewalk without contraction joints or scoring lines shall be approximately 36 square feet. Joints shall be either formed or sawed. Formed joints shall be finished with a tool having a  $\frac{1}{4}$ " radius.
3. Expansion joints shall be located between sidewalks and driveways and all abutting structures. Expansion joints shall match the joints in the adjacent concrete pavement or existing concrete curb and sidewalk. Maximum length of sidewalk without an expansion joint shall be 60 transverse feet. The one-half inch joint filler shall extend the full depth of the concrete.
4. Concrete shall be finished by means of a float, then steel troweled and then broomed with a fine brush in a transverse direction.
5. Sidewalks shall be constructed to a desirable width of 5 feet on major streets, a minimum width of 4 feet on residential streets or as shown on the plans.
6. Scoring lines shall be  $\frac{1}{4}$  inch in depth. They shall be placed at 5 foot spacing when the contraction joint interval is 15 feet and at 6 foot spacing when the contraction joint interval is 12 feet.



CONCRETE SIDEWALK ADJACENT TO CURB







CONCRETE SIDEWALK SETBACK FROM CURB


DESIGN APPROVED <i>James H. H. H.</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR CONSTRUCTION <i>Ronald H. H.</i>	CONCRETE DRIVEWAYS & SIDEWALKS SIDEWALKS	DRAWING NO. C-05.20 Sheet 2 of 2



NO.	DESCRIPTION OF REVISIONS	MADE AT	DATE
1	ADDED NOTES	PHS	3/94
2			
3			
4			



- ### GENERAL NOTES
- Top of curb (TC) and top of ramp elevations shown are in relation to the gutter. Gutter=0'.
  - See Std C-05.10, C-05.11 and C-05.20 for joint requirements.
  - When curb heights of 6" are shown on plans, use dimensions shown in 1/8".
  - If field modification is required, bottom width shall be 4" minimum, as per ADA requirements.
- Use type A1 curb if median is to be landscaped.




DESIGN APPROVED <i>Timothy H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 3/94
APPROVED FOR DISTRIBUTION <i>Gregory A. Hanks</i>	SIDEWALK RAMP TYPE I	DRAWING NO. C-05.30 Sheet 1 of 4


NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	MODIFIED NOTE	7/94	

## GENERAL NOTES


1. Top of curb (TC) and top of ramp elevations shown are in relation to the gutter and are located radially. Gutter=0'.
2. See Std C-05.10, C-05.11 and C-05.20 for joint requirements.
3. When curb heights of 6' or less are shown on plans, use dimensions shown in (1)'s.
- ① 4. When curb heights of greater than 7' are shown on plans, see plans and ADA requirements.




PLAN




PERSPECTIVE



ELEVATION  
DEPRESSED CURB AT SIDEWALK RAMP




SECTION A-A




GROOVE DETAIL

DESIGN APPROVED <i>Dan H. Ottensmeyer</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Road Williams</i>	SIDEWALK RAMP TYPE 2	DRAWING NO. C-05.3C Sheet 2 of 4


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED C-STR CALLOUT TO C-10.16	PHB	10/95
2			
3			
4			




## PLAN




ELEVATION  
DEPRESSED CURB AT SIDEWALK RAMP




SECTION B-B



## PERSPECTIVE



WITH RAMP CURB




WITHOUT RAMP CURB

SECTION A-A

### GENERAL NOTES



1. Top of curb (TC) elevations shown are in relation to the gutter and are located radially. Gutter=0'.
  2. See Std C-05.10, C-05.11 and C-05.20 for joint requirements.
- 161 Maximum Slope.



GROOVE DETAIL


DESIGN APPROVED <i>Long H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Frankie Williams</i>	SIDEWALK RAMP TYPE 3	DRAWING NO. C-05.30 Sheet 3 of 4

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED DIMENSION	TC	1/93
2	ADDED GROOVE DETAIL	TC	1/93
3	ADDED CURB OPTION	TC	1/93
4	ADDED GROOVES	TC	1/93




### GENERAL NOTES


1. Top of curb (TC) elevations shown are in relation to the gutter and are located radially. Gutter=0'.
  2. See Std C-05.10, C-05.11 and C-05.20 for joint requirements.
- 161 Maximum Slope.




ELEVATION  
DEPRESSED CURB AT SIDEWALK RAMP



SECTION B-B




WITH RAMP CURB



WITHOUT RAMP CURB






SECTION A-A



② GROOVE DETAIL

DESIGN APPROVED <i>Joseph Ottoboni</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV.  1/93
APPROVED FOR DISTRIBUTION <i>Chris White</i>	SIDEWALK RAMP TYPE 3	DRAWING NO. C-05-30 Sheet 3 of 4

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED NOTE	PMB	7/94
2			
3			
4			




# GENERAL NOTES


1. Top of curb (TC) and top of ramp elevations shown are in relation to the gutter. Gutter = 0'.
  2. See Std C-05.10, C-05.11 and C-05.20 for joint requirements.
  3. When curb heights of 6' or less are shown on plans, use dimensions shown in ( )s.
  - ① 4. When curb heights of greater than 7' are shown on plans, see plans and ADA requirements.
- For sidewalk widths greater than 6'-5", the overall sidewalk ramp width shall match the sidewalk width.

DESIGN APPROVED <i>Sherry H. Ottman</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR SUBMISSION <i>Ronald Williams</i>	SIDEWALK RAMP TYPE 4	DRAWING NO. C-05.30 Sheet 4 of 4


NO.	DESCRIPTION OF REVISIONS	DATE
1	ADDED LINE MEDIAN ON STRUCTURE. DETAIL ADDED NOTE	1/93
2		
3		
4		
5		




PLAN



SECTION A-A




SECTION B-B



SECTION C-C

## GENERAL NOTES

1. Traffic signal foundations, traffic sign foundations and pull boxes for traffic signs and traffic signals shall be installed prior to placement of median paving.
2. See Std C-05.10, C-05.11 and C-05.20 for joint requirements.
3. Decorative median paving shall be stamped concrete, concrete pavers or as specified on the project plans.
4. Decorative median paving shall not be placed on a median nose transition or on a median island on a structure.
5. A 4' x 6' concrete header shall be used to end decorative paving at locations when concrete sidewalk ramps are not present.
6. Median nose transitions shall not be placed on departure ends of raised medians.
7. Top of curb (TC) and top of ramp elevations shown are in relation to the gutter. Gutter=0'.
8. When curb heights of 6\"/>



NOSE TRANSITION LAYOUT


DESIGN APPROVED <i>David J. Thomas</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 1/93
APPROVED FOR DISTRIBUTION <i>David J. Thomas</i>	MEDIAN PAVING AND NOSE TRANSITION	DRAWING NO. C-05.40

C-05.50






NO.	DATE	BY	CHK'D	DATE
1	REVISION			
2				
3				
4				



R-1 = 20' Min, 30' Desirable  
R-2 = 25' Min, 40' Desirable  
R-3 = 80'  
R-4 = 20' Min  
W = 25' Min, 40' Max  
\*\* - See Proper City or County Regulation

### RURAL DEVELOPMENTS



(1) 10' Min, 20' Desirable  
(2) 15' Min  
(3) 25' Min, 40' Desirable  
(4) 40' Min  
(5) One Way Couplet for Use Only on One Way Roadways  
(6) 40' Max Joint Use Driveways  
Residential - 10' Min, 30' Max  
Commercial - One Way 15' Min, 30' Max  
Two Ways 25' Min, 40' Max  
Industrial - 20' Min, 40' Max

### URBAN DEVELOPMENTS

### GENERAL NOTES


- Driveway types:  
Residential - one providing access to a single family residence, to a duplex, or to an apartment building containing five or fewer dwelling units.  
Commercial - one providing access to an office, retail or institutional building or to an apartment building having more than five dwelling units.  
Industrial - one directly serving a substantial number of truck movements to and from loading docks of an industrial facility, warehouse or truck terminal.
- Joint use driveways may become desirable for landowners of adjacent properties to service both properties. If this is the case, only one of the two adjacent landowners need apply for the access permit, but a notarized written mutual agreement, signed by all parties involved, must accompany the application form.
- Driveways for high volume traffic generators shall be approved individually by Traffic Engineering section.
- Driveways with curb returns in urban areas shall be installed only with the approval of Traffic Engineering section.
- Driveways and depressed curbs shall be located as noted on plans or as directed by the Engineer.
- Drainage structures shall be provided under driveways where necessary.
- Dimensions indicated as minimum shall be avoided whenever possible in favor of those indicated as desirable.
- The Type 'A' turnout is the preferable turnout design. Type 'B' and 'C' shall only be used when absolutely necessary.
- Paved turnouts, plans notation, will be W X L, surface material, type and standard. Example: 20' X 30' ACTO, Type A, Std C-06.10. Show radius (R) graphically.
- Construction of curb, gutter, sidewalk and drainage facilities in urban areas by the permittee along that portion of the highway frontage under permit application, may be a stipulation of the permit approval if there appears to be reasonable need.
- Excavation or embankment for turnouts shall be included in quantities for main roadways.
- Base material shall be the same as that shown for main roadway, unless otherwise noted.
- Desirable side slope rates for rural turnouts are 6:1.

DESIGN APPROVED  
*[Signature]*  
APPROVED FOR  
DISTRIBUTION  
*[Signature]*


STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS  
DRIVEWAY & TURNOUT LAYOUTS

REV.  
7/94  
DRAWING NO.  
C-06.10  
Sheet 1 of 2


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	NOTATED DRIVEWAY BEYOND SIDEWALK	PHB	10/95
2	ADDED NOTE	PHB	10/95
3			
4			



URBAN CROSS SECTION  
(UP GRADE)




URBAN CROSS SECTION  
(DOWN GRADE)




DESIRABLE URBAN CROSS SECTION

# GENERAL NOTES

- Grade as shown on plans or as negotiated between Property Owner and Engineer.
- When field conditions require modifications to plans, contact Design Engineer for assistance.
- See Sheet 1 of 2 for all other General Notes.
- Breakangle greater than 6% requires a vertical curve, L=10' Min. Vertical curve shall not encroach on roadway or sidewalk.




CONCRETE SIDEWALK  
(UP GRADE)




CONCRETE SIDEWALK  
(DOWN GRADE)

DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>David M. Williams</i>	DRIVEWAY & TURNOUT LAYOUTS	DRAWING NO. C-06.10 Sheet 2 of 2


REV.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED DRIVEWAY WIDTH	PHB	7/94
2			
3			



URBAN CROSS SECTION  
(UP GRADE)




URBAN CROSS SECTION  
(DOWN GRADE)




DESIRABLE URBAN CROSS SECTION

## GENERAL NOTES

1. Grade as shown on plans or as negotiated between Property Owner and Engineer.
  2. When field conditions require modifications to plans, contact Design Engineer for assistance.
  3. See Sheet 1 of 2 for all other General Notes.
- ① Breakangle greater than 6% requires a vertical curve, L=(10' Min). Vertical curve shall not encroach on roadway or sidewalk.




CONCRETE SIDEWALK  
(UP GRADE)



CONCRETE SIDEWALK  
(DOWN GRADE)

DESIGN APPROVED <i>Joseph H. Ottman</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Frank J. Allen</i>	DRIVEWAY & TURNOUT LAYOUTS	DRAWING NO. C-06.10 Sheet 2 of 2


NO.	DESCRIPTION OF REVISION	DATE	BY
1	ADDED NOTE	7/94	
2	REVISED NOTE	7/94	
3			
4			



NOTE:  
Dimensions - angular and distance - used on drawing above are exemplary. 70 mph design speed was used. Refer to table for basic design information.

### GENERAL NOTES

- Detour 'A' entrance shall be used where an approaching vehicle must turn left. Detour 'B' shall be used where an approaching vehicle must turn right.
- Detour from a horizontal curve: On the inside of the curve the detour take off shall be a curve, see table. On the outside a tangent take off shall be used. A vertical curve may be required to effect a smooth grade change.
- The design speed shall be comparable between vertical and horizontal alignment.
- The entrance design speed of a detour shall not be less than the normal posted speed of the existing roadway. The design speed for the remainder of the detour may be 20 mph less than the normal posted speed.
- Any intermediate detour entrance may be designed on the basis of normal posted speed less 20 mph where visible construction activity has slowed traffic for the preceding 1/4 mile.
- The minimum width of the detour shall be 28' for existing roadway 34' or wider and a minimum of 24' for existing roadways less than 34' in width.
- The entrance taper for Detour 'A' shall be extended until full detour width is attained. For Detour 'B' the entrance taper shall be extended until a minimum of 14' is attained beyond the edge of existing roadway.
- Any deviation from this standard must be approved by the Plans Engineer and Traffic Engineer and the Engineer shall submit the alignment and profile of the proposed change for their review.
- Native material used in constructing the detour embankment will be considered suitable for backfill around pipe; however, it shall be reasonably free of rocks and debris.



### SPECIAL DETOUR SECTION

TANGENT ROADWAY	
Entrance Design Speed	Entr. Taper Defil. Angle
70	3°
60	3°
50	4°
40	6°
30	10°


CURVED ROADWAY		
Exist. Horiz. Curve	Detour 'A' Take off Curve	Detour 'B' Take off Curve
1°	2°	2° 30'
2°	3°	3° 30'
3°	4°	5°
4°	5°	6°
5°	6°	7°
6°	7°	8°
7°	8°	9°
8°	9°	10°

MAXIMUM HORIZONTAL CURVATURE				
Entrance Design Speed	Curve No. I		Curve No. II*	
	D	Superelev.	D	Superelev.
70	3°	.09'/ft.	3°	.08'/ft.
60	3°	.08'/ft.	4°	.05'/ft.
50	4°	.07'/ft.	6°	.05'/ft.
40	6°	.07'/ft.	10°	.05'/ft.
30	10°	.07'/ft.	19°	.05'/ft.


DESIGN APPROVED <i>Henry H. Ott</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Robert L. Blum</i>	GEOMETRICS, DETOUR	DRAWING NO. C-06.20

Deleted 10/95


NO.	DESCRIPTION OF REVISIONS	DATE	BY	DATE	DESCRIPTION OF REVISIONS	DATE	BY	DATE
1	CHANGED TO EPOXY COATED SMOOTH DOWELS/MODIFIED NOTE	1/83	DES	1/83	1	MODIFIED JOINT DEPTH	TC	1/83
2	MODIFIED JOINT WIDTH	1/83	DES	1/83	2	MODIFIED RECESS OF JOINT SEALANT	TC	1/83
3	ADDED NON-SKEWED TC JOINT	1/83	DES	1/83	3	MODIFIED DETAIL	TC	1/83
4	MODIFIED NOTE	1/83	TC	1/83	4	MODIFIED DIMENSIONS	TC	1/83



LONGITUDINAL WEAKENED PLANE JOINT  
LWP Joint




TRANSVERSE WEAKENED PLANE JOINT  
TWP Joint  
w/o Load Transfer Dowel Assemblies




LONGITUDINAL CONSTRUCTION JOINT  
LC Joint


- ### GENERAL NOTES
- When load transfer dowel assemblies are required, use dimensions shown in (1)s. See Assembly Placement and Edge Clearance Detail, Std C-07.02.
  - In slab form type pavement construction, LWP joints shall be used; in fixed form construction either LWP or LC joints may be used.
  - Same as weakened plane joint detail, except initial saw cut will not be required.




TRANSVERSE CONSTRUCTION JOINT  
TC Joint  
Skewed Joint




EXPANSION JOINT  
E Joint




EXPANSION JOINT  
H Joint



③ TRANSVERSE CONSTRUCTION JOINT  
TC Joint  
Non-Skewed Joint



AC/PCCP EDGE SEAL JOINT  
S Joint




⑦ WEAKENED PLANE JOINT DETAIL

DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 1/93
APPROVED FOR DISTRIBUTION <i>[Signature]</i>	PCCP JOINTS	DRAWING NO. C-07.01 Sheet 1 of 2


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED DETAIL TO SHOW ALL PCCP	PHB	3/94
2	REVISED DETAIL TO SHOW AC PCCP	PHB	3/94
3	DELETED EXPANSION MATERIAL	PHB	3/94
4	ADDED NOTE ON PAVEMENT SLOPE	PHB	3/94

## GENERAL NOTES


- ④ 1. Joints are generally shown with pavement sloping toward the joint. Joints are similar with pavement sloping away from the joint.




**CURB & GUTTER JOINT**  
C Joint



**HALF BARRIER JOINT**  
B Joint



① **MEDIAN BARRIER JOINT**  
B Joint  
PCCP On Both Sides of Barrier




② **MEDIAN BARRIER JOINT**  
B Joint  
AC Pavement On Back Side of Barrier

## JOINT ABBREVIATIONS


G - Gutter Joint  
T - PCCP Thickness  
D - Gutter Thickness  
B - Barrier Joint

DESIGN APPROVED <i>James H. Ottensmeyer</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>Gregory J. Hest</i>	PCCP JOINTS	C-07.01 Sheet 2 of 2


NO.	DESCRIPTION OF REVISION	DATE
1	CHANGED FROM SKETCH TO NEW LAYOUT	1/93
2	MODIFIED DIMENSIONS/RELATED QUANTITY TABLE	1/93
3	MODIFIED DIMENSION	1/93




ISOMETRIC VIEW  
LOAD TRANSFER DOWEL ASSEMBLY




① PLAN VIEW  
LOAD TRANSFER DOWEL ASSEMBLY




ASSEMBLY PLACEMENT AND EDGE CLEARANCE DETAIL



ANCHOR STRAP DETAIL



END AND INTERMEDIATE LEG DETAIL



TRANSVERSE WEAKENED PLANE JOINT WITH  
LOAD TRANSFER DOWEL ASSEMBLY

	DIMENSION TABLE		
	Lane Width		
	12'	14'	16'
①	10'-4"	12'-4"	14'-4"

## GENERAL NOTES

1. Load transfer dowel assemblies shall be used with non-skewed PCCP joints.
2. Load transfer dowel assemblies are to be placed at each transverse weakened plane joint on the traveled lanes as shown on the plans.
3. See Std C-07.01 thru C-07.05 for additional information.
4. See plans or Std C-07.03 thru C-07.05 for transverse joint spacing.
5. See plans for pavement thickness less than 12" or greater than 14".

Load transfer dowel assembly shall be assembled from the following materials.  
(See Quantity Table)


- ① Dowel bars - 1 1/2" dia x 1'-6" plain round bars w/coating. See Special Provisions.
- ② Intermediate legs - 2 Ga or W-5.5 wire.
- ③ End legs - 2 Ga or W-5.5 wire.
- ④ Upper space bar - 2 Ga or W-5.5 wire x ①. (See Dimension Table)
- ⑤ Lower space bar - 2 Ga or W-5.5 wire x ①. (See Dimension Table)
- ⑥ Tie bars - W-1.5 wire x 15".
- ⑦ Anchor straps - 1'x3' steel strap, 0.079 thick. Place with 1-1/2" min steel nail for LCB, 4" min steel nail for ACB or AB, 0.145 dia ASTM A227 Class 1 w/1/4" head or washer to be power driven.

②


Item No.	QUANTITY TABLE		
	Lane Width		
	12'	14'	16'
①	11	13	15
②	18	22	26
③	4	4	4
④	2	2	2
⑤	2	2	2
⑥	5	6	7
⑦	10	12	14

DESIGN APPROVED	STATE OF ARIZONA	REV.
<i>David H. Hines</i>	DEPARTMENT OF TRANSPORTATION	1/93
APPROVED FOR DISTRIBUTION	DIVISION OF HIGHWAYS	
<i>August Hines</i>	STANDARD DRAWINGS	
LOAD TRANSFER DOWEL ASSEMBLY		C-07.02


1	MODIFIED NOTE	LOCATION OF REVISION	DATE
2	ADDED NOTE	TC	1/93
3			
4			




PLAN  
46' PCCP




PLAN  
43.5' PCCP



PLAN  
36' PCCP



PLAN  
24' PCCP



PLAN  
24' PCCP  
(Widening)


### GENERAL NOTES

1. Skewed PCCP joints shall be used when load transfer dowel assemblies are not required.
  2. \*A\* shall equal 4' minimum (typical).  
\*B\* shall equal 3' minimum (typical).  
\*C\* shall equal 2' minimum (typical).
  3. See Std C-07.01 for PCCP joints and additional notes.
  4. All transverse joints shall be in line with joints in adjacent slabs.
  5. See Std C-05.10 for curb and gutter joint requirements.
  6. At intersection of side roads or streets, joints shall be placed to give the intersection a symmetrical appearance while conforming to the cross section of the intersecting road or street.
  7. The reinforcing bars in the LWP & LC joints shall be placed no greater than 1'-3" from the TC joint.
- Transverse Construction Joint (TC) allowable limits (Typ).


DESIGN APPROVED	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 1/93
APPROVED FOR DISTRIBUTION	MAINLINE PCCP JOINT LOCATIONS SKEWED JOINTS	DRAWING NO. C-07.03 Sheet - of 8



DESCRIPTION OF REVISIONS	DATE	BY



PLAN  
58' PCCP



PLAN  
55.5' PCCP

### GENERAL NOTES

1. Skewed PCCP joints shall be used when load transfer dowel assemblies are not required.
  2. "A" shall equal 4' minimum (typical),  
"B" shall equal 3' minimum (typical)  
"C" shall equal 2' minimum (typical)
  3. See Std C-07.01 for PCCP joints and additional notes.
  4. All transverse joints shall be in line with joints in adjacent slabs.
  5. See Std C-05.10 for curb and gutter joint requirements.
  6. At intersection of side roads or streets, joints shall be placed to give the intersection a symmetrical appearance while conforming to the cross section of the intersecting road or street.
  7. The reinforcing bars in the LWP & LC joints shall be placed no greater than 1'-3" from the TC joint.
- Transverse Construction Joint (TC) allowable limits (Typ).

DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	1/93
APPROVED FOR DISTRIBUTION <i>[Signature]</i>	MAINLINE PCCP JOINT LOCATIONS SKEWED JOINTS	DRAWING NO. C-07.03 Sheet 2 of 8

Direction of Pair & Traffic

TO PCCP

10'

12'

12'

12'

12'

12'

2' (Typ)

15'

13'

15'

17'

60' max

Repeat Sequence

Typical Joint Sequence (TWP Joints)

LWP

LC

LWP

LC

LWP

TWP (Typ)

S

'B'

'A'

'A'

'B'

'A'

'C'

'B'

'A'

'C'

'B'


'A'

'C'

'B'


'A'

AC Shoulder







NO.	DESCRIPTION & REVISIONS	DATE
1		
2		
3		




PLAN  
46' PCCP




PLAN  
43.5' PCCP



PLAN  
36' PCCP



PLAN  
24' PCCP




PLAN  
24' PCCP  
(Widening)

### GENERAL NOTES


1. Non-skewed PCCP joints shall be used with load transfer dowel assemblies.
2. See Std C-07.01 for PCCP joints and additional notes.
3. All transverse joints shall be in line with joints in adjacent slabs and are perpendicular (90°) to the longitudinal joints.
4. At intersection of side roads or streets, joints shall be placed to give the intersection a symmetrical appearance while conforming to the cross section of the intersecting road or street.
5. See Std C-05.10 for curb and gutter joint requirements.
6. The reinforcing bars in the LWP & LC joints shall be placed no greater than 1'-3" from the LC joint.
7. Transverse weakened plane joint shall be constructed at least 6'-0" from a transverse construction joint.

DESIGN APPROVED <i>Luigi A. M...</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	1/93
APPROVED FOR DISTRIBUTION <i>Luigi A. M...</i>	MAINLINE PCCP JOINT LOCATIONS NON-SKEWED JOINTS	DRAWING NO. C-07.03 Sheet 5 of 8

REVISION	DESCRIPTION OF REVISIONS	MADE BY	DATE



PLAN  
58' PCCP




PLAN  
55.5' PCCP

### GENERAL NOTES


1. Non-skewed PCCP joints shall be used with load transfer dowel assemblies.
2. See Std C-07.01 for PCCP joints and additional notes.
3. All transverse joints shall be in line with joints in adjacent slabs and are perpendicular (90°) to the longitudinal joints.
4. At intersection of side roads or streets, joints shall be placed to give the intersection a symmetrical appearance while conforming to the cross section of the intersecting road or street.
5. See Std C-05.10 for curb and gutter joint requirements.
6. The reinforcing bars in the LWP & LC joints shall be placed no greater than 1'-3" from the TC joint.
7. Transverse weakened plane joint shall be constructed at least 6'-0" from a transverse construction joint.

DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	1/93
APPROVED FOR DISTRIBUTION <i>[Signature]</i>	MAINLINE PCCP JOINT LOCATIONS NON-SKEWED JOINTS	DRAWING NO. C-07.03 Sheet 5 of 8

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE



PLAN  
70' PCCP




PLAN  
67.5' PCCP


### GENERAL NOTES

1. Non-skewed PCCP joints shall be used with load transfer dowel assemblies.
2. See Std C-07.01 for PCCP joints and additional notes.
3. All transverse joints shall be in line with joints in adjacent slabs and are perpendicular (90°) to the longitudinal joints.
4. At intersection of side roads or streets, joints shall be placed to give the intersection a symmetrical appearance while conforming to the cross section of the intersecting road or street.
5. See Std C-05.10 for curb and gutter joint requirements.
6. The reinforcing bars in the LWP & LC joints shall be placed no greater than 1'-3" from the LC joint.
7. Transverse weakened plane joint shall be constructed at least 6'-0" from a transverse construction joint.


DESIGN APPROVED	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	1/93
APPROVED FOR DISTRIBUTION	MAINLINE PCCP JOINT LOCATIONS NON-SKEWED JOINTS	DRAWING NO. C-07.03 Sheet 1 of 8



PLAN  
96.25' PCCP



PLAN  
84.25' PCCP




PLAN  
72.25' PCCP

### GENERAL NOTES


1. Non-skewed PCCP joints shall be used with load transfer dowel assemblies.
2. See Std C-07.01 for PCCP joints and additional notes.
3. All transverse joints shall be in line with joints in adjacent slabs and are perpendicular (90°) to the longitudinal joints.
4. At intersection of side roads or streets, joints shall be placed to give the intersection a symmetrical appearance while conforming to the cross section of the intersecting road or street.
5. See Std C-05.10 for curb and gutter joint requirements.
6. The reinforcing bars in the LWP & LC joints shall be placed no greater than 1'-3" from the TC joint.
7. Transverse weakened plane joint shall be constructed at least 5'-0" from a transverse construction joint.

NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	REVISED DISTANCE, MOVES BACK OF JOINT	PHB	10/95
2	MODIFIED NOTE	PHB	10/95
3	DELETED REFERENCE TO RAMP CONTROL POINT	PHB	10/95




RAMP TERMINAL AT CROSSROAD

② Ramp joint spacing sequence. See Ramp Terminal At Crossroad Detail Std. C-07.04 and C-07.05




TYPICAL TRANSVERSE WEAKENED PLANE JOINT LAYOUT AT GORE AREAS

- ### GENERAL NOTES
- Dimensions with a tolerance may be adjusted to align to the nearest transverse weakened plane construction joint as directed.
  - See Std C-07.01 for Joint Information.
  - See plans for ramp dimensions.
  - See Std C-07.05 for Sections A-A and B-B.
  - The ratio of transverse to longitudinal joint spacing shall be greater than  $\frac{2}{3}$  but not more than  $\frac{1}{2}$ .
  - Ramp transverse joints shall be perpendicular (90°) to the ramp longitudinal joints, except as shown at the ramp terminal.
- ▲ 6' Minimum
  - Varies - 18' Minimum 11' Minimum
  - Transition, See Std C-05.12
  - Without Curb & Gutter
- ① 12' Face of Curb to Face of Curb
  - ① Mainline Structure Section, See Plans
  - ② Ramp Structure Section, See Plans
  - ③ Gore Structure Section, See Std C-08.20



RAMP WITHOUT CURB AND GUTTER




RAMP WITH CURB AND GUTTER


DESIGN APPROVED <i>Henry H. Ottensm</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Frederick W. Hillman</i>	ENTRANCE RAMP PCCP JOINTS	DRAWING NO. C-07.04



1. EXTENDED L.C. JOINT TAPER RAMP TAPER	TC	1/93
2. MODIFIED NOTE	TC	1/93
3. ADDED E JOINT	TC	1/93
4.		



RAMP TERMINAL AT CROSSROAD




TYPICAL TRANSVERSE WEAKENED PLANE JOINT LAYOUT AT GORE AREAS

*Mastic Problem with joint & dowels*

# GENERAL NOTES

1. Dimensions with a tolerance may be adjusted to align to the nearest transverse weakened plane construction joint as directed.
  2. See Std C-07.01 for Joint Information.
  3. See plans for ramp dimensions.
  4. See Std C-07.05 for Sections A-A and B-B.
  5. The ratio of transverse to longitudinal joint spacing shall be greater than  $\frac{1}{3}$  but not more than  $1\frac{1}{2}$ .
  6. Ramp transverse joints shall be perpendicular (90°) to the ramp longitudinal joints, except as shown at the ramp terminal.
- ▲ 6' Minimum
  - Varies - 18' Maximum  
11' Minimum
  - Transition, See Std C-05.12
  - Without Curb & Gutter
  - ③ 20' Face of Curb to Face of Curb
  - ① Mainline Structure Section, See Plans
  - ② Ramp Structure Section, See Plans
  - ③ Gore Structure Section, See Std C-08.20




RAMP WITH CURB AND GUTTER


DESIGN APPROVED <i>David L. Thomas</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 1/93
APPROVED FOR DISTRIBUTION <i>Gregory H. Moore</i>	ENTRANCE RAMP PCCP JOINTS	DRAWING NO. C-07.04

DRAWING NO.	C-07.05
-------------	---------


NO.	DESCRIPTION OF REVISIONS	DATE
1	MODIFIED JOINT REQUIREMENTS	1/82
2	MODIFIED JOINT	1/81




RAMP TERMINAL AT CROSSROAD



SECTION A-A  
RAMP TAPER




① RAMP WITH CURB AND GUTTER



① RAMP WITHOUT CURB AND GUTTER

GENERAL NOTES


- See Std C-07.04 for General Notes and Transverse Joint Layout at Gore Areas.
- Without Curb & Gutter
- 6' Minimum
- Varies - 18' Maximum 11' Minimum
- 20' Face of Curb to Face of Curb
- Transition, See Std C-05.12
- Mainline Structure Section, See Plans
- Ramp Structure Section, See Plans
- Gore Structure Section, See Std C-06.20




SECTION B-B  
GORE AREA

DESIGN APPROVED	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 1/93
APPROVED FOR DISTRIBUTION	EXIT RAMP PCC JOINTS	DRAWING NO. C-07.05


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED NOTE	AME	10/95
2			
3			
4			




TYPE A




TYPE B




TYPE C




TYPE D




TYPE E



TYPE F



TYPE G



TYPE H


## GENERAL NOTES

1. Bedding per Section 501 of the Standard Specifications.
2. Asphalt concrete shall be in accordance with the requirements of the Standard Specifications.
3. 12" llp is required on the sides of trenches that are not parallel at the center line of the street.
4. Types D & E require 5" of AB at top of trench when there is an existing base.
5. See Standard Drawing C-13.15 for Typical pipe installation.

## LEGEND



Compacted Backfill  
Density Per Section 501









AB, Granular Backfill or Native  
Backfill Per Section 302-2 and 501



AB Per Section 303-2 and 501

DESIGN APPROVED	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION	TRENCH BACKFILL AND PAVEMENT REPLACEMENT	DRAWING NO. C-07.06

NO.	DESCRIPTION OF REVISIONS	DATE
1	REARRANGED SIZES	
2		
3		



## GENERAL NOTES

1. Bedding per Section 501.
2. Asphalt concrete shall be in accordance with the requirements of the Standard Specifications.
3. 12" 1p is required on the sides of trenches that are not parallel at the center line of the street.
4. Types D & E require 9" of AB at top of trench when there is an existing base.
5. See Standard Drawing C013.15 for Typical pipe installation.

## LEGEND


	Compacted Backfill Density Per Section 501
	AB, Granular Backfill or Native Backfill Per Section 302-2 and 501
	AB Per Section 303-2 and 501

DESIGN APPROVED <i>Henry H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>R. Anderson</i>	① TRENCH BACKFILL AND PAVEMENT REPLACEMENT	DRAWING NO. C-07.06

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE

## GENERAL NOTES

1. See Std C-07.01 for joint information.
  2. See plans for crossroad dimensions.
  3. See Std C-07.04 and C-07.05 for ramp joints.
  4. The ratio of transverse to longitudinal joint spacing shall be greater than  $\frac{2}{3}$  but not more than  $1\frac{1}{2}$ .
  5. Transverse joints shall be perpendicular (90°) to the longitudinal joints, except as shown at the ramp terminal.
- ▲ 6' Minimum
  - Varies - 18' Maximum  
8' Minimum
  - Varies - 12' when adjacent gutter widths are 2' or less.  
- 15' when adjacent gutter widths are greater than 2'.




CROSSROAD AT RAMP TERMINAL

DESIGN APPROVED <i>[Signature]</i> APPROVES FOR DISTRIBUTION <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
	CROSSROAD PCCP JOINTS	DRAWING NO. C-07.10


1. REVISIONS	DATE
2. REVISIONS	DATE
3. REVISIONS	DATE
4. REVISIONS	DATE
5. REVISIONS	DATE
6. REVISIONS	DATE
7. REVISIONS	DATE
8. REVISIONS	DATE
9. REVISIONS	DATE
10. REVISIONS	DATE

## GENERAL NOTES


1. For paved gore area details, see Std C-08.20.
2. Parallel deceleration is to be used only under special conditions necessitating ramp curvature ahead of nose.
3. The 50ft taper and corresponding offsets shall also apply when the main roadway has curvature or combined tangent and curvature.
  - Normal to ramp.
  - Distance normal to main roadway construction centerline.



EXIT RAMP



EXIT RAMP




ENTRANCE RAMP

DESIGN APPROVED	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION	RAMP GEOMETRICS	DRAWING NO. C-08.10


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED CURVE CALLOUT	PMB	7/94

# GENERAL NOTES


- For paved gore area details, see Std C-08.20.
- Parallel deceleration is to be used only under special conditions necessitating ramp curvature ahead of nose.
- The 50:1 taper and corresponding offsets shall also apply when the main roadway has curvature or combined tangent and curvature.
  - Normal to ramp.
  - \*\* Distance normal to main roadway construction centerline.



EXIT RAMP




EXIT RAMP



ENTRANCE RAMP


DESIGN APPROVED <i>Joseph H. Ottman</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Allen</i>	RAMP GEOMETRICS	DRAWING NO. C-08.10






PLAN

CONCRETE GORE AREA  
WITH ABUTTING CONCRETE PAVEMENT



PLAN

CONCRETE GORE AREA  
WITH ABUTTING AC PAVEMENT




PLAN


ASPHALTIC CONCRETE GORE AREA  
WITH ABUTTING AC PAVEMENT

# GENERAL NOTES


1. Paved gore area shall be Class S Concrete,  $f'_c = 4000$  psi or asphaltic concrete as called for on plans.
2. See Std. C-07.01 and C-07.04 for joint layout and details.



SECTION A-A




SECTION B-B



SECTION C-C


DESIGN APPROVED	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV.
APPROVED FOR CONSTRUCTION		10/95
	PAVED GORE AREA	DRAWING NO. C-08.20

REVISION	DESCRIPTION OF REVISIONS	DATE
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		




PLAN

### CONCRETE GORE AREA WITH ABUTTING CONCRETE PAVEMENT



PLAN

### CONCRETE GORE AREA WITH ABUTTING AC PAVEMENT




PLAN


### ASPHALTIC CONCRETE GORE AREA WITH ABUTTING AC PAVEMENT

### GENERAL NOTES


1. Paved gore area shall be Class S Concrete,  $f_c = 4000$  psi or asphaltic concrete as called for on plans.
2. See Std. C-07.01 and C-07.04 for joint layout and details.



SECTION A-A




SECTION B-B




SECTION C-C

DESIGN APPROVED <i>Henry H. Ottelmeier</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISSEMINATION <i>R. M. ...</i>	① PAVED GORE AREA	DRAWING NO. C-08.20


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
①	REVISED DETAIL	PMB	3/95
②	ADDED DETAIL	PMB	3/95
③	REVISED NOTE	PMB	3/95
④	REVISED PIPE TO 2" INSIDE DIAMETER	PMB	3/95




STEEL DRUM DETAIL




② TYPICAL SHOULDER GROOVING PLAN FOR UNDIVIDED HIGHWAYS




② TYPICAL SHOULDER GROOVING PLAN FOR DIVIDED HIGHWAYS



① RAMP EXCEPTION DETAIL  
ENTRANCE RAMP SIMILAR



② LEFT SHOULDER GROOVING DETAIL FOR DIVIDED HIGHWAYS  
TYPICALLY 4' WIDE




① RIGHT SHOULDER GROOVING DETAIL  
SHOULDERS 6' AND WIDER

## GENERAL NOTES


- Shoulder Grooving shall be applied to the shoulders of rural highways when called for on the Plans in accordance with the following shoulder widths:  
Undivided Highways - Shoulder 6' and greater  
Divided Highways - Right shoulders 6' and greater  
Left shoulders 4' and greater
- Shoulder Grooving shall be omitted across principal intersecting roadways or other interruptions in normal shoulder width as directed by the Engineer.
- Shoulder Grooving shall be constructed by making indentations in the asphaltic concrete.  
The indentations may be formed by rolling the hot asphalt concrete with a roller to which half segments of 2" inside diameter pipe have been welded to the drum. The pipe segments shall be 2' long and spaced at approximate 8' centers.
- Each roller shall be equipped with an acceptable guide that extends in front of the roller and is clearly visible to the operator in order that proper alignment of the completed scored shoulder is obtained.
- The contractor may utilize other equipment or methods to construct the shoulder grooving if approved by the Engineer.

DESIGN APPROVED <i>Larry H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 3/95
APPROVED FOR CONSTRUCTION <i>Frank Williams</i>	GROOVING FOR BITUMINOUS SHOULDERS	DRAWING NO. C-0910

REV	DESCRIPTION OF REVISIONS	DATE BY	CHK
1	COMBINED & REVISED SECTIONS	PMB	7/94
2	REVISED NOTE	PMB	7/94
3	ADDED NOTE	PMB	7/94
4	REVISED END OF CURB	PMB	7/94



PLAN




SECTION

TYPE A GUARD RAIL INSTALLATION

## GENERAL NOTES


1. All embankment curb shall be protected by guard rail.
2. Guard rail shall extend beyond the limits of embankment curb.
3. See Std. C-10.03 for measurement limits.
4. See Standard Specifications for spacing of reflector tabs.




REFLECTOR TAB DETAIL

DESIGN APPROVED <i>Joseph H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Robert M. Williams</i>	TYPE A GUARD RAIL INSTALLATION, REFLECTOR TAB	DRAWING NO. C-10.01

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	COMBINED & REVISED SECTIONS	PMB	7/94
2	REVISED NOTE	PMB	7/94
3	ADDED NOTE	PMB	7/94
4	REVISED END OF CURB	PMB	7/94



PLAN




SECTION

TYPE B GUARD RAIL INSTALLATION

## GENERAL NOTES

1. All embankment curb shall be protected by guard rail.
2. Guard rail shall extend beyond the limits of embankment curb.
3. See Std. C-10.03 for measurement limits.
4. See Standard Specifications for spacing of reflector tabs.



REFLECTOR TAB DETAIL


DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Forrest Williams</i>	TYPE B GUARD RAIL INSTALLATION, REFLECTOR TAB	DRAWING NO. C-10.02

NO.	DESCRIPTION OF REVISION	DATE BY	REV.
1	CHANGED TEXT	PHB	10/95
2	REVISED DIMENSIONS	PHB	10/95
3	ADDED TITLES	PHB	10/95
4	ADDED CALLOUTS	PHB	10/95


## GENERAL NOTES

- Length shall be as shown unless otherwise indicated on project plans.
- Post type (Timber or Steel) for transitions shall match post type of adjoining guard rail.

*Fix-Notes to cover half barrier footings.*



① HALF BARRIER TRANSITIONS




② BRIDGE BARRIER TRANSITIONS  
With Concrete Barrier Transitions  
Constructed on Top of Wingwalls

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Robert A. ...</i>	MEASUREMENT LIMITS FOR W BEAM AND THRIE BEAM SYSTEM	DRAWING NO. C-10.03 Sheet 1 of 2

NO.	DESCRIPTION OF REVISIONS	DATE	BY	NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	REARRANGED STD. & ADDED DEPARTURES	PMB	7/94	1	CHANGED MEASUREMENT FROM LIN. FT. TO EACH	PMB	7/94
2	CHANGED BRACKET ANCHOR TO NESTED	PMB	7/94	2	REVISED NOTE	PMB	7/94
3	CHANGED RAIL TO SET	PMB	7/94				
4	ADDED TRANSITION TO BRIDGE	PMB	7/94				

## GENERAL NOTES

- Length shall be as shown unless otherwise indicated on project plans.
- Post type (Timber or Steel) for transitions shall match post type of adjoining guard rail.



DESIGN APPROVED  
*Joseph A. Ottaviano*  
APPROVED FOR  
DISTRIBUTION  
*Ronald Williams*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS


REV.  
7/94

① MEASUREMENT LIMITS FOR  
W BEAM AND THRIE BEAM SYSTEM


DRAWING NO.  
C-10.03  
Sheet 1 of 2

REV	DESCRIPTION OF REVISIONS	DATE BY	DATE
1	DELETED MEDIAN BARRIER TRANSITION	PHB	1/94
2	ADDED DEPARTURE	PHB	1/94
3			
4			

①



THRIE BEAM BRIDGE RETROFIT



BRIDGE DADO RETROFIT


DESIGN APPROVED <i>James H. Ottensmeyer</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	MEASUREMENT LIMITS FOR W BEAM AND THRIE BEAM SYSTEM	DRAWING NO. C-10,03 Sheet 2 of 2




DESCRIPTION OF REVISIONS	MADE BY	DATE
1. REVISED CALLOUT FORMS	PHB	10/95
2. REVISED GUTTER DEPRESSION	PHB	10/95
3. ADDED RAIL RAIL	PHB	10/95
4. MOVED LOCATION OF CURB & GUTTER TRANSITION	PHB	10/95

## GENERAL NOTES


- See plans and barrier summary sheets for location and type of guardrail. Timber post installation shown.
- See Construction Standard Drawings C-05.10, 05.12, 10.01, and 10.02 for dimensions and details not shown.
- Type B guard rail installation shown. For Type A guard rail installation, use Type D-1 Curb and Gutter instead of the Type D-2 Curb and Gutter shown. For Type A guard rail installation, flare the Guard Rail Extruder terminal as per Standard Drawing C-10.41.
- See Plans for type and location of drainage facilities.
- Bituminous joint filler ( $\frac{1}{2}$ ") shall be placed where the curb & gutter or concrete widening abuts slotted drains, catch basins, dadas, barrier, etc. Scored joints in PCCP or at 15 ft intervals where adjacent to AC or continuously reinforced concrete pavement.



SECTION A-A



SECTION B-B




## PLAN

① TYPICAL HALF BARRIER TERMINAL  
W/TYPE B OR C CURB & GUTTER


DESIGN APPROVED <i>Timothy Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Howard Callahan</i>	HALF BARRIER TERMINAL W/TYPE B OR C CURB & GUTTER	DRAWING NO. C-10.06

# GENERAL NOTES


1. See plans and barrier summary sheets for location and type of guardrail, timber post installation shown.
2. See Construction Standard Drawings C-05.10, 05.12, 10.01, and 10.02 for dimensions and details not shown.
3. Type B guard rail installation shown. For Type A guard installation, use Type D-1 Curb and Gutter instead of the type D-2 Curb and Gutter shown.
4. See Plans for type and location of drainage facilities.
5. Bituminous joint filler (1/2") shall be placed where the curb & gutter or concrete widening abuts slotted drains, catch basins, dados, barriers, etc. Two inch (2") deep scored joints shall be placed to match adjacent joints in PCCP or at 15 ft intervals where adjacent to AC or continuously reinforced concrete pavement.



SECTION A-A



SECTION B-B




PLAN  
TYPICAL HALF BARRIER TERMINAL  
W/TYPE B OR C CURB & GUTTER

DESIGN APPROVED <i>Henry H. Ottensmeyer</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>Ronald H. Williams</i>	HALF BARRIER TERMINAL W/TYPE B OR C CURB & GUTTER	DRAWING NO. C-10.06

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED NUMBER FROM C-10.20	PMB	7/94
2	REVISED NOTE	PMB	7/94
3	ADDED NOTE	PMB	7/94
4	DELETED BARRIER DETAILS	PMB	7/94


3" Compacted Bituminous Mixture  
or 3" Concrete Foundation Pad (Typ)  
See Plans for Width




## GENERAL NOTES

1. See Std 4-C-1.02 for other typical installations at bridge piers.
2. Transition median paving cross slope to meet level foundation pad. See Plans for length and location.


## MODIFIED SINGLE PIER OR COLUMN



## SECTION C-C



## SECTION A-A




## SECTION B-B


DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	BARRIER DETAILS AT PIERS	DRAWING NO. C-10.15

REV.	DESCRIPTION OF REVISIONS	DATE BY	DATE
1	REVISED NUMBER FROM C-10.01	PHB	7/94
2			
3			

### G4 (1W) SYSTEM




PLAN




ELEVATION

### G4 (1W) SYSTEM




SECTION G4(1W)

### G4 (2W) SYSTEM




PLAN



ELEVATION

### G4 (2W) SYSTEM



SECTION G4(2W)


### GENERAL NOTES

● - Indicates ARTBA designation


DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Robert Williams</i>	G4(1W) AND G4(2W) BLOCKED OUT W BEAM (TIMBER POST)	DRAWING NO. C-10.20

REVISION	DESCRIPTION OF REVISION	DATE
1	REVISED NUMBER FROM C-10.0A	7/94
2		
3		
4		


G4 (1S) SYSTEM



PLAN




ELEVATION  
G4 (1S) SYSTEM




SECTION G4(1S)  
SHOWN WITHOUT CURB


G4 (2S) SYSTEM



PLAN




ELEVATION  
G4 (2S) SYSTEM



SECTION G4(2S)  
SHOWN WITH CURB

GENERAL NOTES

● - Indicates ARTBA designation



W BEAM BACK-UP PLATE DETAIL





DESIGN APPROVED <i>Joseph Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	G4(1S) AND G4(2S) BLOCKED OUT W BEAM (STEEL POST)	DRAWING NO. C-10.21



DESCRIPTION OF REVISIONS	DATE




## GENERAL NOTES

● - Indicates ARTBA designation



G4 (1W-MODIFIED)

G4 (2W-MODIFIED)




RETAINER STRAP DETAIL

DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	10/95
APPROVED FOR CONSTRUCTION <i>Joseph Ottaviano</i>	G4(MODIFIED) BLOCKED OUT W BEAM WITH SPECIAL CURB AND GUTTER G4(1W) AND G4(2W) (TIMBER POST)	DRAWING NO. C-10.22 Sheet 2 of 2


NO.	DESCRIPTION OF REVISIONS	DATE
1	REVISED NUMBER FROM C-10.0A	7/94
2	ADDED NOTE	7/94
3	REVISED NOTE	7/94
4	DELETED DIMENSION	7/94

# GENERAL NOTES


1. Height of curb shall not exceed 4 inches.
- Indicates ARTBA designation



PLAN




W BEAM BACK-UP PLATE DETAIL



ELEVATION

G4(IIS-MODIFIED)



SECTION

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS G4(IIS-MODIFIED) BLOCKED OUT W BEAM (STEEL POST) WITH SPECIAL CURB AND GUTTER	REV. 7/94
APPROVED FOR DIGITIZATION <i>Ronald Williams</i>	DRAWING NO. C-10.22	




DRAWING NO.  
C-10.23

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED NUMBER FROM C-10.0A	PMB	7/94
2			
3			


## GENERAL NOTES

● - Indicates ARTBA designation


### G9 (C) SYSTEM




PLAN




ELEVATION  
G9 (C) SYSTEM



THRIE BEAM BACK-UP PLATE DETAIL




STRUCTURAL SHAPE BLOCK DETAIL




SECTION G9(C)

DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Smith</i>	G9(C) BLOCKED OUT THRIE BEAM (STEEL POST)	DRAWING NO. C-10.24

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED C-STANDARD CALLOUTS	PHB	10/95
2			
3			




PLAN




ELEVATION

NESTED STEEL W BEAM - TYPE 1 - SHORT SPAN  
(Splice Connection Inside Span) Length = 25'-0"



PLAN




ELEVATION

NESTED STEEL W BEAM - TYPE 2 - SHORT SPAN  
(Splice Connection Outside Span) Length = 37'-6"


## GENERAL NOTES

1. ● - Indicates ARTBA designation.
2. See Std C-10.20 and C-10.21 for additional information and dimensions.



SECTION A-A


Bolt Nested Steel W Beam Together  
 $\frac{3}{8}$ "-11UNC x  $\frac{1}{4}$ " Button Head Bolt (●)  
and Recess Nut (●)




SECTION B-B

DESIGN APPROVED <i>Henry H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Robert Williams</i>	NESTED STEEL W BEAM SHORT SPAN - TYPE 1 AND 2	DRAWING NO. C-10.28 Sheet 1 of 2


NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	MOVED AND REVISED SECTION	PWB	7/94
2			
3			
4			




PLAN



ELEVATION  
NESTED STEEL W BEAM - TYPE 1 - SHORT SPAN  
(Splice Connection Inside Span) Length = 25'-0"




PLAN



ELEVATION  
NESTED STEEL W BEAM - TYPE 2 - SHORT SPAN  
(Splice Connection Outside Span) Length = 37'-6"


## GENERAL NOTES

- - Indicates ARTBA designation.
- See Std C-10.04 and C-10.05 for additional information and dimensions.



SECTION A-A

Bolt Nested Steel W Beam Together  
5/8"-11UNC x 1 1/4" Button Head Bolt (●)  
and Recess Nut (●)




SECTION B-B

DESIGN APPROVED <i>Sherry H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	NESTED STEEL W BEAM SHORT SPAN - TYPE 1 AND 2	DRAWING NO. C-10.28 Sheet 1 of 2


NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	NEW SITE FROM C-10.28 & C-10.29	PMB	3/94
2			
3			
4			

## GENERAL NOTES

1. Use Type 3 Nested Steel W Beam to span downdrain or spillway inlets as shown in the plan view.
2. Use Type 3 to span multiple obstructions as shown in the elevation view.



PLAN



ELEVATION


NESTED STEEL W BEAM - TYPE 3 - LONG SPAN  
Length = 37'-6"

DESIGN APPROVED <i>Henry H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISSEMINATION <i>King &amp; Mace</i>	① NESTED STEEL W BEAM LONG SPAN - TYPE 3	DRAWING NO. C-10.28 Sheet 2 of 2


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED C STANDARD CALLOUTS	PHB	10/95
2			
3			
4			

# GENERAL NOTES

- ① 1. See S+d C-10.20 and C-10.21 for additional information and dimensions.



PLAN




ELEVATION  
BOLTED ANCHOR  
BOX CULVERT INSTALLATION

DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>[Signature]</i>	BOLTED ANCHOR GUARD RAIL	DRAWING NO. C-10.29 Sheet of 2


REVISION	DESCRIPTION OF REVISION	MADE BY	DATE
1	NEW STD FROM C-10.27 & C-10.24	PHB	3/94
2			
3			
4			

# GENERAL NOTES

- See Std C-10.04 and C-10.05 for additional information and dimensions.




PLAN




ELEVATION  
BOLTED ANCHOR  
BOX CULVERT INSTALLATION

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISSEMINATION <i>James H. Ottum</i>	BOLTED ANCHOR GUARD RAIL	DRAWING NO. C-10.29 Sheet 1 of 2

NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	NEW STD FROM C-10.23 & C-10.24	PHB	3/94
2			
3			
4			




INSTALLATION DETAIL




BRACKET DETAIL

### BOLTED ANCHOR TIMBER POST INSTALLATION DETAIL



INSTALLATION DETAIL



BRACKET DETAIL

### BOLTED ANCHOR STEEL POST INSTALLATION DETAIL

### GENERAL NOTES

1. Drill through top of box culvert with rotary drill.
2. Bracket may be made of one piece hot bent, or two pieces welded together.
3. Short timber posts anchored to box culvert roof shall be 8' x 8' only.

DESIGN APPROVED <i>Henry H. Ottensmeyer</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR CONSTRUCTION <i>Gregory J. [Signature]</i> ①	BOLTED ANCHOR GUARD RAIL	DRAWING NO. C-10.29 Sheet 2 of 2



NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE

## GENERAL NOTES

- - Indicates ARTBA designation

Concrete Barrier Transition,  
Std C-10.70 or Bridge Concrete  
Barrier Transition, Std B-21.20

Terminal Connector  
Anchor Assembly  
Std C-10.70 & C-10.74

Measurement Limit

Ferrule Wing  
Nut Block Anchor  
Std C-10.70 & C-10.74

Block Anchor  
Assembly (Typ)  
Std C-10.70 & C-10.74

W Beam Back Up Plate  
All Non Lap Connections  
C6x8.2 Rub Rail  
Std C-10.80

W Beam Terminal  
Connector (●)

Traffic

Block 1  
Std C-10.39

Block 2  
Std C-10.39

Block 3  
Std C-10.39


Block 4  
Std C-10.39

Block 5  
Std C-10.39

## PLAN

Std C-10.30  
Sheet 2 of 3 or  
Sheet 3 of 3

7/8"-9UNCx3" Bolt  
With 7/8" Narrow  
Type B Plain Washer  
(Under Head)



5/8"-11UNCx1 1/4" Button Head Bolts (●)  
and Recess Nut (●) with 1" Narrow  
Type A Plain Washer (Under Head) (Typ)  
This Splice Connection Only

5/8"-11UNCx1 1/2" Hex Bolt (Typ)

3/4"-10UNCx3" Hex Bolt with  
7/8" Narrow Type A Plain Washer  
(Under Head). Anchor with 2 Bolts  
(At opposite corners) (Typ)


Rectangular Plate Washer (●)  
Required Under Head of Five  
Bolts Along Concrete Transition

C6x8.2 Rub Rail  
Std C-10.80

## ELEVATION

Guard Rail Transition

Existing Concrete  
Barrier Transition




## ELEVATION

Notes:  
For Notes and Dimensions Not Shown,  
See Guard Rail Transition Above


Guard Rail Transition  
To Existing Concrete  
Barrier Transition

DESIGN APPROVED <i>Henry H. Ottensmeyer</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTIBUTION <i>Gregory M. White</i>	GUARD RAIL TRANSITION W BEAM TO CONCRETE HALF BARRIER (APPROACH)	DRAWING NO. C-10.30 Sheet 1 of 3

DESCRIPTION OF MATERIAL	DATE




PLAN



ELEVATION

GENERAL NOTES  
● - Indicates ARTBA designation

Guard Rail Transition  
(Timber Post)



ELEVATION

Note:  
For Notes and Dimensions Not Shown,  
See Guard Rail Transition Above.


Guard Rail Transition  
To Existing Concrete  
Barrier Transition

DESIGN APPROVED <i>W. H. Ott</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR CONSTRUCTION <i>W. H. Ott</i>	GUARD RAIL TRANSITION W BEAM TO CONCRETE HALF BARRIER (APPROACH)	DRAWING NO. C-10.30 Sheet 2 of 3


DESCRIPTION OF REVISION	DATE	BY

# GENERAL NOTES


● - Indicates ARTBA designation



PLAN



ELEVATION



TUBULAR BLOCKOUT DETAIL

Guard Rail Transition  
(Steel Post)


DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>James H. Ottum</i>	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (APPROACH)	DRAWING NO. C-10.30 Sheet 3 of 3

NO.	DESCRIPTION OF REVISION	DATE	BY
1	ADDED REFERENCE TO STD C-10.71	10/95	PH
2			
3			
4			


## GENERAL NOTES

● - Indicates ARTBA designation

- ① Concrete Barrier Transition,  
Std C-10.70, C-10.71 or  
Bridge Concrete Barrier Transition,  
Std B-21.19




PLAN



ELEVATION

Guard Rail Transition

Notes:  
For Notes and Dimensions Not Shown,  
See Guard Rail Transition Above



ELEVATION


Guard Rail Transition  
To Existing Concrete  
Barrier Transition

DESIGN APPROVED <i>Joseph H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Donna Hillman</i>	GUARD RAIL TRANSITION W BEAM TO CONCRETE HALF BARRIER (APPROACH WITH CURB)	DRAWING NO. C-10.31 Sheet 1 of 3


NO.	DESCRIPTION OF REVISION	DATE

## GENERAL NOTES

- - Indicates ARTBA designation




PLAN



ELEVATION

Guard Rail Transition

Notes:  
For Notes and Dimensions Not Shown,  
See Guard Rail Transition Above




ELEVATION

Guard Rail Transition  
To Existing Concrete  
Barrier Transition

DESIGN APPROVES <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>Joseph H. Ottum</i>	GUARD RAIL TRANSITION W BEAM TO CONCRETE HALF BARRIER (APPROACH WITH CURB)	DRAWING NO. C-10.31 Sheet 1 of 3


NO.	REVISIONS BY	DATE
1	ADDED REFERENCE TO STD C-10.31	10/95
2		
3		
4		



## GENERAL NOTES

● - Indicates ARTBA designation


## PLAN



## Guard Rail Transition (Timber Post)

## ELEVATION


Note:  
For Notes and Dimensions Not Shown,  
See Guard Rail Transition Above.



## ELEVATION

## Guard Rail Transition To Existing Concrete Barrier Transition


Note:  
Curb Height Shall Not Exceed 6"  
When Adjacent to Rub Rail.



## SECTION A-A


DESIGN APPROVED <i>James H. Ottensm</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald Williams</i>	GUARD RAIL TRANSITION W BEAM TO CONCRETE HALF BARRIER (APPROACH) (WITH CURB)	DRAWING NO. C-10.31 Sheet 2 of 3

NO.	REVISION/TYPE OF REVISION	DATE
1		
2		
3		
4		




## GENERAL NOTES

● - Indicates ARTBA designation



## Guard Rail Transition (Timber Post)




## ELEVATION

Note:  
For Notes and Dimensions Not Shown,  
See Guard Rail Transition Above.

## Guard Rail Transition To Existing Concrete Barrier Transition

Note:  
Curb Height Shall Not Exceed 6"  
When Adjacent to Rub Rail.




## SECTION A-A

DESIGN APPROVED <i>Greg H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>Greg H. Ottum</i>	GUARD RAIL TRANSITION W BEAM TO CONCRETE HALF BARRIER (APPROACH) (WITH CURB)	DRAWING NO. C-10.31 Sheet 2 of 3


DESCRIPTION OF REVISIONS	DATE	BY
ADDED REFERENCE TO STD C-10.71	10/95	

## GENERAL NOTES

● - Indicates ARTBA designation




PLAN




ELEVATION

Guard Rail Transition  
(Steel Post)



TUBULAR BLOCKOUT DETAIL



SECTION A-A

Note:  
Curb Height Shall Not Exceed 6"  
When Adjacent to Rub Rail.


DESIGN APPROVED <i>James H. Ott</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>David Sullivan</i>	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (APPROACH) (WITH CURB)	DRAWING NO. C-10.31 Sheet 2 of 3




NO.	DESCRIPTION OF WORK	DATE
1		
2		
3		

# GENERAL NOTES

● - Indicates ARTBA designation




## PLAN




## ELEVATION

Guard Rail Transition (Steel Post)



## TUBULAR BLOCKOUT DETAIL




## SECTION A-A

Note:  
Curb Height Shall Not Exceed 6"  
When Adjacent to Rub Rail.

DESIGN APPROVED <i>Joseph H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTINCTION <i>Joseph H. Ottomano</i>	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (APPROACH) (WITH CURB)	DRAWING NO. C-10.31 Sheet 3 of 3


REVISIONS	DATE
1. APPROVED REFERENCE TO STD C-10.71	10/95
2.	
3.	
4.	



# GENERAL NOTES


- For use with one-way traffic or with two-way traffic outside the clear zone.

● - Indicates ARTBA designation



Guard Rail Transition

Notes:  
For Notes and Dimensions Not Shown,  
See Guard Rail Transition Above



Guard Rail Transition  
To Existing Concrete  
Barrier Transition



DESIGN APPROVED <i>David L. Ott</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV 10/95
APPROVED FOR CONSTRUCTION <i>David L. Ott</i>	GUARD RAIL TRANSITION W BEAM TO CONCRETE HALF BARRIER (DEPARTURE)	DRAWING NO. C-10.32 Sheet 1 of 3

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE

## GENERAL NOTES


- For use with one-way traffic or with two-way traffic outside the clear zone.

● - Indicates ARTBA designation



Guard Rail Transition

Notes:  
For Notes and Dimensions Not Shown,  
See Guard Rail Transition Above



Guard Rail Transition  
To Existing Concrete  
Barrier Transition


DESIGN APPROVED <i>Joseph H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>Joseph H. Ottaviano</i>	GUARD RAIL TRANSITION W BEAM TO CONCRETE HALF BARRIER (DEPARTURE)	DRAWING NO. C-10.32 Sheet 1 of 3

NO.	DESCRIPTION OF REVISIONS	DATE
1	ADDED REFERENCE TO STD C-10.32	10/95
2		
3		


# GENERAL NOTES

● - Indicates ARTBA designation

- ① Concrete Barrier Transition, Std C-10.70, C-10.71 or Bridge Concrete Barrier Transition, Std B-21.19 & B-21.20




PLAN



ELEVATION


Guard Rail Transition  
(Timber Post)

Notes:  
For Notes and Dimensions Not Shown,  
See Guard Rail Transition Above.



ELEVATION

Guard Rail Transition  
To Existing Concrete  
Barrier Transition



SECTION A-A

DESIGN APPROVED  
*[Signature]*  
APPROVED FOR  
DISTRIBUTION  
*[Signature]*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV.  
10/95


GUARD RAIL TRANSITION  
W BEAM TO CONCRETE HALF  
BARRIER (DEPARTURE)

DRAWING NO.  
C-10.32  
Sheet 2 of 3


DESCRIPTION OF REVISION	DATE BY	DATE

# GENERAL NOTES

● - Indicates ARTBA designation




PLAN



ELEVATION


Guard Rail Transition  
(Timber Post)

Notes:  
For Notes and Dimensions Not Shown,  
See Guard Rail Transition Above.



ELEVATION

Guard Rail Transition  
To Existing Concrete  
Barrier Transition




SECTION A-A

DESIGN APPROVED <i>Henry H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>Raymond</i>	GUARD RAIL TRANSITION W BEAM TO CONCRETE HALF BARRIER (DEPARTURE)	DRAWING NO. C-10.32 Sheet 2 of 3


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	ADDED REFERENCE TO STD C-10.71	PHB	10/95
2			
3			

# GENERAL NOTES


● - Indicates ARTBA designation



PLAN



ELEVATION



SECTION A-A


## Guard Rail Transition (Steel Post)

DESIGN APPROVED <i>James H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Kenneth A. Chellier</i>	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (DEPARTURE)	DRAWING NO. C-10.32 Sheet 1 of 3


NO.	DESCRIPTION OF REVISION	WHEN MADE	DATE
1			
2			
3			

# GENERAL NOTES


● - Indicates ARTBA designation



PLAN



ELEVATION




SECTION A-A

Guard Rail Transition  
(Steel Post)


DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>[Signature]</i>	GUARD RAIL TRANSITION, W BEAM TO CONCRETE HALF BARRIER (DEPARTURE)	DRAWING NO. C-10.32 Sheet 3 of 3

DESCRIPTION OF SECTION	MADE BY	DATE




BLOCK	DIMENSION	
	A	B
2	1 1/4"	7/8"
3	2 1/2"	1 3/4"
4	3 1/8"	2 3/8"
5	4 5/8"	3 1/8"



Note:  
Block 1 is a 1/4"x12"x14" Plate




HALF BARRIER  
(BLOCK 1 SHOWN)




HALF BARRIER  
(BLOCK 2 SHOWN)



BLOCK DETAILS



Blocks 2,3,4 and 5



MEDIAN BARRIER  
(BLOCK 2 SHOWN)

BLOCK AND ANCHORAGE DETAILS

DESIGN APPROVED <i>Henry H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>George J. Hines</i>	HARDWARE FOR W BEAM TRANSITION TO CONCRETE BARRIER	DRAWING NO. C-10.39




Delete

### GENERAL NOTES


1. See Std C-10.44 for additional information.

● - Indicates ARTBA designation



## PLAN


Traffic




ELEVATION

DESIGN APPROVED <i>Joseph H. Ottewill</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DIST. TRIBUTION <i>Ronald K. Sullivan</i>	GUARD RAIL EXTRUDER TERMINAL GET-1	DRAWING NO. C-10-40 Sheet 1 of 2

# Delete




SECTION




PLAN

TYPE B GUARD RAIL INSTALLATION



SECTION



PLAN

TYPE A GUARD RAIL INSTALLATION


DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	GUARD RAIL EXTRUDER TERMINAL CET-1	DRAWING NO. C-10.40 Sheet 2 of 2

# Delete


## GENERAL NOTES

1. See Std. C-10.44 for additional information.

● - Indicates ARTBA designation



## PLAN




## ELEVATION


DESIGN APPROVED <i>Luigi Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>Constance Williams</i>	GUARD RAIL EXTRUDER TERMINAL WITH CURB AND GUTTER GET-2	DRAWING NO. C-10.41 Sheet 1 of 2

# Delete

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED GUTTER DEPRESSION	PHB	10/95
2	ADDED NOTE	PHB	10/95
3			
4			




SECTION




PLAN

TYPE B GUARD RAIL INSTALLATION




SECTION




PLAN

TYPE A GUARD RAIL INSTALLATION

DESIGN APPROVED <i>Henry Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Donald Williams</i>	GUARD RAIL EXTRUDER TERMINAL WITH CURB AND GUTTER GET-2	DRAWING NO. C-1041 Sheet 2 of 2




SECTION




PLAN

TYPE B GUARD RAIL INSTALLATION



SECTION




PLAN


TYPE A GUARD RAIL INSTALLATION

# Delete


NO.	DESCRIPTION OF REVISIONS	DATE
1	MODIFIED DIMENSIONS	10/95
2		
3		
4		




18"x24"x $\frac{1}{4}$ "  
SOIL PLATE DETAIL



TYPE A POST DETAIL



TYPE B POST DETAIL



STEEL TUBE DETAIL

## GENERAL NOTES


1. Soil plates, steel tubes, offset strut, yokes, bearing plate and pipe sleeves shall be fabricated from structural steel ASTM A36.

DESIGN APPROVED <i>James H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Robert C. Williams</i>	HARDWARE FOR GUARD RAIL EXTRUDER TERMINAL	DRAWING NO. C-10.44 Sheet 1 of 3


Delete

# GENERAL NOTES


1. Soil plates, steel tubes, offset strut, yokes, bearing plate and pipe sleeve shall be fabricated from structural steel ASTM A36.




SOIL PLATE DETAIL



TYPE A POST DETAIL




TYPE B POST DETAIL




STEEL TUBE DETAIL

Delete


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED DIMENSIONS	PHB	10/95
2			
3			
4			




TYPE C POST DETAIL



OFFSET STRUT DETAIL




YOKE DETAIL




DESIGN APPROVED <i>Joseph H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald Williams</i>	HARDWARE FOR GUARD RAIL EXTRUDER TERMINAL	DRAWING NO. C-10,44 Sheet 2 of 3




# Delete




TYPE C POST DETAIL



OFFSET STRUT DETAIL



YOKE DETAIL










DESIGN APPROVED <i>Joseph H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR CONSTRUCTION <i>Ronald Williams</i>	HARDWARE FOR GUARD RAIL EXTRUDER TERMINAL	DRAWING NO. C-10,44 Sheet 2 of 3

Delete




# GENERAL NOTES

1. The cable assembly shall be tightened to remove slack.



DESIGN APPROVED <i>James H. Ottensmeyer</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR SUBMITTAL <i>Donald Williams</i>	HARDWARE FOR GUARD RAIL EXTRUDER TERMINAL	DRAWING NO. C-10.44 Sheet 3 of 3


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED NUMBER FROM C-10.21	PMB	7/94
2	ADDED NOTE	PMB	7/94
3	REMOVED REFERENCES TO BCT	PMB	7/94




FRONT VIEW

ANCHOR PLATE DETAIL

SIDE VIEW



FRONT VIEW



SIDE VIEW

FOUNDATION PLATE DETAIL


## GENERAL NOTES

1. The cable assembly shall be tightened to remove slack.
2.  $\frac{5}{8}$ " 11UNC X 3-1/4" heavy hex bolts, connecting the BCT terminal post and foundation plates, shall be torqued to 170 ft/lbs.
3. To ensure that the bearing plate remains in position, one wrap of 14 gauge galvanized steel wire shall be wrapped around the terminal post near the top of the plate.
- ② 4. See Std. C-10.03 for measurement limits.


● - Indicates ARTBA designation

DESIGN APPROVED <i>Joseph H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Sullivan</i>	③ GUARDRAIL ANCHOR ASSEMBLY STEEL TERMINAL POST	DRAWING NO. C-10.45


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE	NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED NUMBER FROM C-10.09	PMB	7/94	1	CHANGED TO BOTH SLIP & FIXED FORM	PMB	7/94
2	REVISED TITLE	PMB	7/94				
3	ADDED DETAIL	PMB	7/94				
4	REVISED JOINT	PMB	7/94				




ELEVATION



WITH PCC PAVEMENT  
SECTION A-A



WITH AC PAVEMENT  
SECTION B-B



WITH PCC PAVEMENT  
③ BARRIER WITH GUTTER


## GENERAL NOTES

1. Half Barrier shall be constructed by the slip form or formed Cast-In-Place method.
2. When obstacles are encountered which prevent the use of slip form equipment, the closure shall be accomplished by the use of stationary forms.
3. Concrete shall be Class S, design strength  $f_c = 3000$  PSI.
4. If the footing and barrier are cast monolithically, No. 6 S shaped rebars will not be required.
5. In no case shall the width of barrier exceed the width of the barrier footing or overhang the adjacent pavement.
6. No. 4 Rebar shall extend 12" past the construction joint at the completion of the day's pour.


▲ Depth to match adjacent PCCP thickness (8" Min).

DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Robert M. Hall</i>	⑤ HALF BARRIER CAST IN PLACE SLIP FORM & FIXED FORM	DRAWING NO. C-10.60


NO.	DESCRIPTION OF REVISIONS	DATE
1	MODIFIED REBAR DIMENSIONS	10/95
2	ADDED GENERAL NOTE	10/95
3		
4		




PLAN




ELEVATION



SECTION A-A




AT REBAR  
SECTION B-B




AT WEEP HOLE  
SECTION C-C

## GENERAL NOTES

- Concrete shall be Class S, design strength  $f_c \geq 3000$  PSI.
- Half Barrier shall be placed upon either Asphaltic or Portland Cement Concrete Pavement.
- Pavement thickness adjacent to Half Barrier shall be  $\frac{3}{4}$ " minimum.
- The Half Barrier shall be placed upon a bed of grout in order to provide a uniform bearing.
- Doweled Joints shall be grouted under pressure until all of the openings and the joints are filled.
- This standard shall not be used when an individual run consists of less than five 20 foot sections.
- All bend dimensions for reinforcing steel shall be out-to-out of bars.





PLAN




ELEVATION  
CONSTRUCTION JOINT DETAIL

DESIGN APPROVED <i>Joseph H. Ottensm</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Ronald J. Allen</i>	HALF BARRIER, PRECAST	DRAWING NO. C-10.61


NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	REVISED NUMBER FROM C-10.11	PHB	7/94
2	ADDED GENERAL NOTES	PHB	7/94
3	ADDED REBAR DETAILS	PHB	7/94




ELEVATION



SECTION A-A





AT REBAR  
SECTION B-B



AT WEEP HOLE  
SECTION C-C

## ② GENERAL NOTES

- Concrete shall be Class S, design strength  $f'_c = 3000$  PSI.
- Half Barrier shall be placed upon either Asphaltic or Portland Cement Concrete Pavement.
- Pavement thickness adjacent to Half Barrier shall be  $\frac{3}{4}$ \" minimum.
- The Half Barrier shall be placed upon a bed of grout in order to provide a uniform bearing.
- Doweled joints shall be grouted under pressure until all of the openings and the joints are filled.
- This standard shall not be used when an individual run consists of less than five 20 foot sections.



ELEVATION  
CONSTRUCTION JOINT DETAIL

DESIGN APPROVED

*Joseph H. Ottum*

APPROVED FOR DISTRIBUTION

*Brad Williams*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

HALF BARRIER, PRECAST




REV.

7/94

DRAWING NO.


① C-10.61

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1			
2			
3			
4			



## GENERAL NOTES

1. Half Barrier shall be constructed by the slip form or formed Cast-In-Place method.
2. When obstacles are encountered which prevent the use of slip form equipment, the closure shall be accomplished by the use of stationary forms.
3. Concrete shall be Class 5, design strength  $f'_c = 3000$  PSI.
4. No. 4 Rebar shall extend 12" past the construction joint at the completion of the day's pour.
5. Thickness of footing, "D" can be adjusted to match the PCCP thickness, as approved by the Engineer.
6. When the pavement section slopes away from the gutter, the slope of the gutter shall match the pavement cross slope. Therefore, the 2" gutter depression is not applicable.
7. When bridges are encountered, the cross slope of the gutter shall be transitioned to match the cross slope of the bridge. Length of the transition is 15 feet.



BARRIER GUTTER DETAIL

DESIGN APPROVED

*Lucretia Ottum*

APPROVED FOR  
CONSTRUCTION

*Ronald Williams*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

CONCRETE  
HALF BARRIER  
WITH GUTTER

ISSUE

10/95


DRAWING NO.

C-10.62


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REMOVED INCORRECT REBAR AND NOTE	PHS	10/95
2			
3			
4			

## GENERAL NOTES


1. Concrete shall be Class S, design strength  $f'_c = 3000$  PSI.
2. If the footing and barrier are cast monolithically, No. 6 S shaped rebars will not be required.
3. In no case shall the width of barrier exceed the width of the barrier footing or overhang the adjacent pavement.
4. No. 4 Rebar shall extend 12" past the construction joint at the completion of the day's pour.




PLAN




ELEVATION



WITH AC  
SECTION A-A



WITH PCCP  
SECTION A-A



KEY WAY DETAIL


DESIGN APPROVED <i>James H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Ronald S. Williams</i>	HALF BARRIER (AT PIERS) CAST IN PLACE, FIXED FORM	DRAWING NO. C-10.64 Sheet 1 of 2




REVISION	DESCRIPTION OF REVISIONS	DATE
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		

## GENERAL NOTES


- Concrete shall be Class S, design strength  $f'_c = 3000$  PSI.
- If the footing and barrier are cast monolithically, No. 6 S shaped rebar will not be required.
- In no case shall the width of barrier exceed the width of the barrier footing or overhang the adjacent pavement.
- No. 4 Rebar shall extend 12" past the construction joint at the completion of the day's pour.




ELEVATION



WITH AC  
SECTION A-A



WITH PCCP  
SECTION A-A




KEY WAY DETAIL


DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>Rose</i>	HALF BARRIER (AT PIERS) CAST IN PLACE, FIXED FORM	DRAWING NO. C-10.64 Sheet 1 of 2




NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE




ELEVATION



SECTION A-A





SECTION B-B



# GENERAL NOTES


1. Concrete shall be Class S, design strength  $f'_c = 4000$  PSI.
2. The Half Barrier shall be placed upon a bed of grout in order to provide a uniform bearing.
3. Doweled joints shall be grouted under pressure until all of the openings and the joints are filled.
4. This standard shall not be used when an individual run consists of less than five 20 foot sections.



CONSTRUCTION JOINT DETAIL


DESIGN APPROVED <i>Joseph H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR CONSTRUCTION <i>Kristen Williams</i>	HALF BARRIER (AT PIERS) PRECAST	DRAWING NO. C-10.64 Sheet 2 of 2

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	ADDED GENERAL NOTE	PHB	10/95
2	REVISED NOTE	PHB	10/95
3	REVISED REBAR DIMENSIONS	PHB	10/95




PLAN VIEW


Traffic




ELEVATION



ELEVATION  
DEPARTURE TERMINATION DETAIL




SECTION B-B  
AT CATCH BASINS




SECTION A-A

## GENERAL NOTES

1. All concrete shall be Class "S" (f'c = 3000 psi).
2. All reinforcing steel shall conform to Section 1003.
3. All reinforcing steel shall have 2" minimum clear cover unless otherwise noted.
4. Transverse construction joints shall extend through the foundation slab and be located at intervals not to exceed 20 feet.
5. See drainage sheets for slotted drain and catch basin details.
6. Departure termination may be substituted for the C-10.76 barrier transition under departure conditions.
7. See Std. C-05.20 for sidewalk construction.
8. All bend dimensions for reinforcing steel shall be out-to-out of bars.




BARRIER GUTTER DETAIL




DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald Kallala</i>	HALF BARRIER WITH SIDEWALK	DRAWING NO. C-10.65


DESCRIPTION OF REVISION	MADE BY	DATE




PLAN VIEW




ELEVATION





ELEVATION DEPARTURE TERMINATION DETAIL



SECTION B-B AT CATCH BASINS



SECTION A-A




## GENERAL NOTES


1. All concrete shall be Class 'S' (f'c = 3000 psi).
2. All reinforcing steel shall conform to Section 1003.
3. All reinforcing steel shall have 2" minimum clear cover unless otherwise noted.
4. Transverse construction joints shall extend through the foundation slab and be located at intervals not to exceed 20 feet.
5. See drainage sheets for slotted drain and catch basin details.
6. Departure termination may be substituted for the C-10.76 barrier transition under departure conditions.
7. See Std. C-05.20 for sidewalk construction.

DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>Joseph H. Ottum</i>	HALF BARRIER WITH SIDEWALK	DRAWING NO. C-10.65


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED NUMBER FROM C-10.52	PH	7/74
2	CHANGED TO BOTH SLIP & FIXED FORM	PH	7/74
3			
4			



ELEVATION



WITH PCC PAVEMENT



WITH AC PAVEMENT

## GENERAL NOTES




1. Half Barrier shall be constructed by the slip form or formed Cast-In-Place method.
2. When obstacles are encountered which prevent the use of slip form equipment, the closure shall be accomplished by the use of stationary forms.
3. Concrete shall be Class S, design strength  $f_c = 3000$  PSI.
4. If the footing and barrier are cast monolithically, No. 6 S shaped rebars will not be required.
5. In no case shall the width of barrier exceed the width of the barrier footing or overhang the adjacent pavement.
6. No. 4 Rebar shall extend 12' past the construction joint at the completion of the day's pour.

▲ Depth to match adjacent PCP thickness (6" Min).

## SECTION A-A



DESIGN APPROVED <i>James H. Ottensmeyer</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald L. Ottensmeyer</i>	② MEDIAN BARRIER CAST IN PLACE SLIP FORM & FIXED FORM	DRAWING NO. C-10.66

REVISIONS	DESCRIPTION OF REVISIONS	DATE BY	DATE
1	REVISED CONCRETE STRENGTH	PHB	10/95
2	ADDED GENERAL NOTE	PHB	10/95
3			
4			









## GENERAL NOTES

- Concrete shall be Class S, design strength  $f'_c = 4000$  PSI.
- Half Barrier shall be placed upon either Asphaltic or Portland Cement Concrete Pavement.
- Pavement thickness adjacent to Half Barrier shall be  $\frac{3}{4}$ " minimum.
- The Half Barrier shall be placed upon a bed of grout in order to provide a uniform bearing.
- Doweled Joints shall be grouted under pressure until all of the openings and the joints are filled.
- This standard shall not be used when an individual run consists of less than five 20 foot sections.
- All bend dimensions for reinforcing steel shall be out-to-out of bars.



DESIGN APPROVED	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION	MEDIAN BARRIER, PRECAST	DRAWING NO. C-10.6B

NO	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED NUMBER FROM C-10.14	PNR	7/94
2	ADDED REBAR DETAIL	PNR	7/94
3			
4			



SECTION B-B  
CONSTRUCTION JOINT DETAIL

- ### GENERAL NOTES

1. Concrete shall be Class S, design strength  $f_c$  = 3000 PSI.
2. Half Barrier shall be placed upon either Asphaltic or Portland Cement Concrete Pavement.
3. Pavement thickness adjacent to Half Barrier shall be  $\frac{3}{4}$ " minimum.
4. The Half Barrier shall be placed upon a bed of grout in order to provide a uniform bearing.
5. Doweled Joints shall be grouted under pressure until all of the openings and the joints are filled.
6. This standard shall not be used when an individual run consists of less than five 20 foot sections.

END SECTION

SECTION A-A

DESIGN APPROVED <i>Sam H. Ottewill</i>	
APPROVED FOR DISTRIBUTION <i>Ronald W. Dean</i>	


STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

**MEDIAN BARRIER, PRECAST**

DRAWING NO. C-10.68




NO.	DESCRIPTION OF REVISION	DATE BY	DATE
1	MODIFIED GENERAL NOTE	PMB	10/95
2	ADDED GENERAL NOTE	PMB	10/95
3	MODIFIED CLASSON HORIZONTAL REINFORCING	PMB	10/95



### GENERAL NOTES

- Concrete shall be constructed by the Fixed Form Cast-in-Place method.
- Concrete shall be Class 5, design strength  $f'_c = 3000$  psi.
- All reinforcing steel shall have 2" minimum clear cover unless otherwise noted.
- All bend dimensions for reinforcing steel shall out-to-out of bars.


See Dowel Installation and Construction Joint Detail



ELEVATION  
BARRIER WITHOUT CURB


DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	CONCRETE HALF BARRIER TRANSITION	DRAWING NO. C-10.7C Sheet 1 of 4

DESCRIPTION OF REVISION	DATE BY	DATE



PLAN

See Dowel Installation and Construction Joint Detail



ELEVATION  
BARRIER WITHOUT CURB

### GENERAL NOTES

1. Concrete shall be constructed by the Fixed Form Cast-in-Place method.
2. Concrete shall be Class S, design strength  $f'_c = 3000$  psi.

DESIGN APPROVED

*James H. Citterman*

APPROVED FOR DISTRIBUTION

*James H. Citterman*


STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

3/94

CONCRETE HALF  
BARRIER TRANSITION


DRAWING NO.  
C-10.70  
Sheet 1 of 4

NO.	DESCRIPTION OF REVISIONS	DATE
1	MODIFIED GUTTER HORIZONTAL REINFORCING	10/95
2	CONNECTED SPLITTING	10/95
3		
4		



PLAN


② See Dowel Installation and Construction Joint Detail




ELEVATION  
BARRIER WITH CURB AND GUTTER

DESIGN APPROVED <i>Joseph H. Ott</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Wendell Williams</i>	CONCRETE HALF BARRIER TRANSITION	DRAWING NO. C-10.70 Sheet 2 of 4

REVISION	DESCRIPTION OF REVISION	DATE
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		



PLAN




ELEVATION  
BARRIER WITH CURB AND GUTTER


DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISSEMINATION <i>Gregory Hantz</i>	CONCRETE HALF BARRIER TRANSITION	DRAWING NO. C-10.70 Sheet 2 of 4




DESCRIPTION OF REVISIONS	DATE




SECTION A-A



SECTION B-B




WITHOUT CURB




WITH CURB

SECTION C-C




WITHOUT CURB




WITH CURB

SECTION D-D




WITHOUT CURB




WITH CURB

SECTION E-E



WITHOUT CURB




WITH CURB


SECTION F-F

DESIGN APPROVED <i>John H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>John H. Ottum</i>	CONCRETE HALF BARRIER TRANSITION	DRAWING NO. C-10.70 Sheet 3 of 4


REVISION	DESCRIPTION OF REVISION	DATE
1	ADDED CAISSON HORIZONTAL REINFORCING	10/95
2	REVISED DIMENSIONS	10/95
3		
4		




DOWEL INSTALLATION  
AND CONSTRUCTION JOINT DETAIL




RUB RAIL SLOT DETAIL



BLOCK AND ANCHORAGE  
HALF BARRIER  
(BLOCK 1 SHOWN)




Barrier End





Curb End

CURB TRANSITION DETAIL




BLOCK AND ANCHORAGE  
HALF BARRIER  
(BLOCK 2 SHOWN)




CAISSON REINFORCEMENT

DESIGN APPROVED <i>Lucy H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Robert Williams</i>	CONCRETE HALF BARRIER TRANSITION	DRAWING NO. C-10.70 Sheet 4 of 4

NO.	DESCRIPTION OF REVISION	MADE BY	DATE




Joint Assembly




Dowel Locations


DOWEL INSTALLATION  
AND CONSTRUCTION JOINT DETAIL




RUB RAIL SLOT DETAIL



BLOCK AND ANCHORAGE  
HALF BARRIER  
(BLOCK 1 SHOWN)




Barrier End





Curb End

CURB TRANSITION DETAIL



BLOCK AND ANCHORAGE  
HALF BARRIER  
(BLOCK 2 SHOWN)



CAISSON REINFORCEMENT


DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>James H. Ottum</i>	CONCRETE HALF BARRIER TRANSITION	DRAWING NO. C-10.70 Sheet 4 of 4




DESCRIPTION OF REVISIONS	MADE BY	DATE

## GENERAL NOTES

1. Half Barrier shall be constructed by the Fixed Form Cast-in-Place method.
2. Concrete shall be Class S, design strength  $f_c = 3000$  PSI.
3. All reinforcing steel shall have 2" minimum clear cover unless otherwise noted.
4. All bend dimensions for reinforcing steel shall be out-to-out of bars.




PLAN




ELEVATION  
BARRIER WITH CURB AND GUTTER

DESIGN APPROVED <i>Joseph H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	10/95
APPROVED FOR DISTRIBUTION <i>Ronald J. Allen</i>	CONCRETE HALF BARRIER TRANSITION	DRAWING NO. C-10.71 Sheet 1 of 3


DESCRIPTION OF REVISIONS	DATE	BY




SECTION A-A



SECTION B-B



SECTION C-C




SECTION D-D


DESIGN APPROVED <i>James H. Ottensm</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	ISSUE 10/95
APPROVED FOR DISTRIBUTION <i>Ronald L. Llan</i>	CONCRETE HALF BARRIER TRANSITION	DRAWING NO. C-10.71 Sheet 2 of 3




REV	DESCRIPTION OF REVISION	DATE
1	REVISED STEEL	10/95
2	ADDED NOTE	10/95




BLOCK ANCHOR ASSEMBLY



RUB RAIL TERMINAL ANCHOR



TERMINAL CONNECTOR ANCHOR ASSEMBLY




FERRULE WING NUT BLOCK ANCHOR


• Each Weld Shall Develop  
The Tensile Strength Of  
The Wire

DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>[Signature]</i>	HARDWARE FOR CONCRETE BARRIER TRANSITIONS	DRAWING NO. C-10,74


REVISION	DESCRIPTION OF REVISIONS	DATE



BLOCK ANCHOR ASSEMBLY




RUB RAIL TERMINAL ANCHOR



TERMINAL CONNECTOR ANCHOR ASSEMBLY


• Each Weld Shall Develop  
The Tensile Strength Of  
The Wire




FERRULE WING NUT BLOCK ANCHOR

DESIGN APPROVED <i>James H. Ottewill</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR CONSTRUCTION <i>Charles H. H. H.</i>	HARDWARE FOR CONCRETE BARRIER TRANSITIONS	DRAWING NO. C-10.74


NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	REVISED ELEVATION VIEW	PMB	10/95
2	REVISED REBAR DIMENSIONS	PMB	10/95
3	REVISED NOTE	PMB	10/95
4	ADDED GENERAL NOTE	PMB	10/95




PLAN VIEW




BARRIER GUTTER DETAIL




SECTION A-A



ELEVATION 1



SECTION B-B




SECTION C-C

## GENERAL NOTES


1. All concrete shall be Class 'S' ( $f'_c = 3000$  psi).
2. All reinforcing steel shall conform to Section 1003.
3. All reinforcing steel shall have 2' minimum clear cover unless otherwise noted.
4. See drainage sheets for slotted drain and catch basin details.
5. Barrier transition shall match both adjoining curb and gutter and concrete half barrier.
6. See Std. C-05.20 for sidewalk construction.
7. All bend dimensions for reinforcing steel shall be out-to-out of bars.

DESIGN APPROVED <i>Joseph H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV 10/95
APPROVED FOR CONSTRUCTION <i>Ronald A. Williams</i>	BARRIER TRANSITION-TANCENT DEPARTURE TYPE I	DRAWING NO. C-10.75 Sheet 1 of 3


NO.	DESCRIPTION OF REVISIONS	DATE
1	REVISED NUMBER FROM C-10.68	7/94
2		
3		
4		





PLAN VIEW




BARRIER GUTTER DETAIL



ELEVATION



SECTION B-B




SECTION C-C

## GENERAL NOTES


1. All concrete shall be Class "S" (f'c = 3000 psi).
2. All reinforcing steel shall conform to Section 1003.
3. All reinforcing steel shall have 2' minimum clear cover unless otherwise noted.
4. See drainage sheets for slotted drain and catch basin details.
5. Barrier transition shall match both adjoining curb and gutter and concrete half barrier.
6. See Std. C-05.20 for sidewalk construction.

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>Robert P. Williams</i>	BARRIER TRANSITION-TANGENT DEPARTURE TYPE I	DRAWING NO. ① C-10.75 Sheet 1 of 3


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED REBAR DIMENSIONS	PMB	10/95
2	REVISED NOTE	PMB	10/95
3	ADDED GENERAL NOTE	PMB	10/95




PLAN VIEW




BARRIER GUTTER DETAIL




ELEVATION



SECTION A-A



SECTION B-B



SECTION C-C


# GENERAL NOTES

1. All concrete shall be Class "S" if  $f_c = 3000$  psi.
2. All reinforcing steel shall conform to Section 1003.
3. All reinforcing steel shall have 2" minimum clear cover unless otherwise noted.
4. See drainage sheets for slotted drain and catch basin details.
5. Barrier transition shall match both adjoining curb and gutter and concrete half barrier.
6. See Std. C-05.20 for sidewalk construction.
7. All bend dimensions for reinforcing steel shall be out-to-out of bars.


DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Rosario Williams</i>	BARRIER TRANSITION-TANGENT DEPARTURE TYPE 2	DRAWING NO. C-10.75 Sheet 2 of 3





DESCRIPTION OF REVISIONS		MADE BY	DATE
1	REARRANGED STD	PHB	7/94
2	REVISED DIMENSION	PHB	7/94
3	REVISED TO DEPARTURE	PHB	7/94
4	REVISED NOTE	PHB	7/94




PLAN VIEW




### BARRIER GUTTER DETAIL




ELEVATION



SECTION A-A



SECTION B-B








SECTION C-C

DESIGN APPROVED <i>Lucy H. Ottlinger</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>Michael M. ...</i>	BARRIER TRANSITION-TANGENT DEPARTURE TYPE 2 ① ②	DRAWING NO. C-10.75 Sheet 2 of 3

● Varies - 2'-6", 4'-6" or width as per plans.


DESIGN APPROVED <i>Joseph H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>Frank J. ...</i>	BARRIER TRANSITION-TANGENT DEPARTMENT TYPE 3	DRAWING NO. C-10.75 Sheet 3 of 3

NO.	DESCRIPTION OF REVISION	DATE
1	REVISED REBAR DIMENSIONS	10/95
2	REVISED NOTE	10/95
3	ADDED GENERAL NOTE	10/95



# GENERAL NOTES

1. All concrete shall be Class "S" (f'c = 3000 psi).
2. All reinforcing steel shall conform to Section 1003.
3. All reinforcing steel shall have 2' minimum clear cover unless otherwise noted.
4. See drainage sheets for slotted drain and catch basin details.
5. Barrier transition shall match the adjoining concrete half barrier.
6. See Std. C-05.20 for sidewalk construction.
7. All bend dimensions for reinforcing steel shall be out-to-out of bars.



DESIGN APPROVED <i>Sherry Ottaway</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	BARRIER TRANSITION CURVE	DRAWING NO. C-10.76

NO.	DESCRIPTION OF REVISION	DATE
1	NEW STD FROM OLD STD CHANGES	7/94
2		
3		

Curb & Gutter  
Transition  
Type 4  
Std C-05.12

Sidewalk Ramp  
Type 3  
Std C-05.30

Outside Edge  
of Sidewalk  
Std C-05.20

Radius Per Plans  
15'-0" Min Radius

1/2" Bituminous  
Joint Filler

2'-0"  
1'-1"  
1'-5"

Barrier  
Transition  
Control Point  
See Plans


Concrete Half  
Barrier  
Std C-10.65 or  
As Per Plans

See Dowel  
Installation and  
Construction  
Joint Detail  
Std C-10.70


PLAN VIEW

ELEVATION


Varies from  
1'-5" to 3'-7"



SECTION A-A




SECTION B-B



SECTION C-C

# GENERAL NOTES

1. All concrete shall be Class "S" (f'c = 3000 psi).
2. All reinforcing steel shall conform to Section 1003.
3. All reinforcing steel shall have 2" minimum clear cover unless otherwise noted.
4. See drainage sheets for slotted drain and catch basin details.
5. Barrier transition shall match the adjoining concrete half barrier.
6. See Std. C-05.20 for sidewalk construction.



BARRIER GUTTER DETAIL

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION <i>David A. Dierma</i>	BARRIER TRANSITION CURVE	DRAWING NO. C-10.76

NO.	DESCRIPTION OF REVISION	MADE BY	DATE


Concrete Barrier  
Transition  
Std C-10.70

C6x8.2 Rub Rail


Rub Rail Terminal  
Assembly, Std C-10.83

G4(1W) System  
G4(2W) System  
G4(1S) System  
G4(2S) System

PLAN



ELEVATION - TIMBER POST



ELEVATION - STEEL POST

DESIGN APPROVED  
*Joseph Ottaviano*  
APPROVED FOR  
DISTRIBUTION  
*Robert H. Haver*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

3/94


RUB RAIL

DRAWING NO.  
C-10.80  
Sheet 1 of 2

NO.	DESCRIPTION OF REVISIONS	DATE BY	DATE
1	REVISED CALLOUT	PHB	10/95
2	ADDED WELDING CALLOUT	PHB	10/95
3	CORRECTED DIMENSION	PHB	10/95

# GENERAL NOTES

- All slots in rub rail are  $\frac{1}{8}$ " x 2".  
All square holes are  $\frac{1}{8}$ ".




MODIFIED C6X8.2 RUB RAIL DETAIL

DESIGN APPROVED <i>James H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald Williams</i>	RUB RAIL	DRAWING NO. C-10,80 Sheet 2 of 2

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1			
2			
3			
4			

# GENERAL NOTES

1. All slots in rub rail are  $\frac{3}{8}$ " x 2".  
All square holes are  $\frac{1}{8}$ ".




MODIFIED C6X8.2 RUB RAIL DETAIL


DESIGN APPROVED <i>Joseph H. Ottensm</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISSEMINATION <i>Charles M. Hays</i>	RUB RAIL	DRAWING NO. C-10.80 Sheet 2 of 2




NO.	DESCRIPTION OF REVISIONS	DATE	BY
1			
2			
3			
4			




PLAN  
RUB RAIL BACK BLOCKOUT DETAIL




SECTION



SECTION




PLAN  
STEEL POST




PLAN  
TIMBER POST


RUB RAIL TERMINAL ASSEMBLY



Median Barrier




Half Barrier




Elevation  
RUB RAIL ANCHOR

DESIGN APPROVED <i>John H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	3/94
APPROVED FOR DISTRIBUTION <i>John H. Ottens</i>	HARDWARE FOR RUB RAIL	DRAWING NO. C-10.83


REV.	DESCRIPTION OF REVISION	DATE
1	ADDED STANDARD	7/94
2		
3		



Glare Screen  
Installation on  
Standard Median Barrier




Glare Screen  
Installation on  
Median Barrier Transition




Glare Screen  
Installation on  
Half Barrier at Bridge Pier

## GENERAL NOTES

1. Posts shall be 12'-6" C to C. Structural steel shall conform to ASTM-A-36, galvanized ASTM-A-123.
2. Hex head bolt shall conform to ASTM-A-307, galvanized ASTM-A-153 Class C.
3. Helical spring lock washer shall conform to ASTM-A-313, galvanized ASTM-A-153 Class C.
4. Tension wires: AWG No. 9(0.148") galvanized to conform to ASTM-A-116 Class 2.
5. Hog rings: AWG No. 12 (0.105") galvanized ASTM-A-116 Class 2. Fasten glare screen to top and bottom tension wire spaced approximately 2' apart.
6. Glare Screens: 18 Gauge steel, ASTM-A-526, galvanized ASTM-A-525/G235, expanded to the following dimensions: 1.33" shortway of diamond and 4.0" longway of diamond (center to center of bridges) with a strand width of 0.250" angled at approximately 20° to the plane of the original sheet. Top edge to be shop curved and crimped on 12" centers. Glare screen shall be installed such that flat portion of screen blocks light from headlights. See Direction Detail.
7. Splices allowed in glare screen at posts only, with one full diamond overlap.
8. Glare screen shall be constructed without interruption to the greatest degree possible.




ELEVATION




TENSION WIRE ROUTING DETAIL

DESIGN APPROVED <i>Jimmy H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 3/94
APPROVED FOR DISTRIBUTION <i>August M. Hines</i>	GLARE SCREEN CONCRETE MEDIAN BARRIER	DRAWING NO. C-10.97 Sheet 1 of 3


NO.	DESCRIPTION OF REVISIONS	DATE
1	MODIFIED STANDARD & ADDED SH-2	3/94
2		
3		
4		




CROSS BRACE POST DETAIL




INTERMEDIATE POST DETAIL




TYPE A WIRE TIE




TYPE B WIRE TIE




TYPICAL POST DETAIL



SECTION A-A



DIRECTION DETAIL



TYPE C WIRE TIE

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 3/94
APPROVED FOR DISTRIBUTION <i>James H. Ottum</i>	CLARE SCREEN CONCRETE MEDIAN BARRIER	DRAWING NO. C-10.97 Sheet 2 of 3

A technical diagram showing a wire mesh assembly. A rectangular frame is shown with a diagonal wire mesh. Two long, thin wires, labeled "Tension Wire", are shown running diagonally across the mesh. One wire is positioned above the mesh, and the other is positioned below it. A coiled spring is shown in the center of the mesh, with a line pointing to it from the label "Tension Wire". To the left of the mesh, there is a series of four circular components, possibly washers or spacers, arranged in a row. The entire assembly is shown in a perspective view.


A technical diagram showing a wire mesh assembly. A diagonal wire, labeled "Bottom Tension Wire", runs through a rectangular frame. The wire is connected to a series of circular components (possibly pulleys or rollers) on the left side. The mesh is depicted as a series of intersecting lines forming a diamond pattern.

Diagram illustrating the components of a wire rope clamp assembly:


- Hex Nut with  $\frac{1}{2}$ " Regular Helical Spring Lock Washer
- $\frac{1}{2}$ " Narrow Type A Plain Washer
- $\frac{5}{8}$ " Wide Type A Plain Washer
- Glare Screen
- Tension Wire
- $\frac{1}{2} \times 2\frac{1}{2}$ " Hex Head Bolt

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 3/94
APPROVED FOR CONSTRUCTION <i>Robert T. Hark</i>	GLARE SCREEN CONCRETE MEDIAN BARRIER	DRAWING NO. C-10.97 Sheet 2 of 3


NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	ADDED DETAIL	7/84	PHS
2	DELETED NOTE	7/84	PHS
3	ADDED NOTE	7/84	PHS




PLAN




SECTION A-A




SECTION B-B




ANGLE ASSEMBLY DETAIL NO. 1



ANGLE ASSEMBLY DETAIL NO. 2



ANGLE ASSEMBLY DETAIL NO. 3



END VIEW

## GENERAL NOTES

- Cattle guard shall be sloped to conform to the roadway grade and cross section, except that where an odd number of grill units is specified in a crowned roadway, the center grill unit shall have a level cross slope.
- Grill units shall be set on an angle assembly consisting of one 6"x3 1/2"x3/8" angle and 3/8" diameter studs with head. The studs shall be placed on 1'-0" alternate centers. See Angle Assembly Detail No. 2.
- Where the adjacent roadway is paved, an angle assembly shall consist of one 4"x4"x3/8" angle and 3/8" diameter studs with head. The studs shall be placed on 1'-0" alternate centers. See Angle Assembly Detail No. 1.
- Where the adjacent roadway is unpaved, an angle assembly shall consist of one 4"x4"x3/8" angle and one 2"x2"x3/8" angle and connected with 3/8" diameter studs. The assembly shall be crowned at the centerline and constructed with a bevel cut and welded. The studs shall be bent 90° and placed on 1'-0" centers. See Angle Assembly Detail No. 3.
- Each angle and angle assembly shall be fabricated to form a single piece for the full length of the cattle guard.
- Quantities shown for concrete and reinforcing bars are to be considered approximations for informational purposes only.
- When guard rail is to be used at the cattle guard, it may be possible to reduce the number of grill units required.

## UNIT TABLE


Roadway Width (Feet)	Grill Units Required	Concrete Cubic Yards	Rebar Lbs
12	2	5.8	173.3
16	3	8.0	240.9
20	4	10.3	308.5
28	5	12.5	375.1
34	6	14.7	443.7
36	6	14.7	443.7
38	7	16.9	511.2
40	7	16.9	511.2

DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Kella</i>	ROADWAY CATTLE GUARD	DRAWING NO. C-11.10 Sheet 1 of 3


DESIGN APPROVED <i>Joseph H. Ottewill</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	① ROADWAY CATTLE GUARD	DRAWING NO. C-11-10 Sheet 2 of 3

DESIGN APPROVED <i>Joseph H. Otten</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV.  10/95
APPROVED FOR DISSEMINATION <i>David M. Williams</i>	ROADWAY CATTLE GUARD	DRAWING NO. C-11.10 Sheet 3 of 3


NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	FROM OLD STD C-11.17	PHB	7/94
2			
3			




END VIEW




POST AND BRACE ASSEMBLY



SECTION E-E



SECTION D-D



SHOULDER TRANSITION AT CATTLE GUARDS


## GENERAL NOTES

- I. Material for shoulder transition shall be placed to the finished roadway elevation for the entire length of the transition. When the roadway is paved, Aggregate Subbase or Aggregate Base shall be used. When Roadway is unpaved, a material equivalent to the existing roadway shall be used.


DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Kenneth Williams</i>	ROADWAY CATTLE GUARD	DRAWING NO. C-11.10 SHEET 3 OF 3




NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	MODIFIED NOTE	PHB	7/94
2			
3			
4			



PLAN




SECTION C-C  
IN EMBANKMENT




SECTION C-C  
WHERE USED FOR THRU DRAINAGE-  
CATTLE GUARD OPEN BOTH ENDS

### GENERAL NOTES

1. See Std C-11.10 for all other Cattle Guard details.
2. This standard shall be used in embankment or where highly erodable soil is found.
3. All concrete shall be Class B.






SECTION A-A




SECTION B-B

DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Frankie Williams</i>	CATTLE GUARD, DRAINAGE	DRAWING NO. C-11.20






NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REARRANGED STD.	PMB	7/94
2			
3			
4			



DETAIL NO. 1



DETAIL NO. 2



DETAIL NO. 5

SHIM HEIGHT						
RAIL LBS/YD						
80	90	110	115	119	131	150
2 1/4"	2 3/8"	3 1/2"	3 3/8"	4 1/8"	4 3/8"	4 3/8"
3/8" DIAMETER GALVANIZED DOME HEAD SPIKE LENGTH						
11"	11"	11"	11"	13"	13"	13"

DESIGN APPROVED <i>Tracy H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>W. C. ...</i>	① CATTLE GUARD, RAILROAD	DRAWING NO. C-11.30


- GENERAL NOTES**
1. This design applicable only to wood tie track construction. Wood shims shall be unpainted and cut from material meeting the specifications of the existing ties.
  2. 3"x3"x3/8" treads, 2"x1/2" bearing bars and 2" nominal diameter pipe wing assemblies shall be primed with one coat of No. 1 paint and finished with two coats of yellow enamel paint.

DRAWING NO.  
C-12.10  
Sheet 1 of 5


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REISSUE STD	PMB	7/94
2			
3			

# GENERAL NOTES

1. Intermediate Post Assemblies shall be located as shown and at intervals not to exceed 650', or midway between all braced posts.
2. For game fence the bottom wire shall be barbless.
3. The stays on game fence shall have their ends turned up, to prevent injuries to game.




TYPICAL BARBED WIRE FENCE INSTALLATION-TYPE 2 BW SHOWN




DESIGN APPROVED <i>Lawrence H. Ottensmeyer</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	① FENCE, BARBED WIRE	DRAWING NO. C-12.10 Sheet 2 of 5

DESIGN APPROVED <i>Joseph H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Paul W. Wilson</i>	① FENCE, GATE, TYPE 1 AND 2 FLOOD GATE	DRAWING NO. C-12.10 Sheet 3 of 5

NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	REVISION STD	PHB	7/94
2			
3			
4			




PLAN






ELEVATION  
TYPICAL FLOOD GATE INSTALLATION

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	① FENCE, FLOOD GATE INSTALLATION	DRAWING NO. C-1210 Sheet 4 of 5


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISION	PMB	7/94
2			
3			
4			




TYPICAL FENCE LOCATION AT CATTLE GUARD




DETAIL A  
TYPICAL CROSS SECTIONS  
OF LINE POST SHAPES



DETAIL B  
INTERMEDIATE POST ASSEMBLY




DETAIL C  
END POST ASSEMBLY




DETAIL D  
CORNER POST ASSEMBLY

- GENERAL NOTES**
- Post assemblies shall consist of an upright angle 2 1/2 x 2 1/2 x 1/4 at 4.10 lbs/ft, and brace angles 2 x 2 x 1/4 at 3.19 lbs/ft.




TYPICAL FENCE LOCATION



DETAIL E  
FENCE CONNECTION TO WINGWALL

DESIGN APPROVED <i>Sherry H. Ottewill</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Rod Williams</i>	① FENCE, MISCELLANEOUS DETAILS	DRAWING NO. C-12.10 Sheet 3 of 5

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED DIMENSIONS	AME	3/94
2			
3			



TYPICAL CHAIN LINK FENCE INSTALLATION - TYPE I SHOWN

TYPICAL POST DIMENSIONS								
Fabric Height	Corner, End, Intermediate, Gate, Latch and Pull Posts					Line Posts		
	Round		Roll Formed			Round		Roll Formed
	Length	(OD)	□	□	□	Length	(OD)	H-Section □
36"	6'-0"	2.375"	3.50"x3.50"	2.25"x1.70"	5'-6"	1.900"	1.875"x1.625"	1.875"x1.625"
48"	7'-0"	2.375"	3.50"x3.50"	2.25"x1.70"	6'-6"	1.900"	1.875"x1.625"	1.875"x1.625"
60"	8'-0"	2.375"	3.50"x3.50"	2.25"x1.70"	7'-6"	1.900"	1.875"x1.625"	1.875"x1.625"
72"	9'-0"	2.375"	3.50"x3.50"	2.25"x1.70"	8'-6"	1.900"	1.875"x1.625"	1.875"x1.625"
Over 72"	Height +3'-0"	2.875"	3.50"x3.50"	2.50"x2.50"	Height +2'-6"	2.375"	2.250"x2.000"	1.875"x1.625"

## GENERAL NOTES

- Posts shall be round, H-section, or roll-formed and shall conform to the nominal dimensional requirements shown on the plans. Dimensional tolerances for all shapes shall be according to ASTM A-500. In addition, the material of which posts are fabricated shall have a nominal thickness, before galvanizing, of not less than 0.111" for line posts and 0.130" for terminal posts.
- Chain link fabric shall be either zinc-coated or aluminum-coated steel wire fence fabric. Zinc-coated steel fabric shall conform to the requirements of ASTM A392, Class 1 coating. Aluminum-coated steel fabric shall conform to the requirements of ASTM A491, with a minimum weight of coating of 0.40 ounce per square foot of wire surface area. Fabric shall be 11 gauge for all fence fabric 60 inches or less in height and shall be 9 gauge for fabrics greater than 60 inches in height.
- Tension wires shall be 7 gauge (0.177 inch diameter) coil spring steel wire with a minimum tensile strength of 75,000 pounds per square inch and shall be zinc-coated or aluminum-coated.
- Truss rods shall be 3/8 inch diameter adjustable rods. Truss tighteners shall have a strap thickness of not less than 1/4 inch.
- Stretcher bars shall be 3/8 inch by 1/4 inch steel flat bars. Stretcher bar bands shall be 1/8 inch by one inch preformed steel bands.
- Bottom tension wire shall be 3 inches from top of crown on concrete footings.
- Intermediate post assemblies shall be spaced at 500 foot intervals or midway between pull posts when the distance between such posts is less than 1,000 feet and more than 500 feet.
- See sheet 3 of 3 for typical fence location.

DESIGN APPROVED  
*James H. Ottens*  
 APPROVED FOR  
 DISTRIBUTION  
*James H. Ottens*


STATE OF ARIZONA  
 DEPARTMENT OF TRANSPORTATION  
 DIVISION OF HIGHWAYS  
 STANDARD DRAWINGS

FENCE, CHAIN LINK TYPE I

REV. 3/94  
 DRAWING NO. C-12.20  
 Sheet 1 of 3



NO.	DESCRIPTION OF REVISIONS	DATE BY	DATE
1	MODIFIED DIMENSIONS	PHB	3/94
2			
3			
4			




TYPICAL CHAIN LINK FENCE INSTALLATION - TYPE 2 SHOWN

TYPICAL POST DIMENSIONS							
Fabric Height	Corner, End, Intermediate, Gate, Latch and Pull Posts				Line Posts		
	Round		Roll Formed		Round		Roll Formed
	Length	(OD)	Es	□	Length	(OD)	H-Section □
72"	① 8'-6"	2.375"	3.50"x3.50"	2.50"x2.50"	8'-0"	1.900"	1.875"x1.625" 1.875"x1.625"

## GENERAL NOTES



1. Barbed wire for use with Type 2 chain link fence shall be 12 gauge steel wire with 4 point 14 gauge barbs spaced five inches apart and shall be either zinc-coated or aluminum-coated. Zinc-coated steel wire shall conform to the requirements of ASTM A121, Class 1 coating. Aluminum-coated steel wire shall conform to the requirements of ASTM 1585, Type 1, Class 1 coating.
2. Barbed wire support arm shall be of the type shown on the plans, shall be fabricated from commercial quality steel, and shall be zinc-coated in accordance with the requirements of AASHTO M11.
3. Bottom tension wire shall just clear top of crown on concrete footings.
4. For details and notes not shown - see chain link fence Type 1, sheet 1 of 3.
5. See sheet 3 of 3 for typical fence location.



DETAIL G  
BARBED WIRE SUPPORT ARM


DESIGN APPROVED <i>Lucy H. Ottomero</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 3/94
APPROVED FOR CONSTRUCTION <i>Greg A. Harte</i>	FENCE, CHAIN LINK TYPE 2	DRAWING NO. C-12.20 Sheet 2 of 3

NO.	DESCRIPTION OF REVISION	DATE
1	MODIFIED DRAWING	Feb 3/94
2		
3		
4		




SECTION A-A  
DOUBLE GATE LATCH ASSEMBLY

ROLLING GATE




SINGLE GATE



DOUBLE GATE

TYPICAL GATE DIMENSIONS									
SINGLE AND DOUBLE SWING GATES						ROLLING GATES			
Gate Leaf Width	Vertical Braces	Gate Post Size	Gate Leaf Width	Vertical Braces	Gate Post Size	Gate Leaf Width	No. of Equally Spaced Vertical Braces	Tension Rods Per Braced Panel	Gate Post Size
6' H or Less		00	Over 6' H		00				00
3' to 8'	0	2.8750"	3' to 8'	0	2.8750"	6' to 13'	1	0	2.8750"
8' to 16'	1	4.0000"	8' to 16'	1	4.0000"	13' to 16'	1	1	2.8750"
16' to 18'	2	4.0000"				16' to 21'	2	1	2.8750"
						21' to 27'	2	1	2.8750"
						28' and Larger	3	1	2.8750"


GATES FOR CHAIN LINK FENCE - TYPE 1 SHOWN  
(Type 2, With Barbed Wire Typical)




① TYPICAL FENCE LOCATION

DESIGN APPROVED <i>Tony H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 3/94
APPROVED FOR DISTRIBUTION <i>Charles M. Harty</i>	FENCE, CHAIN LINK GATES	DRAWING NO. C-12.20 Sheet 3 of 3

NO.	DESCRIPTION OF REVISIONS	DATE BY	CHK
1	REVISED SPECIFICATION REFERENCE	PHB	10/96
2			
3			
4			



ELEVATION



PLAN


## GENERAL NOTES

- All concrete shall be Class S, 4000 psi.
- All bolts, nuts, washers and fittings shall meet the dimensional requirements of the American National Standards Institute, unless otherwise designated and shall be galvanized in accordance with ASTM A153.
- Galvanized swaged fitting and U-Bolt shall conform to ASTM A449.
- The 1/4" galvanized wire rope shall conform to AASHTO M30 Class B, Type 2.
- The wire fabric, ties, bands, stretcher bars, and other fittings and hardware shall conform to AASHTO M181.
- The wire fabric fence shall follow contour of the graded median.
- The excavation for the concrete anchor blocks shall be to neat lines. Maximum excess shall be 3".
- Perforated posts shall be square tube formed from 0.105" USS gauge ASTM A 366/A 366M cold rolled carbon steel. The square tubes shall be welded directly in the corner by high frequency resistance welding or equal. The posts to be externally scarfed to agree with standard corner radii of 1/8" ± 1/16".
- Perforated posts shall be galvanized to the requirements of ASTM A 653/A 653M. Coating Designator shall be Z275.
- The cables shall have enough tension to prevent sagging. The location of the concrete anchor blocks may also be varied to provide enough tension to help prevent sagging.
- Two interior U-bolt and clamp bars shall be spaced at 1/3 of the distance between posts.
- See Standard C-12.20 for 48" fabric details.
- An alternate to rectangular concrete anchor block shall be a 36" diameter round footing with an additional depth of 4".
- The median approach grade within 100'± of the Chain Link Cable Barrier should not exceed a grade break of 10 percent.


NOTES  
Shown G4 (2W) System Without  
Curb. May Use Other Systems  
With or Without Curb.

DESIGN APPROVED <i>Joseph H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald J. Williams</i>	CHAIN LINK CABLE BARRIER	DRAWING NO. C-12.30 Sheet 1 of 3

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REWORKED STD	PM	1/84
2			
3			



ELEVATION



PLAN

NOTE:  
Shown G4 (2W) System Without  
Curb. May Use Other Systems  
With or Without Curb.

## GENERAL NOTES

1. All concrete shall be Class 5, 4000 psi.
2. All bolts, nuts, washers and fittings shall meet the dimensional requirements of the American National Standards Institute, unless otherwise designated and shall be galvanized in accordance with ASTM A153.
3. Galvanized swaged fitting and U-Bolt shall conform to ASTM A449.
4. The  $\frac{3}{4}$ " galvanized wire rope shall conform to AASHTO M30 Class B, Type 2.
5. The wire fabric, ties, bands, stretcher bars, and other fittings and hardware shall conform to AASHTO M181.
6. The wire fabric fence shall follow contour of the graded median.
7. The excavation for the concrete anchor blocks shall be to neat lines. Maximum excess shall be 3".
8. Perforated posts shall be square tube formed from 0.105" USS gauge ASTM A366 cold rolled carbon steel. The square tubes shall be welded directly in the corner by high frequency resistance welding or equal. The posts to be externally scarfed to agree with standard corner radii of  $\frac{1}{2}$ "  $\pm$   $\frac{1}{16}$ ".
9. Perforated posts shall be galvanized to the requirements of ASTM A525. Coating Designer shall be G-50.
10. The cables shall have enough tension to prevent sagging. The location of the concrete anchor blocks may also be varied to provide enough tension to help prevent sagging.
11. Two interior U-bolt and clamp bars shall be spaced at  $\frac{1}{3}$  of the distance between posts.
12. See Standard C-12.20 for 48" fabric details.
13. An alternate to rectangular concrete anchor block shall be a 36" diameter round footing with an additional depth of 4".
14. The median approach grade within 100' of the Chain Link Cable Barrier should not exceed a grade break of 10 percent.

DESIGN APPROVED  
*Joseph Ottum*  
APPROVED FOR  
DISTRIBUTION  
*Robert*



STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV.  
7/94

CHAIN LINK CABLE BARRIER


DRAWING NO.  
C-12.30  
Sheet 1 of 3

REV.	DESCRIPTION OF REVISION	DATE	BY
1	REVISION 510	7/94	




DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Ronald K. ...</i>	① CHAIN LINK CABLE BARRIER	DRAWING NO. C-12,30 Sheet 2 of 3


NO.	DESCRIPTION OF REVISION	DATE
1	MESSAGE STD	7/94
2		
3		




VIEW 3  
U-BOLT AND CLAMP BAR




VIEW 4  
CABLE CLAMP ASSEMBLY



VIEW 5  
ANCHOR PLATE




VIEW 6  
STRETCHER BAR BAND ASSEMBLY




VIEW 7  
SWAGED CABLE ASSEMBLY

DESIGN APPROVED <i>Henry H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Robert J. Gable</i>	① CHAIN LINK CABLE BARRIER	DRAWING NO. C-12.30 Sheet 3 of 3


REVISED NOTE	DESCRIPTION OF REVISIONS	DATE	BY
1			
2			
3			




CULVERT INSTALLATION WITHOUT END TREATMENT




CULVERT INSTALLATION WITH END SECTION




CULVERT INSTALLATION WITH HEADWALL



PLAN




ELEVATION WITH END SECTION



ELEVATION


PLATING SLOPES AT PIPE LOCATIONS




Diameter or Span	Installation Type	
	Projecting (W)	Headwall (E)
18"	12"	2'-6"
24"	12"	3'-0"
30"	15"	3'-9"
36"	18"	4'-6"
42"	21"	5'-3"
48" to 66"	D or S/2	D + 36"
72" and Over	36"	D + 36"

MULTIPLE INSTALLATIONS WITHOUT END SECTIONS

1. See plans for any required inlet and/or outlet protection.
2. See remaining C-13 Series standards, Std B-11.11 and Std B-11.14.
3. Dimensions W and E apply to both non-trench and trench conditions.
- ① 4. Minimum cover over pipe culverts shall be 12", measured from the top of pipe.
5. See Pipe Berm Requirement Detail for pipe berm requirements and Std C-03.10 for installation. If Point A is within the recovery area, then a pipe berm is required and Point B is set at the edge of the recovery area.
6. Plating of slopes at pipe locations similar for pipes without end sections and for multiple pipe installations.




PIPE BERM REQUIREMENT DETAIL




MULTIPLE INSTALLATIONS WITH END SECTIONS

DESIGN APPROVED <i>Joseph Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Ronald L. Brown</i>	PIPE CULVERT INSTALLATION	DRAWING NO. C-13.10 Sheet 1 of 2


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MODIFIED NOTE	PMB	7/94
2	ADDED NOTE	PMB	7/94
3	MODIFIED TABLE	PMB	7/94
4	ADDED DETAIL	PMB	7/94




CULVERT INSTALLATION WITHOUT END TREATMENT




CULVERT INSTALLATION WITH END SECTION




CULVERT INSTALLATION WITH HEADWALL



PLAN



ELEVATION WITH END SECTION




MINIMUM SPACING FOR MULTIPLE INSTALLATIONS		
Diameter or Span	Installation Type	
	Projecting (W)	Headwall (E)
18"	12'	2'-6"
24"	12'	3'-0"
30"	15'	3'-9"
36"	18'	4'-6"
42"	21'	5'-3"
48" to 66"	(D or S)/2	D + 36"
72" and Over	36'	D + 36"

③ MULTIPLE INSTALLATIONS WITHOUT END SECTIONS


## GENERAL NOTES

1. See plans for any required inlet and/or outlet protection.
- ① 2. See remaining C-13 Series standards, Std B-11.11 and Std B-11.14.
- ① 3. Dimensions W and E apply to both non-trench and trench conditions.
- ② 4. Minimum cover over pipe culverts shall be 12".
- ② 5. See Pipe Berm Requirement Detail for pipe berm requirements and Std C-03.10 for installation. If Point A is within the recovery area, then a pipe berm is required and Point B is set at the edge of the recovery area.
- ② 6. Platting of slopes at pipe locations similar for pipes without end sections and for multiple pipe installations.




ELEVATION

PLATING SLOPES AT PIPE LOCATIONS



④ PIPE BERM REQUIREMENT DETAIL




MULTIPLE INSTALLATIONS WITH END SECTIONS


DESIGN APPROVED <i>Samuel J. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>David M. ...</i>	PIPE CULVERT INSTALLATION	DRAWING NO. C-13.10 Sheet 1 of 2




NO.	DESCRIPTION OF REVISION	DATE	BY
1	MODIFIED DETAIL	7/94	PMB
2	ADDED DETAIL	7/94	PMB
3	ADDED NOTE	7/94	PMB




② SPECIAL MULTIPLE PIPE END SECTION DETAIL  
FOR PIPE CULVERT EXTENSIONS ONLY




① PERFORATED CMP INSTALLATION



① PIPE AND CATCH BASIN INSTALLATION  
AT SAG CONDITION OF CUT DITCH



① PIPE AND CATCH BASIN INSTALLATION  
AT BASE OF TRANSVERSE DIKE




① PIPE AND CATCH BASIN INSTALLATION  
AT FACE OF TRANSVERSE DIKE

## GENERAL NOTES


1. Minimum cover on pipe culverts shall be 12".
2. See remaining C-13 Series standards for other pipe details.
- ③ 3. After welding, the damaged coating shall be cleaned by a wire brush and painted with at least one full coat of Paint No. 4, or given two coats of an approved hot asphalt paint, as directed by the Engineer.

DESIGN APPROVED <i>John H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>John H. Ottum</i>	PIPE CULVERT INSTALLATION	DRAWING NO. C-13.10 Sheet 2 of 2


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	ADDED NOTE	PMB	7/94
2	REARRANGED STD	PMB	7/94
3			
4			



**TRENCH CONDITION**  
IN NATURAL GROUND OR IN EMBANKMENT  
WITHOUT BRACING




**TRENCH CONDITION**  
IN NATURAL GROUND OR IN EMBANKMENT  
WITH BRACING SHOWN



**TRENCH CONDITION**  
NRCICP IN NATURAL GROUND  
OR IN EMBANKMENT

## GENERAL NOTES

- Pipes shall be installed either in a trench condition or in a non-trench condition in natural ground or in embankment.
- In a trench condition, the vertical and horizontal limits shall be maintained. If horizontal limits are exceeded or the vertical limits are not maintained, a non-trench condition exists.
- Bracing and sloping shall conform to OSHA requirements.
- Pipe backfill may be bedding material.
- In a non-trench condition, the embankment for pipe stability shall be constructed in lifts to the limits shown in the detail simultaneously with the bedding material and pipe backfill. If the contractor chooses to construct it as a trench condition, the embankment shall be constructed before excavating the trench.
- Outside diameter of full circle pipe or outside dimension (span or rise) of arch, arch pipe, elliptical pipe.
- Minimum wall thickness for NRCICP. See Plans.
- D=2 feet maximum for diameters up to 4 feet and D+3 feet maximum for diameters 4 feet and over.
- 6 inches except when on unyielding or unstable material. See standard specifications.




**NON-TRENCH CONDITION**


- TRENCH BACKFILL
- PIPE BACKFILL
- BEDDING

DESIGN APPROVED <i>Joseph L. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>R. A. [Signature]</i>	② TYPICAL PIPE INSTALLATION	DRAWING NO. C-13.15

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REPLACE STD	PHB	7/94
2			
3			
4			




PLAN




SECTION A-A

Pipe Dia	Approx Weight	Dimensions - Inches						Approx Slope
		T	A	B	C	E	F	
24"	1520*	3	9 1/2	43 1/2	30	73 1/2	48	3
27"	1930*	3 1/4	10 1/2	49 1/2	24	73 1/2	54	3
30"	2190*	3 1/2	12	54	19 3/4	73 3/4	60	3
36"	4100*	4	15	63	34 3/4	97 3/4	72	3
42"	5380*	4 1/2	21	63	35	98	78	3




SPACING FOR MULTIPLE INSTALLATION




FRONT ELEVATION

## GENERAL NOTES

- Design of end section shall conform to standards.
- End section joint conformation shall match the pipe joints.
- Embankment slope shall be warped to match slope of end section.




RIGHT ANGLE CULVERT




SKewed CULVERT

DESIGN APPROVED <i>James H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Ronald M. Miller</i>	① PIPE, REINFORCED CONCRETE END SECTION	DRAWING NO. C-13.20


NO.	DESCRIPTION OF REVISION	DATE	BY
1	CORRECTED SPELLING OF "EMBANKMENT"	10-95	
2			
3			



RIGHT ANGLE CULVERT




SKWEDED CULVERT




# GENERAL NOTES


1. The end section may be jointed to the pipe or connector section by bolts, rivets, dimpled bands, slip-seam bands or threaded rod type fasteners. For allowable connector types, see table.
2. The type 1 connector is by means of bolts or rivets. Maximum circumferential fastener spacing shall be 12" and with a minimum of 8 fasteners per joint. The type 1 joint may be used with either annular or helical corrugations.
3. Type 2 and 3 connectors shall be used only with annular or helical pipe with a requisite number of annular corrugations.
4. Type 4 and 5 connectors shall be only used with helical pipe.
5. All steel end section components shall be galvanized.
6. Toe of embankment shall be warped to match toe of skewed end section.
7. A berm shall be added to abnormal projections per Std C-13.10.
8. The foregoing applies to all cross section configurations.



TYPE 1  
RIVETED OR BOLTED CONNECTIONS




TYPE 2  
THREADED ROD CONNECTIONS




SPACING FOR MULTIPLE  
INSTALLATION


		Dimensions - Inches							
Pipe Dia	Ga	A ±1	B Max	H ±1	L 1/2 ±1/2	W ±2	Approx Slope	Connection Type	
18"	16	8	8	6	31	36	2 1/2	1, 2, 3, 4, 5	
24"	16	10	13	6	41	48	2 1/2	1, 2, 3, 4, 5	
30"	14	12 1/4	12 1/2	8	51	57	2 1/2	1, 2, 4, 5	
36"	14	14 1/2	12	9	60	72	2 1/2	1, 2, 4, 5	
42"	12	17	11	10 1/2	69	84	2 1/2	1	



TYPE 3  
THREADED ROD CONNECTIONS



TYPE 4  
DIMPLED BAND CONNECTIONS



TYPE 5  
SLIP SEAM CONNECTIONS

		Dimensions - Inches							
Pipe Arch									
Span	Rise	Ga	A ±1	B Max	H ±1	L 1/2 ±1/2	W ±2	Approx Slope	Connection Type
21"	15"	16	7 1/2	11	6	24	36	2 1/2	1, 2, 3, 4, 5
28"	20"	16	8	16	6	32	48	2 1/2	1, 2, 3, 4, 5
35"	24"	14	10	16	6	39	60	2 1/2	1, 2, 4, 5
42"	29"	14	12	12	7 1/2	46	75	2 1/2	1, 2, 4, 5
49"	33"	12	13 1/2	20	9	53	84	2 1/2	1


DESIGN APPROVED  
*John H. Ottens*  
APPROVED FOR  
DISTRIBUTION  
*Robert M. Ottens*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS


REV.  
10/95

PIPE, CORRUGATED METAL  
END SECTION


DRAWING NO.  
C-13.25




RIGHT ANGLE CULVERT




SKEWED CULVERT




TYPE 1  
RIVETED OR BOLTED CONNECTIONS




TYPE 2  
THREADED ROD CONNECTIONS




SPACING FOR MULTIPLE  
INSTALLATION



TYPE 3  
THREADED ROD CONNECTIONS



TYPE 4  
DIMPLED BAND CONNECTIONS



TYPE 5  
SLIP SEAM CONNECTIONS

## GENERAL NOTES

- The end section may be jointed to the pipe or connector section by bolts, rivets, dimpled bands, slip-seam bands or threaded rod type fasteners. For allowable connector types, see table.
- The type 1 connector is by means of bolts or rivets. Maximum circumferential fastener spacing shall be 12" and with a minimum of 8 fasteners per joint. The type 1 joint may be used with either annular or helical corrugations.
- Type 2 and 3 connectors shall be used only with annular or helical pipe with a requisite number of annular corrugations.
- Type 4 and 5 connectors shall be only used with helical pipe.
- All steel end section components shall be galvanized.
- Toe of embankment shall be warped to match toe of skewed end section.
- A berm shall be added to abnormal projections per Std C-13.10.
- The foregoing applies to all cross section configurations.

Dimensions - Inches									
Pipe Dia	Ga	A ±1	B Max	H ±1	L ±1/2	W ±2	Approx Slope	Connection Type	
18"	16	8	8	6	31	36	2 1/2	1, 2, 3, 4, 5	
24"	16	10	13	6	41	48	2 1/2	1, 2, 3, 4, 5	
30"	14	12 1/4	12 1/2	8	51	57	2 1/2	1, 2, 4, 5	
36"	14	14 1/2	12	9	60	72	2 1/2	1, 2, 4, 5	
42"	12	17	11	10 1/2	69	84	2 1/2	1	

Dimensions - Inches									
Pipe Arch			A ±1	B Max	H ±1	L ±1/2	W ±2	Approx Slope	Connection Type
Span	Rise	Ga							
21"	15"	16	7 1/2	11	6	24	36	2 1/2	1, 2, 3, 4, 5
28"	20"	16	8	16	6	32	48	2 1/2	1, 2, 3, 4, 5
35"	24"	14	10	16	6	39	60	2 1/2	1, 2, 4, 5
42"	29"	14	12	12	7 1/2	46	75	2 1/2	1, 2, 4, 5
49"	33"	12	13 1/2	20	9	53	84	2 1/2	1

DESIGN APPROVED

*John H. Ottum*

APPROVED FOR

*Don K. Kellum*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV.


7/94

① PIPE, CORRUGATED METAL  
END SECTION


DRAWING NO.

C-13.25


NO.	REVISION OR COMMENT	DATE
1	REVISED GENERAL NOTE	10-95
2		
3		
4		




HEADWALL INSTALLATION



PROJECTING INSTALLATION



SECTION A-A




SECTION B-B

### GENERAL NOTES


1. For lateral dimensions of Invert paving, use 72° control for CMP and span for CMPA.
2. Paving shall be scored laterally at 1'-6" minimum intervals along the length of the pipe.
3. Use bevel on Inlet headwall only.
4. Wire mesh shall be fastened or welded to corrugation crests at intervals and in a manner approved by the Engineer. Laps shall be 6" minimum.
5. Paving shall not be placed until backfilling is completed.
6. Concrete shall be Class B.
7. See Std C-14.20 for headwall and bevel dimensions not shown.

DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald K. Kellum</i>	PIPE AND PIPE ARCH, CORRUGATED METAL CONCRETE INVERT PAVING	DRAWING NO. C-13.30


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED STD	PHB	7/94
2			
3			
4			




HEADWALL INSTALLATION



PROJECTING INSTALLATION



SECTION A-A




SECTION B-B

## GENERAL NOTES


1. For lateral dimensions of invert paving, use 72° control for CMP and span for CMPA.
2. Paving shall be scored longitudinally at 1'-6" minimum lateral intervals.
3. Use bevel on inlet headwall only.
4. Wire mesh shall be fastened or welded to corrugation crasts at intervals and in a manner approved by the Engineer. Laps shall be 6" minimum.
5. Paving shall not be placed until backfilling is completed.
6. Concrete shall be Class B.
7. See Std C-14.20 for headwall and bevel dimensions not shown.

DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Donald L. L...</i>	① PIPE AND PIPE ARCH, CORRUGATED METAL CONCRETE INVERT PAVING	DRAWING NO. C-13.30

NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	AS APPROVED, ETS	7/94	PH
2			
3			
4			




LONGITUDINAL SECTION




PLAN NORMAL TO SLOPE

	D	T	S
Combination Vehicle and Cattle Pass	144"	1'-6"	Varies
Cattle Pass Only	120"	6"	Varies



SECTION A-A



END ELEVATION


## GENERAL NOTES

1. This end treatment is to be used only for those cattle and/or vehicle passes not used for drainage.
2. All concrete shall be Class B. An optional 12" AB Invert paving base course and 6" of concrete may be used in the 144" diameter pipe.
3. Anchor bolts shall be retained in a horizontal position during pour with final tightening a minimum of 7 days after pour.
4. Pipe shall be backfilled before concrete bond beam is constructed. Minimum forming may be used.
5. Edges of wire mesh shall be fastened or welded to corrugation crests at intervals and in a manner approved by the Engineer. Laps shall be a minimum of 6".
6. For Installation normal to roadway centerline only.


DESIGN APPROVED <i>David H. Ottensm</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	BY 7/94
APPROVED FOR CONSTRUCTION <i>David H. Ottensm</i>	① PIPE, CATTLE-VEHICLE PASS, MITERED END TREATMENT	DRAWING NO. C-13.55




NO.	REVISION	DATE
1	DESIGNED TYPE & C-100 AND GUTTER	10/95
2		
3		
4		




① TYPE D & G CURB AND GUTTER WITH SLOTTED DRAIN




SECTION A-A



SECTION B-B



TYPE B OR C CURB AND GUTTER WITH SLOTTED DRAIN









CONNECTION OF SLOTTED DRAIN TO CATCH BASIN AND SLOTTED DRAIN END CAP

## GENERAL NOTES

1. Slotted drain pipe shall be 27 1/2"x1/2" corrugated steel pipe with a minimum wall thickness of 0.064" and shall conform to the requirements of AASHTO M36.
2. All concrete shall be Class B.
3. Reinforcing steel shall conform to 1003-1, 2, Grade 40.
4. Structural steel shall conform to ASTM A36.
5. Concrete anchors shall conform to ASTM A307 and hex nuts shall conform to ASTM A563 Grade A.
6. All slotted drain pipe hardware except anchor bolts and reinforcing steel shall be given two coats of "I" paint.
7. When annular pipe is used, apply water proof sealer before attaching coupling band.
8. When helical pipe is used, it shall be formed with at least one annular corrugation at each end of each pipe section. Water proof sealer shall be applied to the annular corrugation prior to attachment of coupling band.
9. Cover slot during construction with removable tape or other acceptable substitute.
10. Slotted drain pipe shall be clean at the time of final acceptance.
11. Concrete curb and gutter thru the slotted drains shall be paid for under the respective curb and gutter items.
12. Refer to curb and gutter details for dimensions and details not shown.
13. Joints in concrete curb & gutter shall match adjoining PCCP and slotted drain bands.

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald M. Williams</i>	SLOTTED DRAIN DETAILS	DRAWING NO. C-13.60

REVISION	DATE	BY
1. CHANGED TO CONTINUOUS WELD PER STD SPECS	7/94	REV




# GENERAL NOTES

1. Slotted drain pipe shall be 2 1/4\" x 1/2\" corrugated steel pipe with a minimum wall thickness of 0.064\" and shall conform to the requirements of AASHTO M36.
2. All concrete shall be Class B.
3. Reinforcing steel shall conform to 1003-1, 2, Grade 40.
4. Structural steel shall conform to ASTM A36.
5. Concrete anchors shall conform to ASTM A307 and hex nuts shall conform to ASTM A563 Grade A.
6. All slotted drain pipe hardware except anchor bolts and reinforcing steel shall be given two coats of #1 paint.
7. When annular pipe is used, apply water proof sealer before attaching coupling band.
8. When helical pipe is used, it shall be formed with at least one annular corrugation at each end of each pipe section. Water proof sealer shall be applied to the annular corrugation prior to attachment of coupling band.
9. Cover slot during construction with removable tape or other acceptable substitute.
10. Slotted drain pipe shall be clean at the time of final acceptance.
11. Concrete curb and gutter thru the slotted drains shall be paid for under the respective curb and gutter items.
12. Refer to curb and gutter details for dimensions and details not shown.
13. Joints in concrete curb & gutter shall match adjoining PCCP and slotted drain bands.


## CONNECTION OF SLOTTED DRAIN TO CATCH BASIN AND SLOTTED DRAIN END CAP

DESIGN APPROVED <i>Joseph H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	SLOTTED DRAIN DETAILS	DRAWING NO. C-13.60

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REARRANGED STD	PHB	7/94
2			
3			




SECTION A-A  
TYPICAL CONNECTION BETWEEN  
CATCH BASIN AND MANHOLE




SECTION C-C  
TYPICAL CONNECTION BETWEEN  
CATCH BASIN AND MAIN STORM DRAIN




SECTION B-B



SECTION D-D



PLAN  
TYPICAL SLOTTED DRAIN AND CATCH BASIN  
INSTALLATION WITH MANHOLE



PLAN  
TYPICAL SLOTTED DRAIN AND CATCH BASIN  
INSTALLATION WITHOUT MANHOLE

## GENERAL NOTES


1. Pipe collars not required where direct catch basins connections can be made within 7' of a normal 90° installation, either horizontally or vertically.
2. "T" connections direct to the main drainage trunk line should be avoided and used only where manhole connections are impractical.

DESIGN APPROVED <i>Joseph H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Robert Williams</i>	① SLOTTED DRAIN INSTALLATION DETAILS	DRAWING NO. C-13.65


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REPLACED STD	PHD	7/94
2			
3			
4			

## GENERAL NOTES


1. Prefabricated tees shall be used when the outside diameter of the inlet pipe exceeds one half of the inside diameter of the main storm drain, except when the manholes are shown on plans.
2. Centerline of the inlet pipe shall intersect the centerline of the main storm drain except when elevation 'S' is shown on plans.
3. If  $\angle$  is 45° or less, type 1 shall be used.
4. All concrete shall be class B.
5. All reinforcing steel shall conform to 1003-1, 2, grade 40.
6. Reinforcing steel shall have 2" minimum cover.




SECTION A-A



CONNECTION DETAIL  
TYPE 2



SIDE INLET  
TYPE 1



CATCH BASIN ABOVE STORM DRAIN  
TYPE 2

DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>John J. Smith</i>	STORM DRAIN CONNECTION DETAILS	DRAWING NO. C-13.70




DESCRIPTION OF REVISIONS		DATE
1. BELLETER NOTE	PWB	7/94
2. BELLETER DETAIL	PWB	7/94
3.		
4.		


# GENERAL NOTES

1. Compact soil at end of pipe plug to 95% of maximum density.
2. If depth of cover is less than 5' or greater than 10', increase plug thickness a minimum of 4".

①  
①  
①



DRAINAGE OUTLET INTO CHANNEL




STORM DRAIN PLUG



②

DESIGN APPROVED <i>Samuel H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Samuel H. Ottum</i>	STORM DRAIN OUTLET DETAILS	DRAWING NO. C-13.75 Sheet 2 of 2

### CONCRETE PIPE COLLAR




- ## GENERAL NOTES
1. All Concrete shall be Class B.
  2. All reinforcing steel shall conform to 1003-1, 2, Grade 40.
  - ① 3. All reinforcing steel shall have 3" minimum clear cover.
  4. A concrete collar shall be required where pipes of different diameters or materials are joined or where the design change in alignment or grade exceeds that allowed for a standard joint.
  5. When pipes of different diameters are joined with a concrete collar, "I" & "I'" shall be those of the larger diameter.
  6. The diameter of the circular ties shall be the outside diameter of pipe + 1.
  7. Pipe ends to be trimmed such that the maximum distance between pipes at any point is 2'.




Pipe Size	L	T	#4 Ties
12"	1.00'	4"	3
18"	1.00'	5"	3
24"	1.00'	6"	3
30"	1.50'	8"	3
36"	1.50'	8"	3
42"	1.75'	10"	4
48"	1.75'	10"	4
52"	1.75'	10"	4
60"	1.75'	11"	4
66"	2.00'	11"	5
72"	2.00'	14"	5
78"	2.00'	14"	5
84"	2.25'	16"	5
96"	2.25'	16"	5


NO.	REVISION	DATE
1	CHANGED "GUTTER" TO "INLET"	10/95
2	COMPLETED SELLING	10/95




PLAN - CATCH BASIN TYPE I - SINGLE




PLAN - CATCH BASIN TYPE I - DOUBLE




DETAIL NO. 1



SECTION B-B  
USE THIS SECTION WHEN  $\pm \geq 8'$



DETAIL NO. 2




DETAIL NO. 3

## GENERAL NOTES

- Pipes can be placed in any wall.
- Sump floor shall have a wood trowel finish and a minimum 4:1 slope in all directions to outlet.
- All structural steel shall be ASTM A36.
- Welding shall be in accordance with Standard Welding Specifications.
- Grate, frame, beam and nose angle shall be given one shop coat of No. 1 paint.
- All concrete shall be Class B.
- Construction joints and drains shall be placed to meet field conditions. See Std C-15.70.
- Any specified inlet depression shall be warped to opening according to Std C-15.70.
- Curb opening areas, sq. ft., for type I-single and type I-double equal 0.25 and 0.54, respectively, for each inch of 'h' + Inlet depression - 2.35'. See Std C-15.70.
- See Stds C-15.50 and C-15.60 for grate and frame details and grate opening areas.
- - 1/4" for longitudinal and 3" for transverse bar grates.
  - - 2'-0" for LW, LB, EF, TW and TB series 1 grates, 1'-6" for LW, LB, EF, TW and TB series 2 grates. Use 1'-6" with combined curb and gutter.
  - - 2'-8 1/2" for LW, LB, EF, TW and TB series 1 grates, 2'-2 1/2" for LW, LB, EF, TW and TB series 2 grates.
- ① = 6" when H is 8' or less.
  - 8" when H is greater than 8'.
  - See Section B-B.

\*3 Bars, 6" C to C,  
1/2" Clear to Top of  
Nose and Inside of Wall  
Detail No. 3

Nose Angle and Anchor  
Detail No. 1




SECTION A-A


DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV 10/95
APPROVED FOR CONSTRUCTION <i>Ronald R. Riden</i>	CATCH BASIN, TYPE I	DRAWING NO. C-15.10



NO.	DESCRIPTION OF REVISION	DATE
1	ADDED LOCATION REFERENCE	7/94
2		
3		




PLAN - CATCH BASIN TYPE 1 - SINGLE




PLAN - CATCH BASIN TYPE 1 - DOUBLE


\*3 Bars, 6\" C to C, 1 1/2\" Clear to Top of Nose and Inside of Wall Detail No. 3




SECTION A-A




DETAIL NO. 1



SECTION B-B  
USE THIS SECTION WHEN  $\pm \geq 8'$



DETAIL NO. 2










DETAIL NO. 3

## GENERAL NOTES

- Pipes can be placed in any wall.
- Slump Floor shall have a wood trowel finish and a minimum 4:1 slope in all directions to outlet.
- All structural steel shall be ASTM A36.
- Welding shall be in accordance with Standard Welding Specifications.
- Grate, frame, beam and nose angle shall be given one shop coat of No. 1 paint.
- All concrete shall be Class B.
- Construction joints and drains shall be placed to meet field conditions. See Std C-15.70.
- Any specified gutter depression shall be warped to opening according to Std C-15.70.
- Curb opening areas, sq. ft., for type 1-single and type 1-double equal 0.25 and 0.54, respectively, for each inch of 'h' + gutter depression  $\times 2.35'$ . See Std C-15.70.
- See Stds C-15.50 and C-15.60 for grate and frame details and grate opening areas.
- \*  $\frac{3}{4}$ " for longitudinal and 3" for transverse bar grates.
  - \*\* - 2'-0" for LW, LB, EF, TW and TB series 1 grates, 1'-6" for LW, LB, EF, TW and TB series 2 grates. Use 1'-6" with combined curb and gutter.
  - \*\*\* - 2'-8 1/2" for LW, LB, EF, TW and TB series 1 grates, 2'-2 1/2" for LW, LB, EF, TW and TB series 2 grates.
- ①  $\pm$  = 6" when H is 8' or less, 8" when H is greater than 8'. See Section B-B.

DESIGN APPROVED <i>Jeff Hottel</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Frederick</i>	CATCH BASIN, TYPE 1	DRAWING NO. C-15.10

NO.	DESCRIPTION OF REVISIONS	DATE
1	CHANGED "OUTLET" TO "INLET"	10/95
2		
3		



## GENERAL NOTES

1. Type 3 - sump only.
2. Type 3-Wing (Illustrated), sump with wing basin upstream.
3. Type 3-Double wing, sump with symmetrical wing basin each side.
4. Pipes can be placed in any wall except wall adjacent to wing basin.
5. Sump floor shall have a wood trowel finish and a minimum slope of 4:1 in all directions toward outlet pipe.
6. Any specified inlet depression shall be warped to opening according to Std C-15.70.
7. All structural steel shall be ASTM A36.
8. Nose angle, frame and cover shall be given one shop coat of No. 1 paint.
9. All concrete shall be class B.
10. All reinforcing bars shall be #4, 1'-6" C to C both ways and 1/2" clear to inside of walls and outside of wing basin floor except as shown.
11. Curb opening area (sq ft) per inch of curb "h" + inlet depression = curb opening length (ft) x 0.0833.
12. Welding shall be in accordance with Standard Welding Specifications.
13. Construction joints at or below bottom of curb line. Construction joints and drains shall be placed to meet field conditions. Std C-15.70.


① H = 6" when H is 8" or less.  
8" when H is greater than 8".  
See Section B-B, Std C-15.10.

① H = 2'-10" min when L = 3'  
3'-0" min when L = 6'  
3'-2" min when L = 10'  
3'-7" min when L = 17'


DESIGN APPROVED <i>Joseph H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Donald A. Williams</i>	CATCH BASIN, TYPE 3	DRAWING NO. C-15.20




NO.	DESCRIPTION OF REVISIONS	DATE
1	CHANGED "CUTTER TO INLET"	10/95
2		
3		
4		




PLAN - CATCH BASIN TYPE 4 - SINGLE




PLAN - CATCH BASIN TYPE 4 - DOUBLE



SECTION A-A



SECTION B-B  
USE THIS SECTION WHEN t=8"




DETAIL NO. 1

## GENERAL NOTES


- Pipes can be placed in any wall.
- Sump floor shall have a wood trowel finish and a minimum 4% slope in all directions toward outlet pipe.
- Curb over catch basin shall not be constructed until catch basin concrete has set for a minimum of 24 hours.
- See Stds C-15.50 and C-15.60 for grate and frame details and opening areas.
- Any specified inlet depression shall be warped to opening according to Std C-15.70.
- All structural steel shall be ASTM A36.
- Grate, frame and beam shall be given one shop coat of No. 1 paint.
- All concrete shall be Class B.
- Construction joints and drains shall be placed to meet field conditions. Std C-15.70.
- \* - 3/4" for longitudinal and 3" for transverse bar grates.
  - \*\* - 2'-0" for LW, LB, EF, TW and TB series 1 grates, 1'-6" for LW, LB, EF, TW and TB series 2 grates. Use 1'-6" with combined curb and gutter.
- ① t = 6" when H is 8' or less.
  - 8" when H is greater than 8'.
  - See Section B-B.

DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>[Signature]</i>	CATCH BASIN, TYPE 4	DRAWING NO. C-15.30


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	ADDED NOTE	PHB	7/94
2	ADDED LOCATION REFERENCE	PHB	7/94
3			
4			




PLAN - CATCH BASIN TYPE 4 - SINGLE




PLAN - CATCH BASIN TYPE 4 - DOUBLE



SECTION A-A



SECTION B-B  
USE THIS SECTION WHEN  $\pm \geq 8'$




DETAIL NO. 1

## GENERAL NOTES


- Pipes can be placed in any wall.
- Sump floor shall have a wood trowel finish and a minimum 4:1 slope in all directions toward outlet pipe.
- Curb over catch basin shall not be constructed until catch basin concrete has set for a minimum of 24 hours.
- See Sids C-15.50 and C-15.60 for grate and frame details and opening areas.
- Any specified gutter depression shall be warped to opening according to Std C-15.70.
- All structural steel shall be ASTM A36.
- Grate, frame and beam shall be given one shop coat of No. 1 paint.
- All concrete shall be Class B.
- Construction joints and drains shall be placed to meet field conditions, Std C-15.70.
- $\bullet$  -  $\frac{1}{4}$ " for longitudinal and  $3'$  for transverse bar grates.
  - $\bullet$  -  $2'-0"$  for LW, LB, EF, TW and TB series 1 grates,  $1'-6"$  for LW, LB, EF, TW and TB series 2 grates. Use  $1'-6"$  with combined curb and gutter.
- $\textcircled{B} \pm$  =  $6'$  when H is  $8'$  or less,  $8'$  when H is greater than  $8'$ . See Section B-B.

DESIGN APPROVED <i>Henry H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	CATCH BASIN, TYPE 4	DRAWING NO. C-15.30



NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	CHANGED "GUTTER" TO "INLET"	PMB	10/95
2			
3			




Note:  
Reinforcing bars shown  
are for roof slab only.  
See sections for other  
reinforcing.



SECTION C-C  
USE THIS SECTION WHEN  $t \geq 8"$



DETAIL NO. 1



DETAIL NO. 2

## GENERAL NOTES

- Type 5 - sump only.
- Type 5 - Single Wing, (Illustrated), sump with wing basin upstream.
- Type 5 - Double Wing, sump with symmetrical wing basins each side.
- Pipes can be placed in any wall except wall adjacent to a wing basin.
- Sump floor shall have a wood trowel finish and a minimum slope of  $4\text{ft}$  in all directions toward outlet pipe.
- Any specified inlet depression shall be warped to opening according to Std C-15.70.
- All structural steel shall be ASTM A36.
- Nose angle shall be given one shop coat of No. 1 paint.
- All concrete shall be class B.
- All reinforcing bars shall be  $\#4$ ,  $1'-6"$  C to C both ways and  $1\frac{1}{2}"$  clear to inside of walls and outside of wing basin floor except as shown.
- Curb opening area (sq ft) per inch of curb  $h" + \text{inlet depression} = \text{curb opening length (ft)} \times 0.0834$ .
- Welding shall be in accordance with Standard Welding Specifications.
- See Std C-15.50 and C-15.60 for grate and frame details and opening areas.
- Construction joints and drains shall be placed to meet field conditions. Std C-15.70.
- $2'-0"$  for LW, LB, EF, TW and TB series 1 grates,  $1'-6"$  for LW, LB, EF, TW, and TB series 2 grates. Use  $1'-6"$  with combined curb and gutter.
  - $\frac{3}{4}"$  for longitudinal and  $3'$  for transverse bar grates.

$\text{H} = 6"$  when  $H$  is  $8'$  or less.  
 $8"$  when  $H$  is greater than  $8'$ .  
See Section C-C.

$H = 3'-3"$  min. when  $L = 3'$   
 $3'-5"$  min. when  $L = 6'$   
 $3'-7"$  min. when  $L = 10'$   
 $4'-0"$  min. when  $L = 17'$

DESIGN APPROVED

*James H. Ottum*

APPROVED FOR DISTRIBUTION

*Ronald K. Kellum*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV.


10/95

DRAWING NO.

CATCH BASIN, TYPE 5


C-15.40

REVISION	DESCRIPTION OF REVISION	DATE	BY
1	ADDED LOCATION REFERENCE	1/84	
2			
3			




Note:  
Reinforcing bars shown  
are for root slab only.  
See sections for other  
reinforcing.

PLAN




SECTION A-A


SECTION C-C  
USE THIS SECTION WHEN t=8"



SECTION B-B



DETAIL NO. 1



DETAIL NO. 2

## GENERAL NOTES

- Type 5 - sump only.
- Type 5 - Single Wing, (Illustrated), sump with wing basin upstream.
- Type 5 - Double Wing, sump with symmetrical wing basins each side.
- Pipes can be placed in any wall except wall adjacent to a wing basin.
- Sump floor shall have a wood trowel finish and a minimum slope of 4:1 in all directions toward outlet pipe.
- Gutter depression shall be warped to opening according to Std C-15.70.
- All structural steel shall be ASTM A36.
- Nose angle shall be given one shop coat of No. 1 paint.
- All concrete shall be class B.
- All reinforcing bars shall be #4, 1'-6" C to C both ways and 1/2" clear to inside of walls and outside of wing basin floor except as shown.
- Curb opening area (sq ft) per inch of curb "h" + gutter depression = curb opening length (ft) x 0.0834.
- Welding shall be in accordance with Standard Welding Specifications.
- See Std C-15.50 and C-15.60 for grate and frame details and opening areas.
- Construction joints and drains shall be placed to meet field conditions, Std C-15.70.
- 2'-0" for LW, LB, EF, TW and TB series 1 grate, 1'-6" for LW, LB, EF, TW, and TB series 2 grates. Use 1'-6" with combined curb and gutter.
  - 3/4" for longitudinal and 3" for transverse bar grates.

① = 6" when H is 8' or less.  
8" when H is greater than 8'.  
See Section C-C.

H = 3'-3" min, when L = 3'  
3'-5" min, when L = 6'  
3'-7" min, when L = 10'  
4'-0" min, when L = 17'

DESIGN APPROVED  
*Joseph Ottaviano*  
APPROVED FOR  
DISTRIBUTION  
*Donald A. Williams*


STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV.  
7/94




CATCH BASIN, TYPE 5

DRAWING NO.  
C-15.40




NO.	DESCRIPTION OF INCHANGES	DATE	BY
1	CHANGED BARS FROM 1/2" TO 3/8"	7/83	



SECTION  
GRATES TYPE LW-1 AND LW-2



SECTION A-A



## GENERAL NOTES

- LW = Longitudinal welded  
LB = Longitudinal bolted  
EF = Electroforged
- Grates type LW and EF are restricted to slopes of 3% or less.
- Use grate type LB on longitudinal grades in excess of 3% or as an alternate to type LW on grades of 3% or less.
- Grating units and frames shall be fabricated from structural steel ASTM A36 except as noted.
- All welding shall be in accordance with Standard Welding Specifications.
- The completed assembly shall be given one shop coat of No. 1 paint.
- Frames and grates shall fit to a maximum rock of 0.093" at any point.

Grate Type	Clear Bar Spacing	No. Bars	X	Grate Opening Sq Ft
LW or LB - 1.0	1"	16	$\frac{3}{8}$ "	3.97
LW or LB - 1.1	1 1/8"	13	$\frac{3}{8}$ "	4.34
LW or LB - 1.2	2"	9	$\frac{1}{2}$ "	4.84
EF - 1	1 1/8"	13	$\frac{3}{8}$ "	3.97
LW or LB - 2.0	1"	12	$\frac{3}{8}$ "	2.98
LW or LB - 2.1	1 1/8"	9	$\frac{1}{2}$ "	3.35
LW or LB - 2.2	2"	7	$\frac{1}{2}$ "	3.60
EF - 2	1 1/8"	10	$\frac{3}{8}$ "	2.95




$\frac{3}{8}$ " Anchors. Delete on One End When Used with I-beam Support

SECTION  
FRAME




DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 1/93
APPROVED FOR CONSTRUCTION <i>[Signature]</i>	CATCH BASIN, GRATES, LONGITUDINAL BARS	DRAWING NO. C-15-50



REV.	DESCRIPTION OF REVISION	DATE	BY
1	REARRANGED STD	7/94	PHB
2			
3			



SECTION  
GRATES TYPE TW-1 AND TW-2



## GENERAL NOTES

1. LW = Longitudinal welded  
LB = Longitudinal bolted  
EF = Electroforged
2. Restrict use to grades of 3% or less.
3. Grating units and frames shall be fabricated from Structural Steel ASTM A36 except as noted.
4. All welding shall be in accordance with Standard Welding Specifications.
5. The completed assembly shall be given one shop coat of No. 1 paint.
6. Frames and grates shall fit to a maximum rock of 0.093" at any point.
7. For Type EF grates, see Std C-15.50.

Grate Type	Clear Bar Spacing	No. Bars	X	Grate Opening Sq Ft
TW or TB - 1.0	1"	26	1"	3.21
TW or TB - 1.1	1 3/8"	21	1"	3.32
TW or TB - 1.2	2"	16	1"	4.66
TW or TB - 2.0	1"	26	1"	2.32
TW or TB - 2.1	1 3/8"	21	1"	2.41
TW or TB - 2.2	2"	16	1"	2.65

DESIGN APPROVED  
*Henry H. Ottensm*  
APPROVED FOR  
CONSTRUCTION  
*Tom Blum*


STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV.  
7/94


① CATCH BASIN, GRATES  
TRANSVERSE BARS

DRAWING NO.  
C-15.60


NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	CHANGED "OUTLET" TO "INLET"	FMB	10/95
2	REVISED DETAIL	FMB	10/95
3	REVISED NOTE TO INCLUDE INLET	FMB	10/95
4			




CATCH BASIN SPACING AT SUMP CONDITION



① INLET DEPRESSION




① INLET DEPRESSION  
CATCH BASIN WITH SLOTTED DRAIN



CATCH BASIN TYPE 4  
OFF ROADWAY LOCATION

Apron Shall Be Shaped to Suit Local Conditions and Shall Extend a Min of 4'-0" from Edge of Grate in All Directions. Grate Shall Be Depressed a Minimum of 4" Below Surrounding Terrain and Bearing Bars Shall Parallel Direction of Principal Flow.




CATCH BASIN CONSTRUCTION DRAIN  
DRAIN MAY BE DELETED AT OPTION OF ENGINEER

## GENERAL NOTES

1. No inlet depression shall extend into a traffic lane.
2. Maximum combined inlet and gutter depression is 3 inches. See Detail No. 1.
3. Maximum distance along curb between catch basins where full gutter depression is used is 10 feet.
4. See Std. C-15.80 for aprons used with C-15.80 Catch Basin.

## LEGEND

- - Normal pavement or gutter flow line elevation.
- - Depressed elevation.
- - Straight grade with downward slope.
- W - Normal gutter width per Std. C-05.10.
- ▲ - Types 1, 3, & 5.
- ◆ - Type 4 & C-15.91.



② DETAIL NO. 1

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald W. Davis</i>	CATCH BASIN MISC. DETAILS	DRAWING NO. C-15.70


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	ADDED NOTE	PMB	7/94
2	REVISED DETAIL	PMB	7/94
3			
4			

## GENERAL NOTES


1. No gutter depression shall extend into a traffic lane.
2. Maximum gutter depression is 3 inches. See Detail No. 1.
3. Maximum distance along curb between catch basins where full gutter depression is used is 10 feet.
4. See Std. C-15.80 for aprons used with C-15.80 Catch Basin.

## LEGEND


- - Normal pavement or gutter flow line elevation.
- - Depressed elevation.
- - Straight grade with downward slope.
- W - Normal gutter width per Std. C-05.10.
- ▲ - Types 1, 3, & 5.
- ◆ - Type 4 & C-15.91.




② CATCH BASIN SPACING AT SUMP CONDITION




② GUTTER DEPRESSION




② GUTTER DEPRESSION  
CATCH BASIN WITH SLOTTED DRAIN



CATCH BASIN TYPE 4  
OFF ROADWAY LOCATION




CATCH BASIN CONSTRUCTION DRAIN  
DRAIN MAY BE DELETED AT OPTION OF ENGINEER




DETAIL NO. 1

DESIGN APPROVED <i>Joseph A. Oller</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Michael J. ...</i>	CATCH BASIN MISC. DETAILS	DRAWING NO. C-15.70


1	DESCRIPTION OF REVISIONS	DATE BY	10/95
2	MOVED DIMENSION FROM PLAN VIEW	PHB	10/95
3			
4			
5			




PLAN



ELEVATION



SECTION Y-Y



SECTION Z-Z

# GENERAL NOTES


1. See also Std. C-13.10.
2. High point of headwall shall not project more than 3" above slope.
3. All concrete shall be Class B.
4. All reinforcing bars shall be Number 4, 1'-0" C to C and 3' clear to inside of walls and floor.

PIPE	DIMENSIONS									QUANTITIES					
	W		A	B	E	F	H	J	K	Concrete C.Y.				Reinforcing Steel	
										Single		Double		Lbs.	
	Single	Double								For Concrete Pipe Deduct	For Concrete Pipe Deduct	Single	Double		
I.D.	Single	Double	A	B	E	F	H	J	K	C.M.P.	For Concrete Pipe Deduct	C.M.P.	For Concrete Pipe Deduct	Single	Double
18"	2'-6"	5'-2"	2'-8"	1'-3"	9"	1'-3 5/8"	3'-1"	9"	1'-6"	0.76	0.03	1.12	0.06	75	107
24"	3'-0"	6'-6"	3'-6"	1'-7 1/2"	1'-1 1/2"	1'-11 3/8"	3'-5"	11"	2'-3"	1.00	0.04	1.55	0.09	92	136
30"	3'-6"	7'-10"	4'-4"	2'-0"	1'-6"	2'-7 1/4"	3'-9"	1'-1"	3'-0"	1.50	0.06	2.29	0.13	112	166
36"	4'-0"	9'-2"	5'-2"	2'-4 1/2"	1'-10 1/2"	3'-3 3/4"	4'-0"	1'-4"	3'-9"	1.96	0.09	3.01	0.17	145	214
42"	4'-6"	10'-6"	6'-0"	2'-9"	2'-3"	3'-10 3/4"	4'-4"	1'-6"	4'-6"	2.49	0.11	3.85	0.23	189	279


DESIGN APPROVED <i>Sam H. Ottman</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>David Williams</i>	CATCH BASIN, DROP INLET	DRAWING NO. C-15.75




NO.	DESCRIPTION OF REVISION	MADE BY	DATE	NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	REVISED PERSPECTIVE	PMB	7/94	1	REVISED DIMENSION	PMB	7/94
2	REVISED SLOPE	PMB	7/94	2	ADDED DIMENSION	PMB	7/94
3	ADDED NOTE	PMB	7/94				
4	ADDED DETAIL	PMB	7/94				




① PERSPECTIVE




GRATING DETAIL




DETAIL NO. 1



PLAN




SECTION A-A




## GENERAL NOTES

1. Apron shall be AC or portland cement concrete as specified on plans.
2. All concrete shall be Class B.
3. Grating shall be fabricated of structural steel.
4. Structural steel shall be in accordance with ASTM A36.
5. Welding shall be in accordance with Standard Welding Specifications.
6. Grating assembly shall be given one shop coat of No. 1 paint.
7. 'H' indicated on plans.

• 8' When Wall Height Exceeds 8'




SECTION B-B




④ MEDIAN DITCH GRADE DETAIL

DESIGN APPROVED <i>Samuel Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald L. Williams</i>	CATCH BASIN, MEDIAN FLUSH	DRAWING NO. C-15.60


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE




GRATING DETAIL




PLAN




SECTION C-C



SECTION A-A




SECTION D-D



DETAIL NO. 1

## GENERAL NOTES

1. Apron shall be AC or portland cement concrete as specified on plans.
2. All concrete shall be Class B.
3. Grating shall be fabricated of structural steel.
4. Structural steel shall be in accordance with ASTM A36.
5. Welding shall be in accordance with Standard Welding Specifications.
6. Grating assembly shall be given one shop coat of No. 1 paint.
7. 'H' indicated on plans.
- 8' When Wall Height Exceeds 8'



SECTION B-B

DIMENSION TABLE	
Slope	A
6:1	0.50'
4:1	0.75'
3:1	1.00'
2:1	1.50'

WALL HEIGHT DETAIL

DESIGN APPROVED <i>Henry H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	7/94
APPROVED FOR DISTRIBUTION	CATCH BASIN, MEDIAN SIDE SLOPE	DRAWING NO. C-15.81

**GENERAL NOTES**

- Concrete shall conform to the requirements for Class 5 Concrete. The minimum strength shall be 4000 psi.
- Grout shall be in accordance with Standard Specifications except water content shall be such that the consistency is proper for smooth trowling.
- Gate cross rods shall be resistance welded, fillet welded or electro-forged to bearing bars.
- The completed grate shall be given one shop coat of No. 1 paint.
- Foundation soil and backfill shall be in accordance with Section 203-5 of the Standard Specifications.

**PLAN**

10'-3"

3'-4"

3'-4 1/2"

2'-11 1/2"

3/8" Inserts to Match Grating Bolt Down Clips (6)

3/8" Lifting Inserts (4)

**SECTION A-A**

10'-0"

2'-6"

4x4-W2.9xW2.9 WWF

28"x20" CMPA

Grout

**SECTION B-B**

2'-0"

2'-6"

4x4-W2.9xW2.9 WWF

**END VIEW**

3'-4"

2'-6"

28"x20" CMPA Opening

**SECTION C-C**

2'-0"

2'-6"

**SECTION D-D**

2'-0"

2'-6"

**BOLT DOWN CLIP DETAIL**

1 1/2"x1/4"x2 1/2" Bar


3/8"x1/4" Bolt

1/8" Hole







NO.	DESCRIPTION OF REVISION	DATE	BY
1	REVISED LOCATION REFERENCE	7/94	PMB
2	MOVED FRAME & GRATE TO SHT 2	7/94	PMB
3			
4			



PLAN




SECTION A-A



NOTES:  
Bend Rebars and Cover with  
Two Layers of 4"x4" Timbers

TIMBER CAP DETAIL




SECTION B-B

## GENERAL NOTES


1. All concrete shall be Class B.
2. All reinforcing steel shall conform to 1003-1, 1003-2, Grade 40.
3. All reinforcing steel shall have 2" min clear cover unless otherwise noted.
4. Reinforcing steel shall be No. 4 rebar, 12" C to C horizontal & vertical in walls.
5. Pipe can be placed in any wall.
6. See Std C-13.60 and C-13.65 for more information and dimensions of slotted drains.
7. \*t = 6" when H is less than 8"  
= 8" when H is greater than 8"

DESIGN APPROVED <i>Joseph Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Rodriguez</i>	FREeway CATCH BASIN DETAILS	DRAWING NO. C-15.91 Sheet 1 of 2


REVISION	DESCRIPTION OF REVISION	DATE	BY
1	REVISED NOTE	10/95	PHB
2	REVISED DIMENSION	10/95	PHB
3	CORRECTED DIMENSIONS	10/95	PHB




PLAN VIEW  
FRAME



SECTION A-A




PLAN VIEW  
GRATE



SECTION B-B

- GENERAL NOTES**
1. All structural steel shall be in accordance with ASTM Spec's A-36.
  2. Grate design is not suitable for locations subject to bicycle traffic.
  3. All welding shall be in accordance with Standard Welding Specifications.
  4. The completed grate assembly (frame & grate) shall be given two shop coats of No. 1 paint.
  5. The installation and inspection of steel studs welded to steel acting as connection devices to the concrete shall conform to the American Welding Society's Structural Welding Code (AWS D1.1), Specifications 4.21-4.27.


GRATE AND FRAME DIMENSIONS					
Type	Curb Height	Gutter Width	Catch Basin Frame		Catch Basin Grate
			A	C	
B	6"	2'-6"	13 1/8"	26"-57'-40"	12 1/8"
C	3"	2'-6"	13 1/8"	18"-14'-22"	11 1/8"




BRACE PLATE DETAIL

DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>[Signature]</i>	FREeway CATCH BASIN DETAILS	DRAWING NO. C-15.91 Sheet 2 of 2


NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	MODIFIED TABLE	7/94	TYPE
2			
3			
4			




PLAN VIEW  
FRAME



SECTION A-A



PLAN VIEW  
GRATE




SECTION B-B

## GENERAL NOTES

1. All structural steel shall be in accordance with ASTM Spec's A-36.
2. All reinforcement steel shall conform to 1003-1, 1003-2, Grade 40.
3. All welding shall be in accordance with ADOT specifications.
4. The completed grate assembly (frame & grate) shall be given two shop coats of No. 1 paint.
5. The installation and inspection of steel studs welded to steel acting as connection devices to the concrete shall conform to the American Welding Society's Structural Welding Code (AWS D1.1), Specifications 4.21-4.27.









① GRATE AND FRAME DIMENSIONS						
Type	Curb Height	Gutter Width	Catch Basin Frame		Catch Basin Grate	
			A	Δ	C	Δ
B	6"	2'-6"	13 <sup>1</sup> / <sub>8</sub> "	26"-57"-40"	12 <sup>1</sup> / <sub>8</sub> "	26"-57"-40"
C	3"	2'-6"	13 <sup>3</sup> / <sub>8</sub> "	18"-14"-22"	11 <sup>7</sup> / <sub>8</sub> "	18"-14"-22"



BRACE PLATE DETAIL

DESIGN APPROVED <i>Joseph H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Ronald Williams</i>	FREeway CATCH BASIN DETAILS	DRAWING NO. C-15.91 Sheet 2 of 2

NO.	DESCRIPTION OF REVISION	DATE BY	DATE
1	MODIFIED C-STANDARD CALLOUT	PMB	10/95
2	BELETED C-STANDARD CALLOUT	PMB	10/95
3			
4			











## GENERAL NOTES

1. See Std C-15.91 for dimensions, sizes and details not shown for installation of catch basin and half barrier.
2. See Std C-13.60 for dimensions, sizes and details not shown for installation of slotted drain.
3. Unless otherwise noted, reinforcement steel in half barrier for installation with catch basin and slotted drain, shall conform to sizes and number specified.
4. The installation and inspection of steel studs welded to steel acting as a connection device to the concrete shall conform to AWS D1.1 and specifications 4.21 - 4.27.
5. Where applicable, see Std C-10.60 for weep hole placement.
6. See Std C-10.65 for additional general notes.
7. Grate design is not suitable for locations subject to bicycle traffic.

DESIGN APPROVED <i>Steve H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald K. Williams</i>	CATCH BASIN WITH HALF BARRIER	DRAWING NO. C-15.92

REARRANGED STD	OPERATION & LOCATION	WORK BY	DATE
3	ROTATED DETAIL	PHB	7/94
3		PHB	7/94







## GENERAL NOTES

- See Std C-15.91 for dimensions, sizes and details not shown for installation of catch basin and half barrier.
- See Std C-13.60 for dimensions, sizes and details not shown for installation of slotted drain.
- Unless otherwise noted, reinforcement steel in half barrier for installation with catch basin and slotted drain, shall conform to sizes and number specified.
- The installation and inspection of steel studs welded to steel acting as a connection device to the concrete shall conform to AWS D1.1 and specifications 4.21 - 4.27.
- Where applicable, see Std C-10.09 for weep hole placement.
- See Std C-10.99 for additional general notes.
- Gate design is not suitable for locations subject to bicycle traffic. See Std C-10.99.

DESIGN APPROVED <i>Joseph H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>James E. Sullivan</i>	CATCH BASIN WITH HALF BARRIER	DRAWING NO. C-15.92

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	CHANGED "DIVISIONS" TO "SECTIONS"	FMB	0/95
2			
3			







# GENERAL NOTES

1. All concrete shall be Class B.
2. All reinforcing bars shall be #4 except two #6 bars over pipe. Bar spacing approximately 1'-0" center to center unless otherwise noted.
3. 30° wing wall flare shown; 45° normally desirable. See Hydraulics and Utility and Railroad Engineering Sections.

PIPE	DIMENSIONS			QUANTITIES		
	ID	L	E	F (Approx)	CY Concrete	Reinf Steel Lbs
18"	2'-0"	1'-0"	1'-9"	0.97	0.96	65
24"	2'-0"	1'-0"	1'-9"	1.11	1.07	78
30"	3'-0"	1'-6"	2'-7"	1.50	1.44	108
36"	4'-0"	2'-0"	3'-6"	2.08	2.01	150
42"	5'-0"	2'-6"	4'-4"	2.71	2.63	205
48"	6'-0"	3'-0"	5'-2"	3.39	3.30	270
54"	7'-0"	3'-6"	6'-1"	4.14	4.02	335
60"	8'-0"	4'-0"	6'-11"	4.96	4.80	410

DESIGN APPROVED	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION	IRRIGATION HEADWALLS 18" TO 60" DIAMETER PIPES	DRAWING NO. C-16.10

REVISION NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	7/94		





## GENERAL NOTES

- All concrete shall be Class B.
- All reinforcing bars shall be #4 except two #6 bars over pipe. Bar spacing approximately 1'-0" center to center unless otherwise noted.
- 30° wing wall flare shown; 45° normally desirable. See Hydraulics and Utility and Railroad Engineering Divisions.



PIPE	DIMENSIONS			QUANTITIES		
	ID	L	E	CY Concrete		Reinf Steel Lbs
			F (Approx)	CMP	RCP	
18"	2'-0"	1'-0"	1'-9"	0.97	0.96	65
24"	2'-0"	1'-0"	1'-9"	1.11	1.07	78
30"	3'-0"	1'-6"	2'-7"	1.50	1.44	108
36"	4'-0"	2'-0"	3'-6"	2.08	2.01	150
42"	5'-0"	2'-6"	4'-4"	2.71	2.63	205
48"	6'-0"	3'-0"	5'-2"	3.39	3.30	270
54"	7'-0"	3'-6"	6'-1"	4.14	4.02	335
60"	8'-0"	4'-0"	6'-11"	4.96	4.80	410

DESIGN APPROVED <i>Henry H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Donald H. Williams</i>	① IRRIGATION HEADWALLS 18" TO 60" DIAMETER PIPES	DRAWING NO. C-16.10







COVER  
IRRIGATION STANDPIPE NO. 1




LOCKING COVER  
IRRIGATION STANDPIPE NO. 2



SECTION C-C



SECTION D-D




BOLTED COVER FOR  
STANDPIPE NO. 2


- GENERAL NOTES
1. All concrete shall be Class B.
  2. Structural steel shall be in accordance with ASTM A36.
  3. All cover steel and exposed appurtenances shall be given one shop coat of No. 1 paint.
  4. Plans shall specify locked or bolted cover for standpipe No. 2.
  5. For specific details of a flush pavement or sidewalk installation, see Utility and Railroad Engineering Section.

DRAWING NO.  
C-16.20


NO.	REVISION	DESCRIPTION OF REVISIONS	DATE BY	DATE
1				
2				
3				
4				



PLAN




ELEVATION



SECTION


PRECAST IRRIGATION GATE  
For Open Ditch Installation  
TYPE 1




Concrete "T" or  
"L" to be Included  
with Valve.

Irrigation Valve Number of Valve  
Shall Correspond to the Size of  
Pipe in Inches, No 6 to No 20.

PART SECTION  
FLUSH IRRIGATION VALVE



ELEVATION



SECTION


IRRIGATION GATE  
For Standpipe Installation  
TYPE 2

TYPE 2 IRRIGATION GATE


For pipes 6" through 24". Gate and frame shall be  
galvanized iron. Type shown is for concrete pipe.  
For CMP, external steel adjustable bend shall be used  
in place of internal steel ring.

DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>[Signature]</i>	① IRRIGATION VALVE AND GATE	DRAWING NO. C-16.30


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REDESIGNED STD	PMB	7/94
2	ADDED NOTE	PMB	7/94
3			
4			




SLEEVE UNDER CROSSROAD




SLEEVE UNDER MAINLINE




SLEEVE UNDER RAMP




SLEEVE UNDER DRIVEWAYS AND PARKING AREAS



TYPICAL INSTALLATION



DUMBBELL WATERSTOP



DETAIL C  
SLEEVE TERMINATION  
AT ELEVATED ROADWAY


## GENERAL NOTES

1. Irrigation sleeves shall be installed in a trench condition. See Std C-13.15 and Std C-7.06.
  2. Bedding and backfill material shall be Class 2 Aggregate Base.
  3. Pipe installation shall conform to Section 501 of Standard Specifications.
  4. The Contractor shall imprint a 4" high letter "S" on the face of all curbs at sleeve locations. The width of the letter shall be 1/2" and shall penetrate the concrete surface 1/2".
  5. For non-continuous sleeves under crossroads, Std C-5.10 Type 'A-1' curb shall be required where median is irrigated. See plans for locations. Dumbell waterstop shall be at all expansion joints.
  6. Materials used for caps or plugs shall be as recommended by the pipe supplier and approved by the Engineer.
- \*\* Generally, sleeves shall be installed parallel to the roadway subgrade. Slope may vary in superelevated sections. Minimum slope nominal to drain.

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Ronald Williams</i>	① IRRIGATION SLEEVES	DRAWING NO. C-16.40


NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	ADDED NOTE	7/94	PHB
2	MODIFIED TABLE	7/94	PHB
3			
4			

6x6-W1.4xW1.4 Galvanized Wire Mesh Entirely Enclosing Rock Backfill Including Both Ends, Lace Laps with 2 Strands of #9 Galvanized Wire.




### PERSPECTIVE

Drawn for types 1 and 2, Type 3 Similar



### TYPE 3 BANK PROTECTION



### TYPE 1 AND 2 BANK PROTECTION

TYPE	H	TOP OF BANK PROTECTION ABOVE THE STREAM BED
3	0' to 2'	2' to 4'
1	0' to 3'	4' to 7'
2	0' to 6'	6' to 12'

### GENERAL NOTES

1. Rock shall be sound and durable, of rounded or angular shape and with a nominal diameter of 8" minimum and 12" maximum. Flat or needle shapes are not acceptable.
2. Wire mesh splice shall have a 6" minimum lap vertically and horizontally.

DESIGN APPROVED  
*Joseph Ottaviano*  
APPROVED FOR DISTRIBUTION  
*Ronald Williams*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS


BANK PROTECTION, RAIL  
TYPES 1, 2, 3

REV.  
7/94  
DRAWING NO.  
C-17.10




NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	REVISED NOTE	10/95	PHB
2	REVISED DETAIL	10/95	PHB
3			
4			


### HALF PLAN BRICK CONCRETE



### SECTION A-A




### SECTION BRICK MANHOLE NO. 1




### SECTION STANDARD BASE STRUCTURE FOR PIPES 6" TO 36" I.D.


### HALF PLAN FOR PIPES 36" I.D. AND SMALLER




### HALF PLAN FOR PIPES OVER 36" I.D.



### SECTION STANDARD BASE STRUCTURE FOR PIPES OVER 36" I.D.



### SECTION MANHOLE NO. 3 PRECAST REINFORCED CONCRETE



### PART SECTION B-B


### GENERAL NOTES

1. Precast Manholes shall conform to the requirements of AASHTO M199 except that the compressive strength of each unit will be determined and accepted in accordance with Section 1006.7 of the ADOT Specifications.
2. Concrete for all other manholes shall be Class B.
3. Every fifth course of bricks in Manhole No. 1 shall be laid as stretchers.
4. See Std C-18.30 and C-18.40 for additional information and dimensions.
5. See plans for Std C-18.20 frame and cover type.
6. Steps shall be placed in manholes in accordance with the requirements of AASHTO M199.
7. See Std C-18.40 for location of Station Location Reference Point.
8. Manhole height, 'H', shall be measured from the lowest pipe invert to the top of the manhole frame.


DESIGN APPROVED <i>Joseph H. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald Williams</i>	MANHOLE DETAILS	DRAWING NO. C-18.10

NO.	DESCRIPTION OF REVISION	DATE
1	REVISED NOTE	7/94
2	ADDED NOTE	7/94
3		


# HALF PLAN BRICK CONCRETE



## SECTION A-A




## SECTION BRICK MANHOLE NO. 1 CONCRETE MANHOLE NO. 2




## SECTION STANDARD BASE STRUCTURE FOR PIPES 6" TO 36" I.D.


# HALF PLAN FOR PIPES 36" I.D. AND SMALLER




## HALF PLAN FOR PIPES OVER 36" I.D.



## SECTION STANDARD BASE STRUCTURE FOR PIPES OVER 36" I.D.



## HALF SECTION MANHOLE NO. 3 PRECAST REINFORCED CONCRETE



## PART SECTION B-B

## GENERAL NOTES

1. Precast Manholes shall conform to the requirements of AASHTO M199 except that the compressive strength of each unit will be determined and accepted in accordance with Section 1006.7 of the ADOT Specifications.
2. Concrete for all other manholes shall be Class B.
3. Every fifth course of bricks in Manhole No. 1 shall be laid as stretchers.
4. See Std C-18.30 for additional information and dimensions.
5. See plans for Std C-18.20 frame and cover type.
6. Steps shall be placed in manholes in accordance with the requirements of AASHTO M199.
7. See Std C-18.40 for location of Station Location Reference Point.
8. Manhole height, "H", shall be measured from the lowest pipe invert to the top of the manhole frame.


DESIGN APPROVED <i>Joseph Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Franklin</i>	MANHOLE DETAILS	DRAWING NO. C-18.10




REV.	DESCRIPTION OF REVISION	MADE BY	DATE
1	REVISED DETAIL	PHB	10/95
2	REVISED SECTION	PHB	10/95
3	REVISED GENERAL NOTE	PHB	10/95

## GENERAL NOTES


- When specified on the plans, the cover (excluding grates) shall include agency identification and conform to the following: Lettering on manhole cover to contain name of agency and utility as directed. Letters and words to be equally spaced. Letters to be 2" in height and raised  $\frac{1}{8}$ " above level of cover. Type of letters and layout to be submitted for approval.
- Casting weights shown are minimum weights and are for either cast iron or ductile iron castings. Maximum casting weights shall not exceed 105 percent of weights shown.
- H20 loading minimum.
- Details shown are typical.
- Alternate designs of manhole frame and cover may be utilized with the approval of the engineer as long as minimum loading and weight are equivalent.




BOTTOM VIEW - TOP VIEW




BOTTOM VIEW




BOTTOM VIEW - TOP VIEW




BOTTOM VIEW ①





PLAN



SECTION OF FRAME  
24" MANHOLE FRAME & COVER  
Approx Wt: Frame 173 Lbs  
Cover 170 Lbs



SECTION OF FRAME  
30" MANHOLE FRAME & COVER  
Approx Wt: Frame 204 Lbs  
Cover 223 Lbs





SECTION C-C  
36" NOMINAL CMP FRAME & GRATE  
Approx Wt: Frame 125 Lbs  
Cover 167 Lbs

DESIGN APPROVED <i>Joseph H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED & SET FOR DISTRIBUTION <i>Ronald Williams</i>	MANHOLE FRAME AND COVER DETAILS	DRAWING NO. C-18-20



NO.	DESCRIPTION OF REVISIONS	NAME BY	DATE
1	REVISION STD	PHS	7/74
2			
3			
4			
5			

## GENERAL NOTES


- When Type A' cover (24" or 30") is specified on the plans then the cover shall include agency identification and conform to the following: Lettering on manhole cover to contain name of agency and utility or as directed. Letters and words to be equally spaced. Letters to be 2" in height and raised  $\frac{1}{8}$ " above level of cover. Type of letters and layout to be submitted for approval. Castings shall be painted or dipped in commercial quality asphaltum paint, unless otherwise specified.
- Weight of castings shall not be more than 2% less than the approximate weight specified.
- H20 loading minimum.
- Details shown are typical.
- Alternate designs of manhole frame and cover may be utilized with the approval of the engineer as long as minimum loading and weight are equivalent.



SECTION OF FRAME  
24" MANHOLE FRAME & COVER  
Approx Wt: Frame 205 Lbs  
Cover 200 Lbs




SECTION OF FRAME  
30" MANHOLE FRAME & COVER  
Approx Wt: Frame 224 Lbs  
Cover 324 Lbs



SECTION C-C  
36" CMP FRAME & GRATE  
Approx Wt: Frame and Cover = 330 Lbs


DESIGN APPROVED <i>Edward H. Thomas</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Robert Smith</i>	① MANHOLE FRAME AND COVER DETAILS	DRAWING NO. C-18-20






END VIEW


If Steps are Required  
 They shall Conform to  
 the Requirements of  
 AASHTO M199




SIDE VIEW



NORMAL INSTALLATION



SHALLOW INSTALLATION




Manhole Control Point  
 Med & Station Location

TOP VIEW


DESIGN APPROVED <i>Shirley H. Otterson</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>W. R. ...</i>	① MANHOLE RISER DETAILS	DRAWING NO. C-18.40

NO.	DESCRIPTION OF REVISIONS	WATER INT.	DATE
1	REARRANGED STD	PNB	7/94
2	REVISED NOTE	PNB	7/94
3	ADDED DETAIL	PNB	7/94
4			




CONCRETE SURFACE ROAD  
CONCRETE WALLS

\* Min Distance Below Stream Bed



BITUMINOUS SURFACE ROAD  
CONCRETE WALLS




DEPTH GAUGE DETAIL



③ JOINT DETAIL


1. Ford walls shall be Class B concrete.
2. Depth gauge tubing shall be protected against concrete entering through bottom or perforations.
3. Depth gauge tubing and both sides of numeral tabs shall be painted with two coats of white enamel. Numerals and markers shall be painted with one coat of gloss black enamel.



ELEVATION LOOKING UPSTREAM


DESIGN APPROVED <i>John H. Ottewill</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV.  7/54
APPROVED FOR DISTRIBUTION <i>Ronald Keith</i>	(1) FORD - CONCRETE WALLS	DRAWING NO. C-19.10

DATE	7/94
DESIGNED BY	FILE
CHECKED BY	FILE
APPROVED BY	FILE




WITH TREATED BASE

TYPE 1  
BITUMINOUS SURFACE ROAD



DETAIL A




Optional Rock Basket Down Stream from Cutoff Wall Detail A

3-2"x12" Planks  
4"x4"x5'-0" Post  
5' C to C

2-2"x12" Planks  
4"x4"x5'-0" Post  
5' C to C

40d Common Nails  
3 Per Board

Wall to be Built to One Foot Above High Water Level



ELEVATION - TYPE 2

TYPE 2  
BITUMINOUS SURFACE FORD  
TIMBER CUTOFF WALLS

## GENERAL NOTES

1. All timber shall be rough, pressure treated and unpainted.
2. Rock basket, full length of structure, shall be included only when called for on plans.
3. See plans for bituminous surface and base material details.
4. See Std C-19.10 for Depth Gauge details. Depth Gauge foundation may be utility concrete.

DESIGN APPROVED

*Joseph H. Ottewill*

APPROVED FOR DISTRIBUTION

*Ronald A. Wilson*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS


① FORD - TYPES 1 AND 2

REV.


7/94

DRAWING NO. C-19.20

NO.	DESCRIPTION OF REVISIONS	DATE
1	REARRANGED S.D.	7/78
2		
3		




PLAN





FRAME A

FRAME B




SURVEY MONUMENT  
FRAME AND COVER



COVER SECTION

1. A survey monument, frame and cover, complete in place shall be considered a unit.
2. A right of way marker, consisting of a survey monument and a reference marker complete in place shall be considered a unit.
3. All markers shall be placed as shown on the plans or as directed by the engineer.
4. Frames may be either Type A or Type B.
5. Frames shall weigh at least 53 pounds.
6. Covers shall weigh at least 16 pounds.
7. Portions of the frame and cover to be machined is shown by the symbol "f". The allowable tolerance for machined areas shall be  $\pm 1/64$ ". Concrete shall conform to the requirements of the specifications.
- 12" or pavement structure thickness, whichever is greater.




ELEVATION  
SURVEY MONUMENT

ELEVATION  
REFERENCE MARKER


RIGHT OF WAY MARKER

DESIGN APPROVED <i>Joseph H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Howard</i>	① SURVEY MONUMENT, FRAME AND COVER, RIGHT OF WAY MARKER	DRAWING NO. C-21.10

REVISIONS	DESCRIPTION & REVISIONS	DATE	BY
1	REVISED STATION TO DECIMAL PLACES	10/95	
2			
3			




PLAN



ELEVATION  
SURVEY MONUMENT


RIGHT OF WAY MARKER

ELEVATION  
REFERENCE MARKER



FRAME A



FRAME B



SURVEY MONUMENT  
FRAME AND COVER

# GENERAL NOTES

1. A survey monument, frame and cover, complete in place shall be considered a unit.
2. A right of way marker, consisting of a survey monument and a reference marker complete in place shall be considered a unit.
3. All markers shall be placed as shown on the plans or as directed by the engineer.
4. Frames may be either Type A or Type B.
5. Frames shall weigh at least 53 pounds.
6. Covers shall weigh at least 16 pounds.
7. Portions of the frame and cover to be machined is shown by the symbol "M". The allowable tolerance for machined areas shall be  $\pm 1/64$ ". Concrete shall conform to the requirements of the specifications.
8. 12" or pavement structure thickness, whichever is greater.



COVER SECTION

DESIGN APPROVED <i>Joseph H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR DISTRIBUTION <i>Ronald W. Williams</i>	SURVEY MONUMENT, FRAME AND COVER, RIGHT OF WAY MARKER	DRAWING NO. C-21.10



### GENERAL NOTES


1. Standard Marker may be used as bench, survey monument or R/W markers.
2. Standard Marker shall be made of brass, bronze or aluminum.
3. Standard Marker will be furnished by the Department. Cast-in lettering format may vary.
4. Bench Marks shall be established on headwalls, bridge curbs or other permanent structures.
5. Surfaces of Aluminum Markers in contact with concrete shall be epoxy coated.
6. Fluted shank may be straight or twisted.
7. Station, Elevation, Year, or other information shall be hand stamped in field, as approved by the Engineer.

DESIGN APPROVED <i>Larry H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV.  7/94
APPROVED FOR PUBLICATION <i>W. S. Kellum</i>	① STANDARD MARKER	DRAWING NO. C-21-20


NO.	REVISION OR REMARKS	DATE
1	REARRANGED STD	7/94
2		
3		
4		

# GENERAL NOTES


1. All concrete shall be Class B.



FOR SINGLE INSTALLATION	
QUANTITIES PER FT OF SLAB LENGTH	
CONCRETE	REINFORCING STEEL
0.31 CY	35.22 Lbs



SECTION A-A




CROSS SECTION


DESIGN APPROVED <i>Henry H. Ottman</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>[Signature]</i>	① UTILITY LINE, PROTECTIVE CONCRETE SLAB	DRAWING NO. C-22.10





NO.	REVISION NOTE	DATE	BY
1	REVISED NOTE	7/94	
2			
3			
4			



TYPE A ENCASEMENT



TYPE B ENCASEMENT




## GENERAL NOTES


1. Type A encasement to be used for sewer laterals or house connections BELOW water lines.
2. Type B encasement to be used for sewer laterals or house connections ABOVE water lines.
3. The encasement shall extend at least 6' on each side of the water line and must include the nearest joint.
- ④ 4. Protection for Type A required when distance from bottom of water to top of sewer line is 24" or less. When the sewer is a 4" or 6" house connection no protection is required if distance is more than 12".
5. For Type A crossings, Class 150 C.I.P. or ductile iron pipe may be used as an alternate. For Type B crossing reinforced encasement is always required.

DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Donald W. Miller</i>	SANITARY SEWER ENCASEMENT	DRAWING NO. C-22.15


NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	ADDED GENERAL NOTE	PMB	10/95
2	ADDED REBAR TO VIEW	PMB	10/95
3			
4			




TYPE A



TYPE B



SECTION A-A



SECTION B-B

## GENERAL NOTES

- Type A pipe support may be used for any Type crossing condition.
- Type C pipe support may be used for crossing pipes with a bell diameter of 18" or less if sufficient clearance over storm sewer is available and total span is less than 34'.
- Intermediate pipe support shall be used in conjunction with Type C pipe support if total span exceeds max. W in table.
- The contractor shall be responsible for furnishing all supports both permanent and temporary. Temporary supports shall not be a separate pay item.
- Permanent pipe supports may be decreased from plan quantities or extended to include some listed below as temporary supports if conditions warrant these changes at the time of construction. Decision shall be made by the engineer.
- When Type A pipe support is used and whenever so directed by the engineer, the contractor shall pierce the wall with suitable openings to prevent unequal pressure resulting from flooding of the backfill. The volume of the pierced opening shall not exceed  $\frac{1}{2}$  the volume of the supporting wall.
- Use Type B pipe support instead of Type C when clearance between pipes is less than Y in table.
- Concrete cover for reinforcing steel shall be 3", minimum.





①

SCHEDULE OF REQUIRED SUPPORTS		
PERMANENT	TEMPORARY	
Sewer Lines	Cast Iron Pipe	Conc Storm Drain
	Conc Irrig Pipe	Conc Box Culvert
	Buried Telco	Traffic Control Conduit
	Gas Pipes	Water and Sewer Lines

NOTE:  
Other utilities as noted on the plans or as required by the engineer at time of construction.

DESIGN APPROVED <i>Henry H. Ott</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV 10/95
APPROVED FOR CONSTRUCTION <i>David H. Williams</i>	PIPE SUPPORT ACROSS TRENCHES	DRAWING NO. C-22.20 Sheet 1 of 3

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED REINFORCEMENT	PHB	7/94
2	REARRANGED STD	PHB	7/94
3			
4			



## GENERAL NOTES

1. Type A pipe support may be used for any type crossing condition.
2. Type C pipe support may be used for crossing pipes with a bell diameter of 18" or less if sufficient clearance over storm sewer is available and total span is less than 34'.
3. Intermediate pipe support shall be used in conjunction with Type C pipe support if total span exceeds max. W in table.
4. The contractor shall be responsible for furnishing all supports both permanent and temporary. Temporary supports shall not be a separate pay item.
5. Permanent pipe supports may be decreased from plan quantities or extended to include some listed below as temporary supports if conditions warrant these changes at the time of construction. Decision shall be made by the engineer.
6. When Type A pipe support is used and whenever so directed by the engineer, the contractor shall pierce the wall with suitable openings to prevent unequal pressure resulting from flooding of the backfill. The volume of the pierced opening shall not exceed  $\frac{1}{2}$  the volume of the supporting wall.
7. Use Type B pipe support instead of Type C when clearance between pipes is less than Y in table.

## SCHEDULE OF REQUIRED SUPPORTS


PERMANENT	TEMPORARY	
Sewer Lines	Cast Iron Pipe	Conc Storm Drain
	Conc Irrig Pipe	Conc Box Culvert
	Buried Teico	Traffic Control Conduit
	Gas Pipes	Water and Sewer Lines

NOTES:  
Other utilities as noted on the plans or as required by the engineer at time of construction.


DESIGN APPROVED <i>Henry H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTE ON <i>Radcliffe</i>	PIPE SUPPORT ACROSS TRENCHES	DRAWING NO. C-22.20 Sheet 1 of 1

NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	REVISED REBAR CLEARANCE	PMB	10/95
2			
3			


TABLE					
DEPTH OF COVER ON SUPPORTS					
W	0' TO 8'		8' TO 16'		Y
	BAR NO.	Y	BAR NO.	Y	
TO 6'	5	8"	6	11"	
7'	5	9"	6	12"	
8'	5	10"	6	13"	
9'	6	11"	6	14"	
10'	6	12"	7	15"	
11'	6	13"	7	16"	
12'	6	14"	7	17"	
13'	7	15"	7	19"	
14'	7	16"	8	20"	
15'	7	17"	8	21"	
16'	7	18"			
17'	8	19"			




SECTION C-C




INTERMEDIATE SUPPORT FOR  
TYPE B CROSSINGS



SECTION D-D



TYPE C




PLAN FOR TYPE B SUPPORT


DESIGN APPROVED <i>Larry Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 10/95
APPROVED FOR CONSTRUCTION <i>Ronald L. Brown</i>	PIPE SUPPORT ACROSS TRENCHES	DRAWING NO. C-22.20 Sheet 2 of 3

NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REARRANGED STD	PMB	7/94
2			
3			


TABLE				
'W'	DEPTH OF COVER ON SUPPORTS			
	0' TO 8'		8' TO 16'	
	BAR NO.	Y	BAR NO.	Y
TO 6'	5	8"	6	11"
7'	5	9"	6	12"
8'	5	10"	6	13"
9'	6	11"	6	14"
10'	6	12"	7	15"
11'	6	13"	7	16"
12'	6	14"	7	17"
13'	7	15"	7	19"
14'	7	16"	8	20"
15'	7	17"	8	21"
16'	7	18"		
17'	8	19"		




SECTION C-C




SECTION D-D



PLAN FOR TYPE B SUPPORT





INTERMEDIATE SUPPORT FOR  
TYPE B CROSSINGS



TYPE C




REV	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISION TO	PHB	7/94
2			
3			




ALTERNATE TO PIPE SUPPORT

DESIGN APPROVED <i>Joseph H. Ottomano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>R. S. Hall</i>	① PIPE SUPPORT ACROSS TRENCHES	DRAWING NO. C-22.20 Sheet 3 of 3



NO.	DESCRIPTION OF REVISIONS	DATE
1	REARRANGED STD	7/94
2		
3		



TYPE B TOP




TYPE A TOP  
Pre-Cast Eccentric  
Conical Top Manhole



PRECAST SEWER MANHOLE


## GENERAL NOTES

1. Pre-cast, reinforced manhole sections shall be manufactured in accordance with AASHTO M199 except that the compressive strength of each unit will be determined and accepted in accordance with section 1006.7 of the specifications.
2. Manhole steps shall be installed at the site of the manhole section manufacture in accordance with industry standards meeting AASHTO M199 requirements. Steps not required in 60" manhole.
3. Use low alkali cement only.
4. Pipe sizes and elevation shown on plans.
5. Frame and cover shall be adjusted to the finished grade prior to placing of the asphaltic concrete or PCCP surface.




DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>David Hall</i>	① PRECAST SANITARY SEWER MANHOLES	DRAWING NO. C-22.25


NO.	DESCRIPTION OF REVISIONS	DATE BY	DATE
1	REARRANGED LTO	PHD	7/94
2			
3			




TYPICAL STUB OUT



PIPE PLUG MARKER



STORM DRAIN LINE PLUG




SEWER LINE PLUG

## GENERAL NOTES


1. Compact soil at end of pipe to 95% of maximum density.
2. If depth of cover is less than 5' or greater than 10', increase plug thickness a minimum of 4'.

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Donald H. Ottum</i>	① STUB OUT AND PLUG	DRAWING NO. C-22.30

NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	REVISION	7/94	
2			
3			
4			




TYPE A  
2.5' TO 5' DROP



TYPE B  
5' OR MORE DROP

DESIGN APPROVED <i>Jerry J. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>[Signature]</i>	① DROP SEWER CONNECTIONS	DRAWING NO. C-22.35

NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	REVISED STD	PHB	7/94
2			
3			
4			





CLEANOUT INSTALLATION


DESIGN APPROVED <i>David L. Ottewill</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>David L. Ottewill</i>	① SEWER CLEANOUT	DRAWING NO. C-22.40

NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	REARRANGED STD	PMB	7/94
2			
3			
4			






Area required  
for 90° Bend



1/2 Area Required  
for 90° Bend



Total Area Equals  
Area Required for Tee



SECTION A-A

## GENERAL NOTES

1. Thrust blocks are to extend to undisturbed ground.
2. All concrete shall be class B.
3. Table is based on 3000#/sq. ft. soil, if conditions are found to indicate soil bearing less, the areas shall be increased accordingly.
4. Areas for pipe larger than 16" shall be calculated for each project.
5. Form all non bearing vertical surfaces.

## MINIMUM THRUST BLOCK AREA REQUIRED (Y x W)

PIPE SIZE	WATER PIPE	
	TEE, DEAD END, 90° BEND	45° & 22½° BENDS
4" & LESS	3 SQ. FEET	3 SQ. FEET
6"	4 " "	3 " "
8"	6 " "	3 " "
10"	9 " "	5 " "
12"	13 " "	7 " "
16"	23 " "	12 " "

DESIGN APPROVED

*Henry H. Ottens*

APPROVED FOR  
DISTRIBUTION

*Ronald Smith*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV.


7/94

① THRUST BLOCKS FOR WATER LINES


DRAWING NO.

C-23,10


NO.	DESCRIPTION OF REVISION	DATE
1	REWORKED SITE	7/94
2		
3		
4		
5		




PLAN




ELEVATION




SECTION A-A  
GATE VALVE



PLAN



ELEVATION



SECTION B-B  
BUTTERFLY VALVE

## GENERAL NOTES

- Gate valves 4\" to 16\" may be used with any type of pipe.
- Gate valves larger than 16\" to be detailed on plans.
- Butterfly valves 3\" to 12\" may be used with any type of pipe.
- Butterfly valves larger than 12\" to be detailed on plans.
- Valve box and cover required per Std C-23.30.

DESIGN APPROVED

*Joseph Ottaviano*  
APPROVED FOR  
DISTRIBUTION  
*Joseph Ottaviano*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV  
7/94


① BLOCKING FOR WATER VALVES  
GATE AND BUTTERFLY

DRAWING NO.  
C-23.15

NO.	DESCRIPTION OF REVISION	DATE	BY
1	REDESIGNED STD	1/78	
2			
3			
4			

## GENERAL NOTES

1. Either this detail or restraint rods may be used when allowed to relocate a water line upward to cross over a conflict.
2. Ductile iron pipe may be used.
3. Anchor blocks for pipe larger than 12" shall be calculated for each project.
4. Reinforcing bars to be coated with 2 coats of coal tar, epoxy, or by other approved methods.




PIPE SIZE	MINIMUM BAR SIZE	A-DIMENSION (HOOK)	MINIMUM * BLOCK DIMENSION
6"	#6	6"	3'x3'x3'
8"	#6	9"	4'x4'x2.5'
12"	#8	9"	4'x5'x5'

\* For 125 psi Working Pressure


DESIGN APPROVED <i>Joseph H. Ottensm</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Paul J. Sullivan</i>	① ANCHOR BLOCK FOR VERTICAL BENDS	DRAWING NO. C-23.20




NO.	DESCRIPTION OF REVISIONS	DATE
1	REARRANGED STD	7/94
2		
3		
4		



CAST IRON



ASBESTOS CEMENT




CAST IRON  
MECHANICAL JOINT

## GENERAL NOTES


1. This detail covers moving of water mains, 2' to 12' only.
2. Thrust blocking per Std C-23.10 and C-23.20.
3. If offset is to go over obstruction, joint restraints must be used.
4. Pipe is to be cast iron or ductile iron.
5. 45° cast iron bends may be used in place of cast iron offsets.
6. Drop section is to be prefabricated and installed as a single unit for cast iron mechanical joints.

DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>Robert H. H. H.</i>	① VERTICAL REALIGNMENT OF WATER MAINS	DRAWING NO. C-23.25

NO	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REVISED GENERAL NOTE	PMB	10/95
2			
3			
4			
5			



TYPE A-1  
TO BE USED IN AREAS SUBJECT TO VEHICULAR TRAFFIC




DETAIL A

### GENERAL NOTES


1. Extension to valve stems required on all valves where operating nut is over 5' below surface. Extension stem shall be 1/4" minimum diameter steel designation A-15, with square socket on bottom to fit 2" square valve nut. Length to fit each installation, 2" square operating nut to be held on top of the extension stem with stop nut.
2. If two or more joints of ACP are used to make riser, use standard AC pipe rubber gasket coupling to join pipe. Where riser pipe length exceeds 10', use 12" AC pipe.
- ① 3. All steel to have prime coat of paint No. 4 and one heavy application (finish coat) of Light Grey Enamel paint as per section 1002-4.06.
4. Valve box shall be adjusted to the finished grade prior to the placing of the asphaltic concrete surface or PCCP.
5. Ground below the concrete pad or three bricks to be compacted to 95% of the maximum density.
6. Use Parkson, Tyler Apco, or equal deep skirted cover (4" or more) type, sliding adjustable cast iron valve box, Cl minimum TS 30,000 psi.

DESIGN APPROVED <i>Sam J. Ottman</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV.  10/95
APPROVED FOR CONSTRUCTION <i>Frank R. [Signature]</i>	VALVE BOX INSTALLATION	DRAWING NO. C-2330 Sheet 1 of 2

NO.	DESCRIPTION OF REVISIONS	SHEET NO.
1	REARRANGED STD	1/24
2	NOTE FROM SHEET 2 OF 3	1/24
3		1/24
4		1/24



**TYPE A-1**  
TO BE USED IN AREAS SUBJECT TO VEHICULAR TRAFFIC




**DETAIL A**

## GENERAL NOTES


1. Extension to valve stems required on all valves where operating nut is over 5' below surface. Extension stem shall be 1/4" minimum diameter steel designation A-15, with square socket on bottom to fit 2" square valve nut. Length to fit each installation. 2" square operating nut to be held on top of the extension stem with stop nut.
2. If two or more joints of ACP are used to make riser, use standard AC pipe rubber gasket coupling to join pipe. Where riser pipe length exceeds 10', use 12" AC pipe.
3. All steel to have prime coat of paint No. 4 and one heavy application (finish coat) of paint No. 10092-4.06 as per section 1002.
4. Valve box shall be adjusted to the finished grade prior to the placing of the asphaltic concrete surface or PCCP.
5. Ground below the concrete pad or three bricks to be compacted to 95% of the maximum density.
6. Use Parkson, Tyler Apco, or equal deep skirted cover (4' or more) type, sliding adjustable cast iron valve box, CI minimum TS 30,000 psi.

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Robert L. Brown</i>	① VALVE BOX INSTALLATION	DRAWING NO. C-23.30 Sheet 1 of 2


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	MOVED NOTE TO SHEET 1	PHB	7/94
2	REARRANGED STD	PHB	7/94
3			
4			



**TYPE A-2**  
TO BE USED WHEN VALVE BOX IS LOCATED WITHIN PCCP PAVEMENT




**TYPE B**  
NOT SUBJECT TO VEHICULAR TRAFFIC




**TYPE C**

DESIGN APPROVED <i>Henry A. Othman</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Donald Williams</i>	VALVE BOX INSTALLATION	DRAWING NO. C-23,30 Sheet 2 of 2

NO.	DESCRIPTION OF REVISION	DATE	BY
1	REARRANGED STD. TAP. NOTES	7/94	
2			
3			
4			



PLAN



ELEVATION

## GENERAL NOTES

1. Thrust blocks are to extend to undisturbed ground.
2. Optional blocking of 2"x8"x12" solid concrete masonry units may be used as indicated.
3. All concrete shall be class B normally, cure 24 hours before backfilling, or use high, early strength concrete.
4. All taps shall be made by city crews at prevailing rates.
5. Install permanent blocking under valve before tap is made. All flange bolts shall be clear of footing.
6. All tapping sleeves must be pressure tested prior to request for tap by city.
7. Contractor shall excavate as shown and shall set tapping sleeve and valve, and tighten all bolts prior to requesting city to make tap.
8. Tapping sleeve to be placed a minimum of 18" from any bell, coupling, valve, or other obstruction.
9. Areas for pipe larger than 16" shall be calculated for each project.

SIZE OF PIPE BEING CONNECTED	MINIMUM THRUST AREA REQUIRED EQUALS (A x B)
4" & LESS	3 SQUARE FEET
6"	4 SQUARE FEET
8"	6 SQUARE FEET
10"	9 SQUARE FEET
12"	13 SQUARE FEET
16"	23 SQUARE FEET

DESIGN APPROVED <i>[Signature]</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>[Signature]</i>	① TAPPING SLEEVE AND VALVE INSTALLATION	DRAWING NO. C-23.35

REVISION	DESCRIPTION OF REVISION	DATE
1	REVISED SPECIFICATION CALLOUT	10/95
2		
3		

## GENERAL NOTES

1. This detail is for use only on underground installations where the use of concrete thrust blocking per Std C-23.10 cannot be used because of obstructions, or requirements of the specifications.
2. Washers may be cast iron or steel, and may be round or square. Holes shall be  $\frac{1}{8}$  inch larger than the rods.
3. All tie rods, rod couplings, turnbuckles, bolts and nuts for these joints shall be of carbon steel equivalent to ASTM A-307, grade B, with cadmium plating in accordance with ASTM B 766, except that the minimum thickness of the plating shall be .0002 of an inch. Cadmium plated bolts shall have class 2A threads and the nuts, rod couplings and turnbuckles shall have 2B threads.
4. High strength, heat treated cast iron tee-head bolts with hexagon nuts, all in accordance with the strength requirements of AWWA C-111, may be used in lieu of the cadmium plated bolts and nuts.
5. The sketches in this series of figures show acceptable methods of providing anchorage. There is no particular significance to be attached to whether the sketch shows a bell and spigot joint or a standard mechanical joint. The anchoring procedure illustrated applies in most cases to either type of joint. In some cases, dimensions of the particular pipe or hub and space available for working around the particular joint will influence the choice of methods used.
6. In certain assemblies of rod and clamps shown, rods run from a lug on the fitting (or a clamp behind the hub of a bell) to a clamp against a face of a bell. Note that this arrangement anchors only one joint. The stability of the joint where the clamp is against the face of the bell depends on having soil above a relatively long piece of pipe on both sides of the joint. Consequently, if the distance between the first and the second joint is less than 12 feet, the second joint shown shall be anchored by a clamp behind the hub of the bell and rods to a clamp at the face of the next bell.
7. For pipe larger than 12 inch diameter, restraint details shall be submitted for approval prior to installation.
8. All exposed metal shall be coated with asphaltic primer per subsection 907-2.02.
9. Bolt holes in clamps shall be  $\frac{1}{8}$  inch larger than the bolts.

## CLAMP DETAIL

NOTE:  
Rods are attached to lugs cast on bell of hydrant. If hydrant is not fitted with lugs, rods are attached as shown below by the dashed line.

Hydrant Anchor

PIPE SIZE	A	B	C	D	CLAMP	ROD	BOLTS	WASHERS	
								CAST IRON	STEEL
4"	12 1/2"	10 1/8"	2 1/2"	1 3/4"	1/2" x 2"	3/4"	3/8"	3/8" x 3"	1/2" x 3"
6"	14 1/2"	12 1/8"	3 3/8"	2 1/4"	1/2" x 2"	3/4"	3/8"	3/8" x 3"	1/2" x 3"
8"	16 3/4"	14 3/8"	4 1/8"	3 3/8"	3/8" x 2 1/2"	3/4"	3/8"	3/8" x 3"	1/2" x 3"
10"	19 1/4"	16 1/8"	5 3/4"	5"	3/8" x 2 1/2"	7/8"	3/4"	3/8" x 3"	1/2" x 3"
12"	22 3/8"	19 3/8"	6 3/4"	5 1/8"	3/8" x 3"	7/8"	7/8"	3/4" x 3 1/2"	1/2" x 3 1/2"

DESIGN APPROVED

*Leahy H. Ottman*

APPROVED FOR

CONSTRUCTION

*Donald H. Williams*

STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

JOINT RESTRAINT WITH TIE RODS

REV.

10/95


DRAWING NO.

C-23.40

REVISION	DATE	BY	CHKD BY
1	7/54		
2			
3			
4			
5			
6			
7			
8			
9			
10			

## GENERAL NOTES

1. This detail is for use only on underground installations where the use of concrete thrust blocking per Std C-23.10 cannot be used because of obstructions, or requirements of the specifications.
2. Washers may be cast iron or steel, and may be round or square. Holes shall be  $\frac{1}{8}$  inch larger than the rods.
3. All tie rods, rod couplings, turnbuckles, bolts and nuts for these joints shall be of carbon steel equivalent to ASTM A-307, grade B, with cadmium plating in accordance with ASTM A-165, except that the minimum thickness of the plating shall be .0002 of an inch. Cadmium plated bolts shall have class 2A threads and the nuts, rod couplings and turnbuckles shall have 2B threads.
4. High strength, heat treated cast iron tee-head bolts with hexagon nuts, all in accordance with the strength requirements of AWWA C-111, may be used in lieu of the cadmium plated bolts and nuts.
5. The sketches in this series of figures show acceptable methods of providing anchorage. There is no particular significance to be attached to whether the sketch shows a bell and spigot joint or a standard mechanical joint. The anchoring procedure illustrated applies in most cases to either type of joint. In some cases, dimensions of the particular pipe or hub and space available for working around the particular joint will influence the choice of methods used.
6. In certain assemblies of rod and clamps shown, rods run from a lug on the fitting (or a clamp behind the hub of a bell) to a clamp against a face of a bell. Note that this arrangement anchors only one joint. The stability of the joint where the clamp is against the face of the bell depends on having soil above a relatively long piece of pipe on both sides of the joint. Consequently, if the distance between the first and the second joint is less than 12 feet, the second joint shown shall be anchored by a clamp behind the hub of the bell and rods to a clamp behind the face of the next bell.
7. For pipe larger than 12 inch diameter, restraint details shall be submitted for approval prior to installation.
8. All exposed metal shall be coated with asphaltic primer per subsection 907-2.02.
9. Bolt holes in clamps shall be  $\frac{1}{16}$  inch larger than the bolts.



CLAMP DETAIL

NOTE:  
Rods are attached to lugs cast on bell of hydrant. If hydrant is not fitted with lugs, rods are attached as shown below by the dashed line.

Hydrant Anchor

PIPE SIZE	A	B	C	D	CLAMP	ROD	BOLTS	WASHERS	
								CAST IRON	STEEL
4"	12 1/2"	10 1/8"	2 1/2"	1 3/4"	1/2" x 2"	3/4"	3/8"	3/8" x 3"	1/2" x 3"
6"	14 1/2"	12 1/8"	3 3/8"	2 3/8"	1/2" x 2"	3/4"	3/8"	3/8" x 3"	1/2" x 3"
8"	16 3/4"	14 3/8"	4 3/8"	3 3/8"	5/8" x 2 1/2"	3/4"	3/8"	3/8" x 3"	1/2" x 3"
10"	19 1/8"	16 1/8"	5 3/4"	5"	5/8" x 2 1/2"	1"	3/4"	3/8" x 3"	1/2" x 3"
12"	22 3/8"	19 3/8"	6 3/4"	5 3/8"	3/8" x 3"	1"	3/4"	3/4" x 3 1/2"	1/2" x 3 1/2"

DESIGN APPROVED

*Henry H. Ottensmeyer*

APPROVED FOR DISTRIBUTION

*Robert J. Miller*


STATE OF ARIZONA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
STANDARD DRAWINGS

REV.  
7/94


JOINT RESTRAINT WITH TIE RODS

DRAWING NO.  
C-23.40


NO.	DESCRIPTION OF REVISIONS	DATE	BY
1	REARRANGED STD	PMB	7/94
2			
3			
4			



PLAN



SECTION B-B



SECTION A-A

## GENERAL NOTES

1. The meter boxes shall conform to the dimensions as shown and shall be made of portland cement concrete poured and tamped (or vibrated) in true forms.
2. Use Class 5 concrete,  $f'_c=4000$  psi.

## METER BOX DIMENSIONS

	BOX NUMBER			
DIM.	1	2	3	4
A	19"	24 1/2"	29 1/2"	33 1/2"
B	12"	16 3/4"	18 1/2"	22 3/4"
C	11"	12"	13"	12"
D	14"	16"	23 3/4"	27 3/4"
E	16"	22"	26 1/2"	30 1/2"
F	9"	13 1/4"	15"	19 3/4"
G	7"	11 1/4"	12 3/4"	17"
H	9"	14 1/4"	15 1/2"	19 3/4"
I	6"	8 3/8"	9 1/4"	11 3/8"
J	1 1/2"	3/4"	1 3/4"	1 1/2"
K	3/4"	1 1/8"	1"	1"
L	1/4"	3/8"	3/8"	3/8"
M	16"	21"	25 1/2"	30 1/2"
N	2 1/2"	3 1/2"	4"	4"
	3/8" OR 3/4" METER	1" METER	1 1/2" METER	2" METER


DESIGN APPROVED <i>Joseph L. Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	SEC. 7/94
APPROVED FOR DISTRIBUTION <i>Joseph L. Ottaviano</i>	① CONCRETE WATER METER BOX	DRAWING NO. C-23.45




NO.	DESCRIPTION OF REVISION	MADE BY	DATE
1	REARRANGED STD	PHB	7/94
2			
3			

## GENERAL NOTES

1. All steel per section 1004-1 and 1004-2.




PERSPECTIVE




CORNER DETAIL



SECTION A-A



DETAIL 1




DETAIL 2

## SPECIFICATIONS


NO	A	B	C	D	STEEL PLATE BRACE	WEIGHT	MATERIAL
1	9"	15 1/8"	1 3/8"	None	None	None	5 1/4 Lbs. 14 Gauge
2	14 1/8"	21 3/4"	1 1/2"	6 1/2"	3/8" x 1 1/4" x 13 1/8"	Detail 1	12 3/4 Lbs. 12 Gauge
3	15 1/4"	26 1/4"	1 1/2"	8 1/4"	3/8" x 1 1/4" x 14 1/4"	Detail 1	19 1/4 Lbs. 12 Gauge
4	19 1/2"	30"	1 1/2"	7 1/8"	3/8" x 1 1/4" x 18 3/4"	Detail 2	33 Lbs. 11 Gauge

DESIGN APPROVED <i>Joseph H. Ottens</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>David C. Chaffin</i>	① STEEL COVER FOR WATER METER BOX	DRAWING NO. C-23.50


REVISION	DESCRIPTION OF REVISION	DATE	BY
1	REMOVED NOTE	7/94	
2			
3			



PLAN



SECTION A-A




ELEVATION

## GENERAL NOTES


1. Cut and plugs must be adequately 'dry blocked'.
2. Dry blocks shall be standard size solid masonry concrete blocks, (ASTM C-139).
3. The quantity and arrangement of the blocking must withstand the line pressure by holding the cap or plug in position.
- ① 4. Concrete thrust blocks shall not be poured until line pressure is restored and the cap or plug is inspected for leakage.
5. Concrete shall not be poured over any portion of the abandoned pipe.
6. Minimum thrust block area per Std C-23.10.
7. Where a 4" or larger line is specified to be abandoned, the cut and plug should occur at the supply line main to avoid creating an unused deadend line.

DESIGN APPROVED <i>James H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>Robert L. Williams</i>	WATERLINE CUT AND PLUG FOR 12" DIAMETER MAIN AND SMALLER	DRAWING NO. C-23.55


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REARRANGED STD	PHB	7/94
2			
3			
4			



PLAN



ELEVATION



ALTERNATE PLAN  
(SEE NOTE 3)

## GENERAL NOTES


1. All joints in hydrant run-out to be mechanical joints.
2. Hydrant Tee; Clow or approved equal may be used in place of Tee and 90° bend.
3. 90° bend not required if sufficient room for perpendicular installation.
4. See Std C-23.10 and C-23.15 for concrete thrust blocks.
5. A flange by mechanical joint shutoff valve, connecting directly to the Tee or below at the main shall be used.
6. Fire hydrant, fire hydrant threads, valve and valve boxes per municipality requirements.

DESIGN APPROVED <i>Joseph H. Ottum</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR CONSTRUCTION <i>David G. Smith</i>	① HYDRANT INSTALLATION	DRAWING NO. C-23.60


NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	REARRANGED L&D	PHB	7/94
2			
3			
4			

## GENERAL NOTES

- Obstructions such as utility poles, street signs, irrigation boxes, fences, etc., must not be placed between curb and hydrant.
- \* Radius varies by municipality.
- Dimensions shown on plans supersede locations shown on this detail.
- On locations in midblock, the fire hydrant will be aligned with a property line.



AREA WITH SIDEWALK



PARKWAY AREA OR NO SIDEWALK

DESIGN APPROVED <i>Joseph Ottaviano</i>	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV. 7/94
APPROVED FOR DISTRIBUTION <i>James A. Williams</i>	① FIRE HYDRANT LOCATIONS	DRAWING NO. C-23,65