



**NOTES:**

1. All materials and construction shall conform to the requirements of the Specifications.
2. Unstable soil may require deeper foundations. See specifications.
3. Mounting studs projection above foundation shall be 2" minimum.
4. Use an approved Silicon Sealer RTV Type Grey in color or clear, between cabinet and foundation.
5. Elevation of cabinet foundation shall be 4" above ground line.
6. 1" sleeve (for ground rod) shall be installed when foundation is poured per utility company requirements.
7. In unpaved areas a raised PCC pad 36" X 4" X width of foundation, shall be placed in front of the cabinet. Pad shall be set 2" below the foundation elevation. Slope pad away from cabinet. See pad detail, T.S. 2-1.
8. Contractor shall verify conduit placement, ground rod placement and mounting stud locations per manufacturer's requirements.
9. Conduit projection above foundation shall be 2" minimum.

DESIGN APPROVED	<b>SIGNATURE</b>	ARIZONA DEPT. OF TRANSPORTATION INTERMODAL TRANSPORTATION DIVISION TRAFFIC SIGNALS & LIGHTING STANDARD DRAWINGS	REV. 9/05
APPROVED FOR DISTRIBUTION		UPS FOUNDATION DETAIL	DRAWING NO. T.S. 2-7
<b>ON FILE</b>			