



NO.	DESCRIPTION OF REVISIONS	MADE BY	DATE
1	ADDED SHEET 2 OF 2	PARSONS BRINCKERHOFF	3/09
2			
3			
4			



NOTES:

- All materials and construction shall conform to the requirements of the Specifications.
- Pole shall comply with 1994 AASHTO loading requirements for Structural Supports for Highway Signs, Luminaires and Traffic Signals.
- Four 1 1/4" - 7 high strength bolts are required for signal mast arms ASTM A-325.
- See T.S.4-23 detail "B" for anchor bolt details. Each anchor bolt shall have four hex nuts and two flat washers, all to be furnished with pole.
- Anchor bolts shall project 4 1/2" above the foundation.
- Conduit shall project a minimum of 2" above the foundation. Maximum projection shall be 4".
- Block out for leveling nuts. See specs. for grout requirements.
- The foundation hole shall be augered and class "S" (3000 psi) concrete poured against undisturbed compacted earth.
- Unstable soil may require deeper foundation. See Specifications.
- A 25' coil of No. 4 AWG bare copper conductor shall be installed before the concrete is poured and connected to pole grounding screw in the hand hole.
- For inboard tenon, when specified, see tenon detail on T.S.9-1.
- All dimensions are nominal.



POLE BASE

MAST ARM INFORMATION				
	Nom. M.A. Length	Lum. M.A. Rise	"A" Min.	"B" Min.
LUMINAIRE	6'	2'-0"	3 3/8"	—
	8'	2'-6"	3 5/8"	—
	10'	3'-4"	3 7/8"	—
	12'	4'-3"	4 5/16"	—
	15'	4'-9"	4 3/4"	—
	18'	5'-9"	5 3/16"	—
SIGNAL	20'	5'-9"	5 1/4"	—
	45'	—	—	10 1/16"
	50'	—	—	10 3/4"
	55'	—	—	11 7/16"

FOUNDATION PLAN

PLAN SYMBOL

SHEET 1 OF 2
NOT TO SCALE

	DESIGN APPROVED	ARIZONA DEPARTMENT OF TRANSPORTATION INTERMODAL TRANSPORTATION DIVISION TRAFFIC SIGNALS & LIGHTING STANDARD DRAWINGS	REV. 3/09
	APPROVED FOR DISTRIBUTION	TYPE "R" POLE AND MAST ARMS	DRAWING NO. T.S. 4-11