



NOTES:

1. See Specifications for construction requirements.
2. For Cabinet Lock Details see T.S. 3-10.
3. The materials shall be cast aluminum or 10 gauge steel.
4. The door shall be raintight and dustproof.
5. Anchor bolts shall be 3/4" x 18" x 3" galvanized steel with 2 nuts, 2 washers, and shall be furnished with cabinet.
6. Anchor bolt projection above foundation shall be 1 3/4" min. and 2 1/4" max.
7. Conduit projection above foundation shall be 2" min and 4" max. See the plans for location and size of conduit.
8. Unstable soil may require deeper foundation, see Specifications.
9. Alternate foundations may be round and shall be 30" in diameter.
10. In unpaved areas a raised PCC pad 36" x 4" x width of foundation, shall be placed in front of cabinet. Pad shall be set 2" below the foundation elevation. Slope pad away from cabinet. See pad detail T.S. 2-1.
11. Ground Rod shall be 5/8" x 10" Bonded Copper.

DESIGN APPROVED <i>Charles Brown</i> 7/24/85	STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS STANDARD DRAWINGS	REV.
APPROVED FOR DISTRIBUTION <i>[Signature]</i>	TYPE I PEDESTAL CABINET AND FOUNDATION	DRAWING NO. T.S.3-8