ARIZONA DEPARTMENT OF TRANSPORTATION
INTERMODAL TRANSPORTATION DIVISION
CONTRACTS AND SPECIFICATIONS SECTION

BID SCHEDULE

CONTRACT # 2016049

TRACS No.	Project No.	Item	County	District	Gross Length	Net Length	Prepared By:
010 MA 112 H878701C	010-A-(226)T	11617	MARICOPA		8		Mahdi Ghalib

Highway Termini	Location	Work Description
• I-10	• SR 85 - VERRADO (WB)	• System Preservation (Restoration/Rehab/Resurface)

BID SCHEDULE

010 MA 112 H878701C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
2020042	REMOVAL OF PIPE (VARIES SIZES)	L.FT.	32		
2020053	REMOVE (END SECTION) (VARIES SIZES)	EACH	3		
2020081	REMOVE BITUMINOUS PAVEMENT (MILLING) (1")	SQ.YD.	504		
2020084	REMOVE BITUMINOUS PAVEMENT (MILLING) (2 1/2")	SQ.YD.	3,800		
2020085	REMOVE BITUMINOUS PAVEMENT (MILLING) (3")	SQ.YD.	24,550		
2020086	REMOVE BITUMINOUS PAVEMENT (MILLING) (3 1/2 ")	SQ.YD.	56,670		
2020162	REMOVE (BITUMINOUS PAVEMENT) (MILLING) (4 1/2")	SQ.YD.	56,670		
2030112	SHOULDER BUILD-UP (MILLED AC)	L.FT.	88,733		
2030113	SHOULDER BUILD-UP (COMPACTION)	HOUR	74		
2030902	BORROW (IN-PLACE)	CU.YD.	48		
4040111	BITUMINOUS TACK COAT	TON	90		
4040116	APPLY BITUMINOUS TACK COAT	HOUR	157		
4040127	FOG COAT (SS-1)	TON	20		
4040163	BLOTTER MATERIAL	TON	61		
4040282	ASPHALT BINDER (PG 76-16)	TON	1,300		

BID SCHEDULE

010 MA 112 H878701C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
4140040	ASPHALTIC CONCRETE FRICTION COURSE (ASPHALT-RUBBER)	TON	4,150		
4140042	ASPHALT RUBBER MATERIAL (FOR AR-ACFC)	TON	395		
4140044	MINERAL ADMIXTURE (FOR AR-ACFC)	TON	38	$90.00	$3,420.00
4160004	ASPHALTIC CONCRETE (3/4" MIX) (END PRODUCT) (SPECIAL MIX)	TON	26,000		
4160031	MINERAL ADMIXTURE	TON	245	$90.00	$22,050.00
5010017	PIPE, CORRUGATED METAL, 30"	L.FT.	2		
5010025	PIPE, CORRUGATED METAL, 36"	L.FT.	4		
5010035	PIPE, CORRUGATED METAL, 48"	L.FT.	26		
5014030	FLARED END SECTION, 30" (C-13.25)	EACH	1		
5014036	FLARED END SECTION, 36" (C-13.25)	EACH	2		
6010505	BRIDGE REPAIR (PENETRATING CRACK SEAL)	SQ.YD.	766		
7015052	OBLITERATE PAVEMENT MARKING (STRIPE)	L.FT.	4,500		
7016030	BARRICADE (TYPE II, VERT.PANEL, TUBULAR MARKER)	EACH-DAY	14,305		
7016031	BARRICADE (TYPE III, HIGH LEVEL FLAG TREES)	EACH-DAY	123		
7016032	PORTABLE SIGN STANDS (RIGID)	EACH-DAY	126		

BID SCHEDULE

010 MA 112 H878701C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7016033	PORTABLE SIGN STANDS (SPRING TYPE)	EACH-DAY	1,667		
7016035	WARNING LIGHTS (TYPE A)	EACH-DAY	2,192		
7016037	WARNING LIGHTS (TYPE C)	EACH-DAY	14,305		
7016038	TRAFFIC CONE (28 INCHES)	EACH-DAY	370		
7016039	EMBEDDED SIGN POST	EACH-DAY	1,130		
7016050	TRUCK MOUNTED ATTENUATOR	EACH-DAY	67		
7016051	TEMPORARY SIGN (LESS THAN 10 S.F.)	EACH-DAY	995		
7016052	TEMPORARY SIGN (10 S.F. OR MORE)	EACH-DAY	1,940		
7016061	FLASHING ARROW PANEL	EACH-DAY	42		
7016067	CHANGEABLE MESSAGE BOARD (CONTRACTOR FURNISHED)	EACH-DAY	558		
1 7016075	FLAGGING SERVICES (CIVILIAN)	HOUR	45		
1 7016078	FLAGGING SERVICES (LOCAL ENFORCEMENT OFFICER)	HOUR	30		
1 7016080	FLAGGING SERVICES (DPS)	HOUR	450	$65.26	$29,367.00
7040005	PAVEMENT MARKING (WHITE EXTRUDED THERMOPLASTIC) (0.090")	L.FT.	90,950		

BID SCHEDULE

010 MA 112 H878701C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7040006	PAVEMENT MARKING (YELLOW EXTRUDED THERMOPLASTIC) (0.090")	L.FT.	72,700		
7040072	PAVEMENT MARKING (TRANSVERSE) (THERMOPLASTIC) (ALKYD) (0.090")	L.FT.	1,200		
7040073	PAVEMENT LEGEND (EXTRUDED THERMOPLASTIC) (ALKYD) (0.090")	EACH	7		
7040074	PAVEMENT SYMBOL (EXTRUDED THERMOPLASTIC) (ALKYD) (0.090")	EACH	24		
7050047	PAVEMENT MARKING, PREFORMED, PATTERNED, WHITE STRIPE	L.FT.	37,500		
7060013	PAVEMENT MARKER, RAISED, TYPE C	EACH	2,040		
7060015	PAVEMENT MARKER, RAISED, TYPE D	EACH	38		
7060017	PAVEMENT MARKER, RAISED, TYPE E	EACH	2,060		
7060018	PAVEMENT MARKER, RAISED, TYPE G	EACH	44		
1 7080001	PERMANENT PAVEMENT MARKING (PAINTED) (WHITE)	L.FT.	157,600		
1 7080011	PERMANENT PAVEMENT MARKING (PAINTED) (YELLOW)	L.FT.	96,800		
7080111	PERMANENT PAVEMENT MARKING (PAINTED SYMBOL) (	EACH	1		

BID SCHEDULE

010 MA 112 H878701C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7080121	PERMANENT PAVEMENT MARKING (PAINTED SYMBOL) (ARROW)	EACH	24		
7080221	PERMANENT PAVEMENT MARKING (PAINTED LEGEND) (ONLY)	EACH	7		
7350006	LOOP DETECTOR (COUNTER) (FULL REPLACEMENT)	EACH	2		
7350023	LOOP DETECTOR (SPEED/CLASSIFICATION) (PARTIAL REPLACEMENT)	EACH	1		
8050003	SEEDING (CLASS II)	ACRE	13		
8101021	EROSION CONTROL (WATTLES) (9")	L.FT.	1,331		
9010001	MOBILIZATION	L.SUM	1		
9230002	CONTRACTOR BASED ON-THE-JOB TRAINING	HOUR	500	$3.00	$1,500.00
9240116	MISCELLANEOUS WORK (POLYMER MODIFIED ASPHALT-RUBBER CRACK SEALANT)	LB.	14,718		
9240170	CONTRACTOR QUALITY CONTROL	L.SUM	1		
9240181	MISCELLANEOUS WORK (CONTROL OF NOXIOUS PLANTS) (MANUAL/MECHANICAL METHODS)	SQ.YD.	23,662		
9240182	MISCELLANEOUS WORK (CONTROL OF NOXIOUS PLANTS) (HERBICIDE)	SQ.YD.	35,493		

BID SCHEDULE

010 MA 112 H878701C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
9250001	CONSTRUCTION SURVEYING AND LAYOUT	L.SUM	1		

BID TOTAL :